PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.05.04.20351.1, ETC.	30	12

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT
								MI	FT			TONS	SMI	TON	SY	TONS	TONS	TON	TONS
2026CPT.05.04.20351.1	Franklin	1	SR-1237 / BEASLEY RD	FROM SR 1235 TO US 401	1	2	2WD	3.442	20.5	0.000	3.442	171	6.85	633	1,225		3,006	201	114
TOTAL FOR MAP NO. 1								**3.442**				**171**	**6.85**	**633**	**1,225**		**3,006**	**201**	**114**
2026CPT.05.04.20351.1	Franklin	2	SR-1251 / SOLLIE AYSCUE RD	FROM SR 1003 TO SR 1253	2	2	2WD	0.820	20.5	0.000	0.820	41	1.64	152	142		860	56	
TOTAL FOR MAP NO. 2								**0.820**				**41**	**1.64**	**152**	**142**		**860**	**56**	
2026CPT.05.04.20351.1	Franklin	3	SR-1265 / FLETCHER FULLER RD	FROM SR 1003 TO SR 1253	2	2	2WD	0.270	20	0.000	0.270	14	0.54	50	112		277	18	
TOTAL FOR MAP NO. 3								**0.270**				**14**	**0.54**	**50**	**112**		**277**	**18**	
2026CPT.05.04.20351.1	Franklin	4	SR-1453 / RICKS RD	FROM NC 561 TO NC 561	4	2	2WD	0.590	15	0.000	0.590	30	1.18	109	211		378	31	134
TOTAL FOR MAP NO. 4								**0.590**				**30**	**1.18**	**109**	**211**		**378**	**31**	**134**
2026CPT.05.04.20351.1	Franklin	5	SR-1639 / DUKE MEMORIAL RD	FROM NASH CO TO NC 581	3	2	2WD	3.840	19	0.000	3.840	192	7.67	710	7,232	271	3,352	230	
TOTAL FOR MAP NO. 5								**3.840**				**192**	**7.67**	**710**	**7,232**	**271**	**3,352**	**230**	
2026CPT.05.04.20351.1	Franklin	6	SR-1642 / MITCHELL RD	FROM NC 581 TO DEAD END	2	2	2WD	0.790	19.5	0.000	0.790	40	1.58	146	121		788	51	
TOTAL FOR MAP NO. 6								**0.790**				**40**	**1.58**	**146**	**121**		**788**	**51**	
TOTAL FOR PROJ NO. 2026CPT.05.04.20351.1								**9.752**				**488**	**19.46**	**1,800**	**9,043**	**271**	**8,661**	**587**	**248**
2026CPT.05.04.20352.1	Franklin	7	SR-1224 / MAY RD	FROM NC 56 TO SR 1223	1	2	2WD	1.240	19.5	0.000	1.240	62	2.48	229	121		1,030	67	
TOTAL FOR MAP NO. 7								**1.240**				**62**	**2.48**	**229**	**121**		**1,030**	**67**	
2026CPT.05.04.20352.1	Franklin	8	SR-1252 / GOOCH RD	FROM NC-56 TO SR 1223	1	2	2WD	1.610	20	0.000	1.610	80	3.22	297	117		1,371	89	
TOTAL FOR MAP NO. 8								**1.610**				**80**	**3.22**	**297**	**117**		**1,371**	**89**	
2026CPT.05.04.20352.1	Franklin	9	SR-1445 / THOMAS JONES RD	FROM SR 1003 TO VANCE CO.	1	2	2WD	1.400	20	0.000	1.400	70	2.80	259	249		1,192	78	
TOTAL FOR MAP NO. 9								**1.400**				**70**	**2.80**	**259**	**249**		**1,192**	**78**	
TOTAL FOR PROJ NO. 2026CPT.05.04.20352.1								**4.250**				**212**	**8.50**	**785**	**487**		**3,593**	**234**	
GRAND TOTAL								**14.002**				**700**	**27.96**	**2,585**	**9,530**	**271**	**12,254**	**821**	**248**