

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	1	15

TOTAL SUMMARY OF QUANTITIES

ROUTE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
	LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H-SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
	HR	EA	EA	EA	EA	LF	LF	LF
NC-885/I-885	112	14	12	2	168	48		36
I-85	224	28	24	4	336	82		120
I-40	408	51	37	16	518	212	146	84
I-440	48	6	4	2	56	20		12
US-1	272	34	26	12	364	100	40	84
US-70	64	8	7	1	98	10		12
US64/US-264	152	19	19	1	266	20		24
US-15/US-501, Business US-15/US-501	72	9	9		126			24
NC-540/I-540	136	17	9	10	112	242		12
NC-147	120	15	11	6	154	46		24
TOTAL FOR PROJ NO. 50977.3.13	1,608	201	158	54	2,198	780	186	432
GRAND TOTAL	1,608	201	212		2,198	966		432

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	2	15

SUMMARY OF QUANTITIES

LOCATION REFERENCE NUMBER	COUNTY	EXIT NUMBER	ROUTE	DESCRIPTION	PAVEMENT TYPE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
						LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H-SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
						HR	EA	EA	EA	EA	LF	LF	LF
1	Durham/Wake	Exit 2	NC-885	NC-885 Toll Southbound at Davis Drive	Asphalt	8	1	1		14			
2	Durham/Wake	Exit 3	NC-885	NC-885 Toll Northbound at Davis Drive	Asphalt	8	1	1		14			
3	Durham/Wake	Exit 3	NC-885	NC-885 Toll Southbound at Hopson Road	Asphalt	8	1	1		14			
4	Durham/Wake	Exit 3	NC-885	NC-885 Toll Northbound at Hopson Road	Asphalt	8	1	1		14			
5	Durham	Exit 6	I-885	I-885 Southbound at E. Cornwallis Road	Asphalt	16	2	1	1	14	24		12
6	Durham	Exit 6	I-885	I-885 Northbound at E. Cornwallis Road	Asphalt	8	1	1		14			12
7	Durham	Exit 7	I-885	I-885 Southbound at TW Alexander Drive	Asphalt	8	1	1		14			
8	Durham	Exit 7	I-885	I-885 Northbound at TW Alexander Drive	Asphalt	8	1	1		14			12
9	Durham	Exit 8	I-885	I-885 Southbound at Ellis Road	Asphalt	8	1	1		14			
10	Durham	Exit 8	I-885	I-885 Northbound at Ellis Road	Asphalt	8	1	1		14			
11	Durham	Exit 12	I-885	I-885 Southbound at Cheek Road	Asphalt	16	2	1	1	14	24		
12	Durham	Exit 12	I-885	I-885 Northbound at Cheek Road	Asphalt	8	1	1		14			
TOTAL FOR NC-885/I-885						112	14	12	2	168	48		36
GRAND TOTAL						112	14	14		168	48		36

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	3	15

SUMMARY OF QUANTITIES

LOCATION REFERENCE NUMBER	COUNTY	EXIT NUMBER	ROUTE	DESCRIPTION	PAVEMENT TYPE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
						LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
						HR	EA	EA	EA	EA	LF	LF	LF
13	Durham	Exit 173	I-85	I-85 Northbound at Cole Mill Road	Asphalt	8	1	1		14			12
14	Durham	Exit 173	I-85	I-85 Southbound at Cole Mill Road	Asphalt	8	1	1		14			12
15	Durham	Exit 183	I-85	I-85 Southbound at Redwood Road	Asphalt	8	1	1		14			
16	Granville	Exit 186B	I-85	I-85 Northbound at US-15	Asphalt	8	1	1		14			12
17	Granville	Exit 189	I-85	I-85 Northbound at Gate Two Road	Asphalt	8	1	1		14			
18	Granville	Exit 189	I-85	I-85 Southbound at Gate Two Road	Asphalt	8	1	1		14			12
19	Granville	Exit 191	I-85	I-85 Northbound at Butner Creedmoor Road	Concrete	8	1	1		14			12
20	Granville	Exit 191	I-85	I-85 Southbound at Butner Creedmoor Road	Concrete	8	1	1		14			
21	Vance	Exit 214	I-85	I-85 Northbound at W Andrews Avenue	Asphalt	8	1	1		14			
22	Vance	Exit 214	I-85	I-85 Southbound at W Andrews Avenue	Asphalt	16	2	1	1	14	24		
23	Vance	Exit 215	I-85	I-85 Northbound at N Garnett St	Asphalt	16	2	1	1	14	20		12
24	Vance	Exit 215	I-85	I-85 Southbound at Parham Road	Asphalt	8	1	1		14			12
25	Vance	Exit 217	I-85	I-85 Northbound at Satterwhite Point Road	Asphalt	8	1	1		14			12
26	Vance	Exit 217	I-85	I-85 Southbound at Satterwhite Point Road	Asphalt	8	1	1		14			12
27	Vance	Exit 220	I-85	I-85 Northbound at Flemington Road/Highway One Road	Asphalt	16	2	1	1	14	16		
28	Vance	Exit 220	I-85	I-85 Southbound at Flemington Road/Highway One Road	Asphalt	16	2	1	1	14	22		12
29	Warren	Exit 223	I-85	I-85 Northbound at Manson-Drewry Road	Asphalt	8	1	1		14			
30	Warren	Exit 223	I-85	I-85 Southbound at Manson-Drewry Road	Asphalt	8	1	1		14			
31	Warren	Exit 226	I-85	I-85 Northbound at Ridgeway-Drewry Road	Asphalt	8	1	1		14			
32	Warren	Exit 226	I-85	I-85 Southbound at Ridgeway-Drewry Road	Asphalt	8	1	1		14			
33	Warren	Exit 229	I-85	I-85 Northbound at Oine Road	Asphalt	8	1	1		14			
34	Warren	Exit 229	I-85	I-85 Southbound at Oine Road	Asphalt	8	1	1		14			
35	Warren	Exit 233	I-85	I-85 Northbound at US-1	Asphalt	8	1	1		14			
36	Warren	Exit 233	I-85	I-85 Southbound at US-1	Asphalt	8	1	1		14			
TOTAL FOR I-85						224	28	24	4	336	82		120
GRAND TOTAL						224	28	28		336	82		120

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	4	15

SUMMARY OF QUANTITIES

LOCATION REFERENCE NUMBER	COUNTY	EXIT NUMBER	ROUTE	DESCRIPTION	PAVEMENT TYPE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
						LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H-SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
						HR	EA	EA	EA	EA	LF	LF	LF
37	Orange/Durham	Exit 270	I-40	I-40 Eastbound at Durham Chapel Hill Boulevard	Asphalt	8	1	1		14			12
38	Orange/Durham	Exit 270	I-40	I-40 Westbound at Durham Chapel Hill Boulevard	Asphalt	8	1	1		14			12
39	Durham	Exit 273	I-40	I-40 Westbound at W NC 54	Asphalt	16	2	2		28			
40	Durham	Exit 273A	I-40	I-40 Eastbound at W NC 54	Asphalt	8	1	1		14			12
41	Durham	Exit 274	I-40	I-40 Eastbound at NC 751	Asphalt	8	1	1		14			
42	Durham	Exit 274	I-40	I-40 Westbound at NC 751	Asphalt	8	1	1		14			12
43	Durham	Exit 276	I-40	I-40 Eastbound at Fayetteville Road	Asphalt	16	2	1	1	14			
44	Durham	Exit 276	I-40	I-40 Westbound at Fayetteville Road	Asphalt	16	2	1	1	14			
45	Durham	Exit 278	I-40	I-40 Eastbound at Apex Highway	Asphalt	16	2	1	1	14			
46	Durham	Exit 278	I-40	I-40 Westbound at Apex Highway	Asphalt	16	2	1	1	14			
47	Durham	Exit 280	I-40	I-40 Eastbound at Davis Drive	Asphalt	16	2	1	1	14	26		
48	Durham	Exit 280	I-40	I-40 Westbound at Davis Drive	Asphalt	16	2	1	1	14	24		12
49	Durham	Exit 281	I-40	I-40 Eastbound at Miami Boulevard	Asphalt	16	2	1	1	14		42	
50	Durham	Exit 281	I-40	I-40 Westbound at Miami Boulevard	Asphalt	16	2	1	1	14	30		
51	Durham	Exit 282	I-40	I-40 Eastbound at Page Road	Asphalt	16	2	1	1	14	38		
52	Durham	Exit 282	I-40	I-40 Westbound at Page Road	Asphalt	16	2	1	1	14	26		12
53	Wake	Exit 285	I-40	I-40 Eastbound at Aviation Parkway	Asphalt	8	1	1		14			
54	Wake	Exit 285	I-40	I-40 Westbound at Aviation Parkway	Asphalt	16	2	2		28			
55	Wake	Exit 287	I-40	I-40 Eastbound at Harrison Avenue	Asphalt	8	1	1		14			
56	Wake	Exit 287	I-40	I-40 Westbound at Harrison Avenue	Asphalt	8	1	1		14			
57	Wake	Exit 290	I-40	I-40 Eastbound at Chapel Hill Road	Asphalt	8	1	1		14			
58	Wake	Exit 290	I-40	I-40 Westbound at Chapel Hill Road	Asphalt	8	1	1		14			
59	Wake	Exit 295	I-40	I-40 Eastbound at Gorman Street	Asphalt	8	1	1		14			
60	Wake	Exit 295	I-40	I-40 Westbound at Gorman Street	Asphalt	8	1	1		14			
61	Wake	Exit 297	I-40	I-40 Eastbound at Lake Wheeler Road	Asphalt	8	1	1		14			
62	Wake	Exit 297	I-40	I-40 Westbound at Lake Wheeler Road	Asphalt	8	1	1		14			
63	Wake	Exit 298	I-40	I-40 Eastbound at Saunders Street	Asphalt	24	3	2	2	28		52	12
64	Wake	Exit 298	I-40	I-40 Westbound at Saunders Street	Asphalt	24	3	2	2	28		52	
65	Wake	Exit 299	I-40	I-40 Eastbound at Hammond Road	Asphalt	8	1	1		14			
66	Wake	Exit 299	I-40	I-40 Westbound at Hammond Road	Asphalt	8	1	1		14			
67	Wake	Exit 300A	I-40	I-40 Eastbound at Rock Quarry Road	Asphalt	16	2	1	1	14	34		
68	Wake	Exit 300A	I-40	I-40 Westbound at Rock Quarry Road	Asphalt	24	3	2	1	28	34		
TOTAL FOR I-40						408	51	37	16	518	212	146	84
GRAND TOTAL						408	51	53		518	358		84

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	5	15

SUMMARY OF QUANTITIES

LOCATION REFERENCE NUMBER	COUNTY	EXIT NUMBER	ROUTE	DESCRIPTION	PAVEMENT TYPE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
						LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H-SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
						HR	EA	EA	EA	EA	LF	LF	LF
69	Wake	Exit 12	I-440	I-440 Eastbound at Yonkers Road	Concrete	16	2	1	1	14	20		12
70	Wake	Exit 12	I-440	I-440 Westbound at Brentwood Road	Asphalt/Concrete	16	2	1	1	14			
71	Wake	Exit 15	I-440	I-440 Eastbound at Poole Rd	Asphalt	8	1	1		14			
72	Wake	Exit 15	I-440	I-440 Westbound at Poole Rd	Asphalt	8	1	1		14			
TOTAL FOR I-440						48	6	4	2	56	20		12
GRAND TOTAL						48	6	6		56	20		12

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	6	15

SUMMARY OF QUANTITIES

LOCATION REFERENCE NUMBER	COUNTY	EXIT NUMBER	ROUTE	DESCRIPTION	PAVEMENT TYPE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
						LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H-SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
						HR	EA	EA	EA	EA	LF	LF	LF
73	Wake	Exit 89	US-1	US-1 Northbound at New Hill Holleman Road	Asphalt	8	1	1		14			
74	Wake	Exit 89	US-1	US-1 Southbound at New Hill Holleman Road	Asphalt	8	1	1		14			
75	Wake	Exit 95	US-1	US-1 Northbound at E Williams Street	Asphalt	8	1	1		14			
76	Wake	Exit 95	US-1	US-1 Southbound at E Williams Street	Asphalt	8	1	1		14			
77	Wake	Exit 96	US-1	US-1 Northbound at Ten-Ten Road	Asphalt	16	2	1	1	14	30		
78	Wake	Exit 96	US-1	US-1 Southbound at Ten-Ten Road	Asphalt	16	2	1	1	14	34		
79	Wake	Exit 101	US-1	US-1 Northbound at Crossroads Blvd	Asphalt	8	1		2			40	
80	Wake	Exit 101A	US-1	US-1 Southbound at Walnut St	Asphalt	16	2	1	2	14			
81	Wake	Exit 101B	US-1	US-1 Southbound at Crossroads Blvd & Buck Jones Rd	Asphalt	8	1	1		14			
82	Wake	Exit 124	US-1	US-1 Northbound at NC-98	Asphalt	16	2	1	2	14			12
83	Wake	Exit 124	US-1	US-1 Southbound at NC-98	Asphalt	16	2	1	2	14			
84	Wake	Exit 125	US-1	US-1 Northbound at Durham Rd	Asphalt	8	1	1		14			
85	Wake	Exit 125	US-1	US-1 Southbound at Durham Rd	Asphalt	8	1	1		14			
86	Franklin	N/A	US-1	US-1 Northbound at NC-56 (W Green St)	Asphalt	8	1	1		14			12
87	Franklin	N/A	US-1	US-1 Southbound at NC-56 (W Green St)	Asphalt	8	1	1		14			12
88	Vance	N/A	US-1	US-1 Northbound at Bus 1 (Raleigh Rd)	Asphalt	8	1	1		14			
89	Vance	N/A	US-1	US-1 Southbound at Bus 1 (Raleigh Rd)	Asphalt								12
90	Vance	N/A	US-1	US-1 Northbound at Bear Pond Rd	Asphalt	8	1	1		14			
91	Vance	N/A	US-1	US-1 Southbound at Bear Pond Rd	Asphalt	8	1	1		14			
92	Vance	N/A	US-1	US-1 Northbound at Vanco Mill/Garrett Rd	Asphalt	8	1	1		14			12
93	Vance	N/A	US-1	US-1 Southbound at Vanco Mill Rd	Asphalt	8	1	1		14			
94	Vance	N/A	US-1	US-1 Northbound at E Andrews Ave	Asphalt	8	1	1		14			
95	Vance	N/A	US-1	US-1 Southbound at E Andrews Ave	Asphalt	8	1	1		14			
96	Vance	Exit 154	US-1	US-1 Northbound at Warrenton Road	Asphalt	16	2	1	1	14	18		
97	Vance	Exit 154	US-1	US-1 Southbound at Warrenton Road	Asphalt	16	2	1	1	14	18		
98	Vance	Exit 155A	US-1	US-1 Northbound at US 1 158 Highway North	Asphalt	8	1	1		14			12
99	Vance	Exit 155B	US-1	US-1 Northbound at US 1 158 Highway North	Asphalt	8	1	1		14			
100	Vance	Exit 155	US-1	US-1 Southbound at US 1 158 Highway North	Asphalt	8	1	1		14			12
TOTAL FOR US-1						272	34	26	12	364	100	40	84
GRAND TOTAL						272	34	38	364	140	84		

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	7	15

SUMMARY OF QUANTITIES

LOCATION REFERENCE NUMBER	COUNTY	EXIT NUMBER	ROUTE	DESCRIPTION	PAVEMENT TYPE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
						LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H-SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
						HR	EA	EA	EA	EA	LF	LF	LF
101	Wake	N/A	US-70	US-70 Eastbound at N Greenfield Parkway	Asphalt	8	1	1		14			
102	Wake	N/A	US-70	US-70 Westbound at N Greenfield Parkway	Asphalt	8	1	1		14			
103	Wake	N/A	US-70	US-70 Eastbound at Benson Road	Asphalt	8	1	1		14			12
104	Wake	N/A	US-70	US-70 Westbound at Umstead Lane	Asphalt	8	1	1		14			
105	Wake	N/A	US-70	US-70 Eastbound at Vandora Springs Road	Asphalt	8	1	1		14			
106	Wake	N/A	US-70	US-70 Westbound at Vandora Springs Road	Asphalt	16	2	1	1	14	10		
107	Wake	N/A	US-70/401	US-401/70 Northbound at W Peace St	Asphalt	8	1	1		14			
TOTAL FOR US-70						64	8	7	1	98	10		12
GRAND TOTAL						64	8	8		98	10		12

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	8	15

SUMMARY OF QUANTITIES

LOCATION REFERENCE NUMBER	COUNTY	EXIT NUMBER	ROUTE	DESCRIPTION	PAVEMENT TYPE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
						LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H-SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
						HR	EA	EA	EA	EA	LF	LF	LF
108	Wake	N/A	US-64	US-64 Eastbound at W Williams St	Asphalt	8	1	1		14			
109	Wake	N/A	US-64	US-64 Westbound at W Williams St	Asphalt	16	2	1	1	14	20		12
110	Wake	N/A	US-64	US-64 Eastbound at N Salem St	Asphalt	8	1	1		14			
111	Wake	N/A	US-64	US-64 Westbound at N Salem St/Davis Rd	Asphalt	8	1	1		14			
112	Wake	Exit 13	US-264	US-264 Westbound at Knighdale Boulevard	Asphalt	8	1	2		28			
113	Wake	Exit 14	US-264	US-264 Westbound at Rolesville Road	Asphalt	8	1	1		14			
114	Wake	Exit 432	US-264	US-264 Westbound at Lizard Lick Road	Asphalt	8	1	1		14			
115	Wake	Exit 432	US-264	US-264 Eastbound at Lizard Lick Road	Asphalt	8	1	1		14			
116	Wake	Exit 435	US-264	US-264 Westbound at N Arendell Drive	Asphalt	8	1	1		14			
117	Wake	Exit 435	US-264	US-264 Eastbound at N Arendell Drive	Asphalt	8	1	1		14			
118	Wake	Exit 2	US-264	US-264 Westbound at E Gannon Avenue	Asphalt	8	1	1		14			
119	Wake	Exit 2	US-264	US-264 Eastbound at E Gannon Avenue	Asphalt	8	1	1		14			12
120	Wake	Exit 3	US-264	US-264 Westbound at NC 39 Highway	Asphalt	8	1	1		14			
121	Wake	Exit 3	US-264	US-264 Eastbound at NC 39 Highway	Asphalt	8	1	1		14			
122	Franklin	Exit 439	US-64	US-64 Westbound at NC-39	Asphalt	8	1	1		14			
123	Franklin	Exit 439	US-64	US-64 Eastbound at NC-39	Asphalt	8	1	1		14			
124	Franklin	Exit 442	US-64	US-64 Westbound at Tant Rd	Asphalt	8	1	1		14			
125	Franklin	Exit 442	US-64	US-64 Eastbound at Tant Rd	Asphalt	8	1	1		14			
TOTAL FOR US-64/US-264						152	19	19	1	266	20		24
GRAND TOTAL						152	19	20		266	20		24

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	9	15

SUMMARY OF QUANTITIES

LOCATION REFERENCE NUMBER	COUNTY	EXIT NUMBER	ROUTE	DESCRIPTION	PAVEMENT TYPE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
						LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H-SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
						HR	EA	EA	EA	EA	LF	LF	LF
126	Durham	N/A	US-15-501 BUS	US-15-501 BUS Northbound at Academy Road	Asphalt	8	1	1		14			12
127	Durham	N/A	US-15-501 BUS	US-15-501 BUS Southbound at Academy Road	Asphalt								12
128	Durham	Exit 106	US-15-501	US-15-501 Northbound at W Cornwallis Road	Asphalt	8	1	1		14			
129	Durham	Exit 106	US-15-501	US-15-501 Southbound at W Cornwallis Road	Asphalt	8	1	1		14			
130	Durham	Exit 107	US-15-501	US-15-501 Northbound at Cameron Boulevard	Asphalt	8	1	1		14			
131	Durham	Exit 107	US-15-501	US-15-501 Southbound at Cameron Boulevard	Asphalt	8	1	1		14			
132	Durham	Exit 108A	US-15-501	US-15-501 Northbound at Morreene Road	Asphalt	8	1	1		14			
133	Durham	Exit 108B	US-15-501	US-15-501 Southbound at Morreene Road	Asphalt	8	1	1		14			
134	Durham	Exit 108D	US-15-501	US-15-501 Northbound at Hillsborough Road	Asphalt	8	1	1		14			
135	Durham	Exit 108D	US-15-501	US-15-501 Southbound at Hillsborough Road	Asphalt	8	1	1		14			
TOTAL FOR US-15/US-501, Business US-15/US-501						72	9	9		126			24
GRAND TOTAL						72	9	9		126			24

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	10	15

SUMMARY OF QUANTITIES

LOCATION REFERENCE NUMBER	COUNTY	EXIT NUMBER	ROUTE	DESCRIPTION	PAVEMENT TYPE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
						LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H-SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
						HR	EA	EA	EA	EA	LF	LF	LF
136	Wake	Exit 55	NC-540	NC-540 Toll Northbound at Veridea Pkwy	Concrete	8	1		1		22		
137	Wake	Exit 55	NC-540	NC-540 Toll Southbound at Veridea Pkwy	Asphalt	16	2	1	1	14	22		
138	Wake	Exit 57	NC-540	NC-540 Toll Eastbound at Salem St	Asphalt	16	2	1	1	14	32		
139	Wake	Exit 57	NC-540	NC-540 Toll Westbound at Salem St	Asphalt	16	2	1	1	14	32		
140	Wake	Exit 62	NC-540	NC-540 Toll Eastbound at Green Level Road	Asphalt	16	2	1	1	14	34		
141	Wake	Exit 62	NC-540	NC-540 Toll Westbound at Green Level Road	Asphalt	16	2	1	1	14	34		
142	Wake	Exit 69	NC-540	NC-540 Toll Eastbound at Chapel Hill Road	Asphalt	16	2	1	2	14			
143	Wake	Exit 69	NC-540	NC-540 Toll Westbound at Chapel Hill Road	Asphalt	16	2	2	1	14	44		
144	Wake	Exit 3	I-540	I-540 Eastbound at Lumley Road	Asphalt	16	2	1	1	14	22		12
TOTAL FOR NC-540/I-540						136	17	9	10	112	242		12
GRAND TOTAL						136	17	19	112	242			12

PROJECT NO.	SHEET NO.	TOTAL NO.
50977.3.13	11	15

SUMMARY OF QUANTITIES

LOCATION REFERENCE NUMBER	COUNTY	EXIT NUMBER	ROUTE	DESCRIPTION	PAVEMENT TYPE	4510000000-N	4600000000-N	4725000000-E		4895000000-N	4688000000-E		4890000000-E
						LAW ENFORCEMENT	RAMP/LOOP CLOSURES	WRONG-WAY RAMP ARROW (90 MIL)	ELONGATED STRAIGHT ARROW (90 MIL)	POLYCARBONATE H-SHAPED MARKERS	2 FT. - 6 FT./SP YELLOW MINISKIP (6", 90 MIL)	2 FT. - 6 FT./SP WHITE MINISKIP (6", 90 MIL)	24" YIELD LINE TRIANGLE (90 MIL)
						HR	EA	EA	EA	EA	LF	LF	LF
145	Durham	Exit 1	NC-147	NC-147 Northbound at S Briggs Avenue	Concrete	8	1	1		14			12
146	Durham	Exit 1C	NC-147	NC-147 Southbound at S Briggs Avenue	Concrete	8	1	1		14			
147	Durham	Exit 3A	NC-147	NC-147 Northbound at Fayetteville St/Jackie Robinson	Asphalt	8	1	1		14			
148	Durham	Exit 3	NC-147	NC-147 Southbound at Morehead Ave/ Fayetteville	Concrete/Asphalt	8	1	1		14			
149	Durham	Exit 4A	NC-147	NC-147 Northbound at W Chapel Hill St	Concrete	16	2	1	1	14	26		
150	Durham	Exit 4A	NC-147	NC-147 Southbound at W Chapel Hill St	Concrete/Asphalt	8	1	1		14			
151	Durham	Exit 4B	NC-147	NC-147 Northbound at Swift Ave	Concrete	8	1	1		14			
152	Durham	Exit 4B	NC-147	NC-147 Southbound at Swift Ave	Concrete	16	2	1	1	14	20		
153	Durham	Exit 5	NC-147	NC-147 Northbound at Elba St/Trent Dr	Asphalt	8	1	1		14			
154	Durham	Exit 6	NC-147	NC-147 Northbound at Fulton St	Asphalt	16	2	1	2	14			
155	Durham	Exit 6	NC-147	NC-147 Southbound at Fulton St/Hillandale Rd	Asphalt	16	2	1	2	14			12
TOTAL FOR NC-147						120	15	11	6	154	46		24
GRAND TOTAL						120	15	17		154	46		24