


**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**

**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**

**This file or an individual page
shall not be considered a certified document.**

CONTRACT: DE00206 TIP PROJECT: 17BP.5.R.54




STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
DURHAM COUNTY


LOCATION: BRIDGE NO. 117 OVER MUD CREEK ON SR 1308 (CORNWALLIS ROAD)

TYPE OF WORK: GRADING, PAVING, DRAINAGE, STRUCTURE AND SIGNAL

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.5.R.54	1	
STATE PROJECT NO.	F.A. PROJ. NO.	DESCRIPTION	
17BP.5.R.54			



**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**



DESIGN DATA

ADT (2011) = 3300

ADT (2025) = 6600

V = 45 MPH

CLASS =
MINOR ARTERIAL
SUB REGIONAL TIER

PROJECT LENGTH

LENGTH ROADWAY TIP PROJECT = 0.216 MILES

LENGTH STRUCTURE TIP PROJECT = 0.014 MILES

TOTAL LENGTH TIP PROJECT = 0.230 MILES

Prepared in the Office of Hatch Matt MacDonald for
DIVISION 5
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

2012 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
DECEMBER 5, 2016

LETTING DATE:
DECEMBER 13, 2017

NCDOT CONTACT: LISA GILCHRIST, EI

TIM JORDAN, PE
PROJECT ENGINEER

TRENT CORMIER, PE
HYDRAULICS ENGINEER

ROADWAY DESIGN ENGINEER

HYDRAULICS ENGINEER

11/6/2017 P.E.

11/6/2017 P.E.

PLANS PREPARED BY:

M MOTT MACDONALD

PO Box 700
Fuquay-Varina, NC 27526
(919) 552-2253
(919) 552-2254 (Fax)
www.mottmac.com/americas

LICENSE NO. F-0669

ICA

ICA Engineering, Inc.
5121 Kingdom Way,
Suite 100
Raleigh, NC 27607
NC License No: F-0258

PROJECT REFERENCE	SHEET NO.
17BP.5.R.54 - DURHAM 117	1-A
ROADWAY DESIGN ENGINEER	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
Prepared in the Office of:	
	MOTT MACDONALD 1 & E, LLC PO Box 700 Fuquay-Varina, NC 27526 www.mottmac.com

GENERAL NOTES

GENERAL NOTES: 2012 SPECIFICATIONS
 EFFECTIVE: 01-17-12
 REVISED: 01-24-17

GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

END BENTS:

THE SURVEYOR SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTIONS PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES: UTILITY OWNERS ON THIS PROJECT ARE FRONTIER, CHARTER AND CITY OF DURHAM (GRAVITY SEWER). ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

LIST OF ROADWAY STANDARD DRAWINGS

EFF. 01-17-2012
REV. 05-24-2017

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
DIVISION 2 - EARTHWORK	
200.03	Method of Clearing - Method III
225.02	Guide for Grading Subgrade - Secondary and Local
225.04	Method of Obtaining Superelevation - Two Lane Pavement
DIVISION 3 - PIPE CULVERTS	
300.01	Method of Pipe Installation
DIVISION 4 - MAJOR STRUCTURES	
422.10	Reinforced Bridge Approach Fills
DIVISION 5 - SUBGRADE, BASES AND SHOULDERS	
560.01	Method of Shoulder Construction - High Side of Superelevated Curve - Method I
DIVISION 8 - INCIDENTALS	
806.01	Concrete Right-of-way Marker
840.00	Concrete Base Pad for Drainage Structures
840.18	Concrete Grated Drop Inlet Type 'B' - 12" thru 36" Pipe
840.25	Anchorage for Frames - Brick or Concrete or Precast
840.27	Brick Grated Drop Inlet Type 'B' - 12" thru 36" Pipe
840.29	Frames and Narrow Slot Flat Grates
840.45	Precast Drainage Structure
840.66	Drainage Structure Steps
846.01	Concrete Curb, Gutter and Curb & Gutter
846.04	Drop Inlet Installation in Shoulder Berm Gutter
876.01	Rip Rap in Channels
876.02	Guide for Rip Rap at Pipe Outlets
876.04	Drainage Ditches with Class 'B' Rip Rap

INDEX OF SHEETS

SHEET NUMBER	DESCRIPTION
1	TITLE SHEET
1-A	INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS
1-B	CONVENTIONAL SYMBOLS
1C-1	SURVEY CONTROL SHEET
2A-1	PAVEMENT SCHEDULE AND TYPICAL SECTIONS
2C-1 THRU 2C-11	DETAILS FOR GUARDRAIL PLACEMENT AND INSTALLATION
3B-1	GUARDRAIL SUMMARY, SHOULDER BERM GUTTER SUMMARY AND EARTHWORK SUMMARY
3D-1	DRAINAGE SUMMARY
4	PLAN SHEET
5	PROFILE SHEET
TMP-1 THRU TMP-4	TRAFFIC MANAGEMENT PLANS
PMP-1	PAVEMENT MARKING PLANS
EC-1 THRU EC-5	EROSION CONTROL PLANS
RF-1	REFORESTATION DETAIL SHEET
SIG-1 THRU SIG-2	SIGNAL PLANS
UO-1	UTILITIES BY OTHERS PLANS
X-1A	CROSS-SECTION SUMMARY SHEET
X-1 THRU X-6	CROSS-SECTIONS
S-1 THRU S-18	STRUCTURE PLANS
SN	STANDARD STRUCTURE NOTES

Note: Not to Scale

*S.U.E. = *Subsurface Utility Engineering*

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CONVENTIONAL PLAN SHEET SYMBOLS

BOUNDARIES AND PROPERTY:

State Line	-----
County Line	-----
Township Line	-----
City Line	-----
Reservation Line	-----
Property Line	-----
Existing Iron Pin	○ EIP
Property Corner	-----
Property Monument	ECM
Parcel/Sequence Number	123
Existing Fence Line	-x-x-x-
Proposed Woven Wire Fence	○
Proposed Chain Link Fence	□
Proposed Barbed Wire Fence	◇
Existing Wetland Boundary	-WLB-
Proposed Wetland Boundary	-WLB-
Existing Endangered Animal Boundary	-EAB-
Existing Endangered Plant Boundary	-EPB-

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	○
Sign	○
Well	○
Small Mine	✕
Foundation	□
Area Outline	□
Cemetery	+
Building	□
School	□
Church	□
Dam	□

HYDROLOGY:

Stream or Body of Water	-----
Hydro, Pool or Reservoir	□
Jurisdictional Stream	-JS-
Buffer Zone 1	-BZ 1-
Buffer Zone 2	-BZ 2-
Flow Arrow	→
Disappearing Stream	→
Spring	○
Wetland	WLB
Proposed Lateral, Tail, Head Ditch	← FLOW
False Sump	◇

RAILROADS:

Standard Gauge	CSX TRANSPORTATION
RR Signal Milepost	MILEPOST 35
Switch	SWITCH
RR Abandoned	-----
RR Dismantled	-----

RIGHT OF WAY:

Baseline Control Point	◆
Existing Right of Way Marker	△
Existing Right of Way Line	-----
Proposed Right of Way Line	○ R W
Proposed Right of Way Line with Iron Pin and Cap Marker	○ R W ▲
Proposed Right of Way Line with Concrete or Granite Marker	○ R W ●
Existing Control of Access	○
Proposed Control of Access	○
Existing Easement Line	-E-
Proposed Temporary Construction Easement	-E-
Proposed Temporary Drainage Easement	-TDE-
Proposed Permanent Drainage Easement	-PDE-
Proposed Permanent Utility Easement	-PUE-

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	-----
Existing Curb	-----
Proposed Slope Stakes Cut	-C-
Proposed Slope Stakes Fill	-F-
Proposed Wheel Chair Ramp	WCR
Existing Metal Guardrail	-----
Proposed Guardrail	-----
Existing Cable Guiderail	-----
Proposed Cable Guiderail	-----
Equality Symbol	⊕
Pavement Removal	⊗

VEGETATION:

Single Tree	☼
Single Shrub	☼
Hedge	-----
Woods Line	-----
Orchard	-----
Vineyard	Vineyard

EXISTING STRUCTURES:

MAJOR:	
Bridge, Tunnel or Box Culvert	CONC
Bridge Wing Wall, Head Wall and End Wall	CONC WW
MINOR:	
Head and End Wall	CONC HW
Pipe Culvert	-----
Footbridge	-----
Drainage Box: Catch Basin, DI or JB	CB
Paved Ditch Gutter	-----
Storm Sewer Manhole	⊕
Storm Sewer	-----

UTILITIES:

POWER:	
Existing Power Pole	●
Proposed Power Pole	○
Existing Joint Use Pole	●
Proposed Joint Use Pole	○
Power Manhole	⊕
Power Line Tower	⊗
Power Transformer	⊗
U/G Power Cable Hand Hole	⊕
H-Frame Pole	●
Recorded U/G Power Line	-P-
Designated U/G Power Line (S.U.E.*)	-P-

TELEPHONE:

Existing Telephone Pole	●
Proposed Telephone Pole	○
Telephone Manhole	⊕
Telephone Booth	⊕
Telephone Pedestal	⊕
Telephone Cell Tower	⊕
U/G Telephone Cable Hand Hole	⊕
Recorded U/G Telephone Cable (S.U.E.*)	-T-
Designated U/G Telephone Cable (S.U.E.*)	-T-
Recorded U/G Telephone Conduit	-TC-
Designated U/G Telephone Conduit (S.U.E.*)	-TC-
Recorded U/G Fiber Optics Cable	-T FO-
Designated U/G Fiber Optics Cable (S.U.E.*)	-T FO-

WATER:

Water Manhole	⊕
Water Meter	○
Water Valve	⊗
Water Hydrant	⊕
Recorded U/G Water Line	-W-
Designated U/G Water Line (S.U.E.*)	-W-
Above Ground Water Line	A/G Water

TV:

TV Satellite Dish	⊕
TV Pedestal	⊕
TV Tower	⊗
U/G TV Cable Hand Hole	⊕
Recorded U/G TV Cable	-TV-
Designated U/G TV Cable (S.U.E.*)	-TV-
Recorded U/G Fiber Optic Cable	-TV FO-
Designated U/G Fiber Optic Cable (S.U.E.*)	-TV FO-

GAS:

Gas Valve	◇
Gas Meter	⊕
Recorded U/G Gas Line	-G-
Designated U/G Gas Line (S.U.E.*)	-G-
Above Ground Gas Line	A/G Gas

SANITARY SEWER:


Sanitary Sewer Manhole	⊕
Sanitary Sewer Cleanout	⊕
U/G Sanitary Sewer Line	-SS-
Above Ground Sanitary Sewer	A/G Sanitary Sewer
Recorded SS Forced Main Line	-FSS-
Designated SS Forced Main Line (S.U.E.*)	-FSS-

MISCELLANEOUS:

Utility Pole	●
Utility Pole with Base	□
Utility Located Object	○
Utility Traffic Signal Box	⊕
Utility Unknown U/G Line	-ZUTL-
U/G Tank; Water, Gas, Oil	□
A/G Tank; Water, Gas, Oil	□
U/G Test Hole (S.U.E.*)	⊕
Abandoned According to Utility Records	AATUR
End of Information	E.O.I.

SURVEY CONTROL SHEET 31-0117

PROJECT REFERENCE NO.	SHEET NO.
17BP.5.R.54 - DURHAM 117	1C-1
LOCATION AND SURVEYS	



BL POINT	DESC.	NORTH	EAST	ELEVATION	L STATION	OFFSET
2	31-0117-2	815212.7860	2009338.2460	346.87	OUTSIDE PROJECT LIMITS	
9	BL-1	815779.9410	2008539.9370	298.00	OUTSIDE PROJECT LIMITS	
10	BL-2	816612.8720	2007891.4890	289.44	09+99.60	16.93 RT
1	31-0117-1	817037.9290	2007622.9960	324.89	OUTSIDE PROJECT LIMITS	

 BM1 ELEVATION = 278.92
 N 816409 E 2008098
 L STATION 12+86.00 32 LEFT
 RR SPIKE SET IN 20" OAK

 BM2 ELEVATION = 276.55
 N 816161 E 2008280
 L STATION 15+94.00 36 LEFT
 RR SPIKE SET IN 24" GUM

DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NCDOT FOR MONUMENT "31-0117-2"
 WITH NAD 83/NA 2011 STATE PLANE GRID COORDINATES OF
 NORTHING: 815,212.786(ft) EASTING: 2,009,338.246(ft)
 ELEVATION: 346.87'(ft)
 THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.99994423
 THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "31-0117-2" TO -L- STATION 5+85.00 IS
 N 44°00'35.3" W 2,421.07'
 ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES
 VERTICAL DATUM USED IS NAVD 88

NOTES:


○ INDICATES GEODETIC CONTROL MONUMENTS USED OR SET FOR HORIZONTAL AND VERTICAL PROJECT CONTROL BY THE NCDOT LOCATION AND SURVEYS UNIT.
 PROJECT CONTROL ESTABLISHED USING GNSS (GLOBAL NAVIGATION SATELLITE SYSTEM).


SITE CALIBRATION INFORMATION HAS NOT BEEN PROVIDED FOR THIS PROJECT. IF FURTHER INFORMATION IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

GEOID G12NC
 NOTE: DRAWING NOT TO SCALE

12/20/16


11:56:15 AM
 R:\Projects\17BP.5.R.54 - DURHAM 117\310117.LS.1C.dgn
 10/26/16

PROJECT REFERENCE 17BP.5.R.54 - DURHAM 117	SHEET NO. 2A-1
ROADWAY DESIGN ENGINEER MOTT MACDONALD 1 & E, LLC 11/6/2017	
	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	
Prepared in the Office of: M MOTT MACDONALD 1 & E, LLC PO Box 700 Fuquay-Varina, NC 27526 www.mottmcc.com	



TYPICAL SECTION NO. 1


USE TYPICAL SECTION NO. 1:
 -L- STA 5+85.00 TO 6+60.00
 TRANSITION FROM TYPICAL SECTION NO. 1 TO NO. 2:
 -L- STA 6+60.00 TO 9+00.00



TYPICAL SECTION NO. 4


USE TYPICAL SECTION NO. 4:
 -L- STA 14+94.88 (BEGIN BRIDGE) TO 15+67.13 (END BRIDGE)

NOTE: SEE STRUCTURE PLANS FOR PAVEMENT DEPTHS ON STRUCTURE




TYPICAL SECTION NO. 2

USE TYPICAL SECTION NO. 2:
 -L- STA 9+00.00 TO 13+50.00
 -L- STA 17+10.00 TO 17+50.00
 TRANSITION FROM TYPICAL SECTION NO. 2 TO EXISTING:
 -L- STA 17+50.00 TO 18+00.00




DETAIL FOR FULL DEPTH PAVED SHOULDER IN CONJUNCTION WITH GUARDRAIL



DETAIL FOR SHOULDER BERM GUTTER IN CONJUNCTION WITH GUARDRAIL

-L- STA 14+42.00 TO 14+84.00 LT



TYPICAL SECTION NO. 3

TRANSITION FROM TYPICAL SECTION NO. 2 TO NO. 3:
 -L- STA 13+50.00 TO 14+10.00
 USE TYPICAL SECTION NO. 3:
 -L- STA 14+10.00 TO 14+94.88 (BEGIN BRIDGE)
 -L- STA 15+67.13 (END BRIDGE) TO 16+50.00
 TRANSITION FROM TYPICAL SECTION NO. 3 TO NO. 2:
 -L- STA 16+50.00 TO 17+10.00

PAVEMENT SCHEDULE	
C	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C1	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 1 1/2" IN DEPTH OR GREATER THAN 2" IN DEPTH.
D	PROP. APPROX. 2 1/2" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YD.
E	PROP. APPROX. 5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 570 LBS. PER SQ. YD.
T	EARTH MATERIAL.
R	SHOULDER BERM GUTTER.

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.

11/6/2017 11:26:33 AM
 R:\Roadway\ProJ\310117_r.dwg - tjp.dgn
 10:66165

04-MAY-2017 15:14 S:\Contracts\Contractors\Special Details\Standard Drawings\Details in Lieu of Standards\Drawings\862d01 862d01 862d01.dgn
 JHowerton A1 CS0-29295

ROADWAY DETAIL DRAWING FOR GUARDRAIL PLACEMENT

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR GUARDRAIL PLACEMENT

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

NOTE SPECIAL LAYER OF PAVEMENT
 USE 3'-1 1/2" POST SPACING ON THE 50' OF GUARDRAIL PARALLEL TO LANES AND 6'-3" POST SPACING ON 15:1 TRANSITION SECTIONS.
 GRADE MEDIAN IN THE VICINITY OF THE SIGN SUPPORT AS ILLUSTRATED IN THE ROADWAY STANDARD DRAWINGS (STANDARD 862D01 SHEET 1 OF 12).

SECTION Y-Y
 MEDIAN WIDTH
 SHOULDER SLOPE PER PLANS (10:1 OR FLATTER)
 6'-3"

SECTION Z-Z
 MEDIAN WIDTH
 SHOULDER SLOPE PER PLANS (10:1 OR FLATTER)
 6'-0"

SHEET 2 OF 11
862D01

ROADWAY DETAIL DRAWING FOR GUARDRAIL PLACEMENT

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR GUARDRAIL PLACEMENT

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

SECTION X-X
 MEDIAN WIDTH
 SHOULDER SLOPE PER PLANS (10:1 OR FLATTER)
 SHOULDER (VAR.)
 DITCH (VAR.)
 DITCH SLOPE
 SHOULDER SLOPE PER PLANS (10:1 OR FLATTER)
 INLET & PIPE REQUIRED WHERE DITCH CANNOT BE GRADED TO DRAIN.

SECTION Y-Y
 MEDIAN WIDTH
 SHOULDER SLOPE PER PLANS (10:1 OR FLATTER)

SECTION Z-Z
 MEDIAN WIDTH
 SHOULDER SLOPE PER PLANS (10:1 OR FLATTER)
 1" OFFSET (TYP.)
 SINGLE FACED PRECAST CONCRETE BARRIER SEE STD. DWG. 857.01

NOTE: WHEN OFFSET DISTANCE FROM FACE OF OBSTRUCTION TO FACE OF GUARDRAIL IS BETWEEN 3'-6" AND 5'-6" BEGIN 3'-1 1/2" POST SPACING AT A POINT 25' BEFORE REACHING THE OBSTRUCTION AND CARRY THROUGHOUT ITS LENGTH. IF THE OFFSET IS LESS THAN 3'-6" USE CONCRETE BARRIER.

NOTE: GUARDRAIL APPROACH TREATMENT AS REQUIRED FOR CUT OR FILL.
 0'-0" TO 12'-6"
 CAT-1
 12' MIN. DESTRIABLE
 3'-6" MIN. 5'-6" DESTRIABLE
 OFFSET SEE NOTE

NOTE: WHEN OFFSET DISTANCE FROM FACE OF OBSTRUCTION TO FACE OF GUARDRAIL IS 5'-6" OR GREATER. SEE NOTE.

NOTE: WHEN OFFSET DISTANCE FROM FACE OF OBSTRUCTION TO FACE OF GUARDRAIL IS BETWEEN 3'-6" AND 5'-6" BEGIN 3'-1 1/2" POST SPACING AT A POINT 25' BEFORE REACHING THE OBSTRUCTION AND CARRY THROUGHOUT ITS LENGTH. IF THE OFFSET IS LESS THAN 3'-6" USE CONCRETE BARRIER.

SHEET 1 OF 11
862D01

DETAIL OF MEDIAN TREATMENT AT UNDERPASS

DETAIL OF RIGHT SIDE GUARDRAIL AT UNDERPASS

CONTRACT STANDARDS AND DEVELOPMENT UNIT
 Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J. HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE:
 CHECKED BY: DATE:
 FILE SPEC.: DATE:



DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

94 MAY 2017 15:14 C:\projects\Special Details\Standard Drawings\2012 Standard Drawings\Division 8\862d01.dgn 862d03 862d03\862d01.dgn
 jhowerton AT 050 292595

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 4 OF 11
862D01

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 4 OF 11
862D01



**GUARDRAIL INSTALLATION AT BRIDGE APPROACHES
FOR TWO-LANE, TWO-WAY TRAFFIC**

DESIGN SPEED (MPH)	"L" APPROACH LENGTH (FT.)		"L1" TRAILING LENGTH (FT.)			
	DESIGN YEAR ADT OVER 2000	CURRENT YEAR ADT 400-1000	DESIGN YEAR ADT OVER 2000	CURRENT YEAR ADT 1001-2000	CURRENT YEAR ADT 2001-1000	CURRENT YEAR ADT 400-400
70	362.5'	382.5'	350.0'	287.5'	187.5'	175.0'
60	300.0'	287.5'	275.0'	225.0'	137.5'	100.0'
50	212.5'	212.5'	200.0'	162.5'	87.5'	75.0'
40	175.0'	150.0'	137.5'	112.5'	75.0'	75.0'
X*	8'	6'	4'	4'	8'	4'

* USE FLARE RATE AS THE CONTROL IF THE "X" DISTANCE IS NOT OBTAINED. ("X" IS BASED ON SHOULDER WIDTHS IN THE HIGHWAY DESIGN BRANCH MANUAL, PART 1, 1-4B, F1).

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL WHERE GUARDRAIL IS PARALLEL TO LANE.

SEE STD. 862.03 FOR STRUCTURE ANCHOR UNITS


FOR POSTED SPEEDS ≥ 45mph USE GREU TYPE TL-3
FOR POSTED SPEEDS < 45mph USE GREU TYPE TL-2

LENGTHS AND OFFSETS FOR PROPOSED GUARDRAIL AT TWO LANE - TWO WAY LOCATIONS

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 3 OF 11
862D01



DIMENSIONS FOR LENGTH OF GUARDRAIL APPROACHING DUAL LANE BRIDGES

MEDIAN WIDTH	70 MPH	60 MPH	50 MPH	-L2- DIM.
30'	300.0'	250.0'	150.0'	80.0'
36'	300.0'	250.0'	150.0'	60.0'
40' & ABOVE	300.0'	250.0'	150.0'	40.0'

FOR POSTED SPEEDS ≥ 45mph USE GREU TYPE TL-3
FOR POSTED SPEEDS < 45mph USE GREU TYPE TL-2

NOTES: * MINOR VARIATION TO THE 25'-0" DIMENSION IS PERMISSIBLE TO ACCOMMODATE THE 12'-6" IN GUARDRAIL LENGTHS.

** NO GUARDRAIL IS REQUIRED ON THE TRAILING END WHEN THIS DISTANCE EXCEEDS CLEAR ROADSIDE RECOVERY AREA FOR THE APPROPRIATE DESIGN SPEED.

*** BASED ON "X" OF 12' USE FLARE RATE AS THE CONTROL IF THE "X" DISTANCE IS NOT OBTAINED. ("X" IS BASED ON SHOULDER WIDTHS IN THE HIGHWAY DESIGN BRANCH MANUAL, PART 1, 1-4B, F1A).

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL WHERE GUARDRAIL IS PARALLEL TO LANE. THE DESIGN LAYOUT FOR LENGTHS SHOWN ON THIS STANDARD ARE MINIMUM DESIGN LENGTHS. SEE SHEET 1 OF 12 FOR SECTIONS XX, YY

SEE STD. 862.03 FOR STRUCTURE ANCHOR UNITS

DETAIL OF GUARDRAIL APPROACHING DUAL LANE BRIDGES

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

**CONTRACT STANDARDS
AND DEVELOPMENT UNIT**
Office 919-707-6950 FAX 919-250-4119


SEE TITLE BLOCK

ORIGINAL BY: J. HOWERTON	DATE: 06-22-12
MODIFIED BY: _____	DATE: _____
CHECKED BY: _____	DATE: _____
FILE SPEC.: _____	



84 MAY-2017 15:45 I:\projects\Special Details\Standard Drawings\Details in Lieu of Standards\Drawings\Division 8\862d01_862d03_862d01.dgn
 jhowerton AT CSO-292595

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.




STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 6 OF 11
862D01

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.



STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 5 OF 11
862D01



DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

**CONTRACT STANDARDS
 AND DEVELOPMENT UNIT**
 Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J. HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE:
 CHECKED BY: DATE:
 FILE SPEC.:

Q:\MAY-2017\516\Projects\Special Details\Jhowerton\Standard Drawings\Details in Lieu of Standards\Division 8\862d01 862d03 862d03\862d01.dgn
 Jhowerton AT CSD-2625.dwg

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.	ROADWAY DETAIL DRAWING FOR GUARDRAIL PLACEMENT	SHEET 8 OF 11 862D01
DETAIL - 1 GUARDRAIL END UNIT TYPE TL-3 OR TL-2 (50:1 TAPER) SHOP CURVED GUARDRAIL (50:1 TAPER) R=20' TO 75' (SEE NOTES) AT-1 4' OFFSET		
DETAIL - 2 GUARDRAIL END UNIT TYPE TL-3 OR TL-2 (50:1 TAPER) GUARDRAIL END UNIT TYPE TL-3 OR TL-2 (50:1 TAPER) 'R' IS GREATER THAN 75' (SEE NOTES)		
GUARDRAIL TREATMENT AT INTERSECTIONS		
NOTES: SHOP CURVED GUARDRAIL IS DEFINED AS HAVING A RADIUS OF 150' OR LESS. WHEN RADIUS IS LESS THAN 20' REFER TO SHEET 9. WHENEVER SHOP CURVED GUARDRAIL IS USED AS AN ANCHOR AND THE RADIUS IS FROM 20' TO 75', USE A MINIMUM LENGTH OF 50' OF SHOP CURVED GUARDRAIL AND FLARE WITH AN AT-1 ANCHOR UNIT. REFER TO DETAIL 1. WHENEVER SHOP CURVED GUARDRAIL RADIUS IS MORE THAN 75', REFER TO DETAIL 2. MAINTAIN CLEAR SIGHT DISTANCE. FOR POSTED SPEEDS ≥ 45mph USE GREU TYPE TL-3 FOR POSTED SPEEDS < 45mph USE GREU TYPE TL-2		
ROADWAY DETAIL DRAWING FOR GUARDRAIL PLACEMENT		
STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.		


STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.	ROADWAY DETAIL DRAWING FOR GUARDRAIL PLACEMENT	SHEET 7 OF 11 862D01
DETAIL AT UNDERPASSES * GUARDRAIL OPENING MAY BE SPACED AS CLOSE AS 350 FT. FROM STRUCTURE IF NECESSARY TO ALLOW MOWER ACCESS TO MEDIAN		
DETAIL AT OVERPASSES FOR POSTED SPEEDS ≥ 45mph USE GREU TYPE TL-3 FOR POSTED SPEEDS < 45mph USE GREU TYPE TL-2		
GUARDRAIL BREAK INTERVALS WITH 30' - 36' MEDIANS		
ROADWAY DETAIL DRAWING FOR GUARDRAIL PLACEMENT		
STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.		

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

**CONTRACT STANDARDS
AND DEVELOPMENT UNIT**
Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J HOWERTON	DATE: 06-22-12
MODIFIED BY: _____	DATE: _____
CHECKED BY: _____	DATE: _____
FILE SPEC.: _____	




C:\MAY-2017\5r6\Projects\Special Details\Howerton\Standard Drawings\Details in Lieu of Standards\Division 8\862d01 862d03 862d03\862d01.dgn
 Howerton
 CSD-26258g

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
RALEIGH, N.C.

ENGLISH DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 10 OF 11
862D01



FLEXIBLE PAVED SHOULDER

CONCRETE PAVED SHOULDER

NOTE:
WHEN WOODEN GUARDRAIL POSTS ARE USED, DRILL HOLES THROUGH EARTH MATERIAL AND BASE COURSE. THE POST MAY THEN BE DRIVEN TO THE PROPER DEPTH. DRILL THE HOLE OF SUFFICIENT SIZE TO ACCOMMODATE THE PARTICULAR POST BEING USED. BACKFILL AND TAMP HOLES USING THE EXCAVATED MATERIAL.

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ENGLISH DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 9 OF 11
862D01

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT

SHEET 9 OF 11
862D01



DETAIL -3
DIVIDED HIGHWAY

DETAIL -4
UNDIVIDED HIGHWAY

NOTE:
USE DETAIL 3 & 4 WHENEVER
20' OR LARGER RADIUS CANNOT
BE UTILIZED.
MAINTAIN CLEAR SIGHT DISTANCE.

FOR POSTED SPEEDS \geq 45mph USE GREU TYPE TL-3
FOR POSTED SPEEDS $<$ 45mph USE GREU TYPE TL-2

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL PLACEMENT


SHEET 9 OF 11
862D01

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED


**CONTRACT STANDARDS
AND DEVELOPMENT UNIT**
Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J HOWERTON	DATE: 06-22-12
MODIFIED BY: _____	DATE: _____
CHECKED BY: _____	DATE: _____
FILE SPEC.: _____	



C:\JAY-2017\5R17\Projects\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01 862d03 862d01.dgn
 Jhowerton AT CSD-262588



DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

**CONTRACT STANDARDS
AND DEVELOPMENT UNIT**
Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J. HOWERTON	DATE: 06-22-12
MODIFIED BY:	DATE:
CHECKED BY:	DATE:
FILE SPEC.:	

23-MAY-2017 12:50 S:\Contracts\Contractors\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01 862d03 862d02.dgn
 Jhowerton - A1 CS0-29295

STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 2 OF 8
862D02


STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 2 OF 8
862D02



* WHEN INSTALLING GUARDRAIL END UNITS THAT ARE 2'-1" MOUNTING HEIGHT TO EXISTING GUARDRAIL, REMOVE THE EXISTING GUARDRAIL TO TRANSITION FROM THE EXISTING HEIGHT TO THE PROPOSED 2'-1" HEIGHT. SEE 862.02, SHEET 4 OF 8 FOR TRANSITION DETAILS.



APPROACH END UNITS

STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 1 OF 8
862D02

STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 1 OF 8
862D02



TRAILING END UNIT ASSEMBLY
C.A.T. - 1 SYSTEM

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

**CONTRACT STANDARDS
 AND DEVELOPMENT UNIT**
 Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J. HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE:
 CHECKED BY: DATE:
 FILE SPEC.:



I:\MAY-2017_07130_S:\Contracts\ContractDocs\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01_862d03_862d03\862d02.dgn
 J:\Howerton\ContractDocs\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01_862d03_862d03\862d02.dgn

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION


SHEET 4 OF 8
862D02

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 4 OF 8
862D02

NOTE: IF EXISTING GUARDRAIL IS LOWER THAN 1'-11", USE AN ADDITIONAL 12'-6" LONG SECTION OF GUARDRAIL, FOR EVERY 1" OF HEIGHT DIFFERENCE, TO TRANSITION FROM EXISTING GUARDRAIL TO PROPOSED 2'-1" GUARDRAIL.



ELEVATION VIEW

TRANSITION FROM OR 1'-11" TO 2'-1" W-BEAM GUARDRAIL MOUNTING HEIGHT

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 3 OF 8
862D02

STATE OF
NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 3 OF 8
862D02



15'-7 1/2" W-BEAM GUARDRAIL PANEL


NOTE: USE 5-SPACE 15'-7 1/2" W-BEAM GUARDRAIL PANEL AT THE DOWNSTREAM END OF AN END UNIT OR EXISTING GUARDRAIL THAT DOES NOT OFFSET THE W-BEAM PANEL SPLICE TO MIDSPAN

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

**CONTRACT STANDARDS
AND DEVELOPMENT UNIT**
Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J. HOWERTON	DATE: 06-22-12
MODIFIED BY: _____	DATE: _____
CHECKED BY: _____	DATE: _____
FILE SPEC.: _____	



04-MAY-2017 15:20 S:\Contracts\Construction\Special Details\Howerton\Standard Drawings\Details in Lieu of Standards\Division 8\862d01 862d03 862d02.dgn
 Howerton - N1 CSP-24298

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 6 OF 8
862D02

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 6 OF 8
862D02



SYSTEM PARTS

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 5 OF 8
862D02

STATE OF NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 5 OF 8
862D02




TYPICAL GUARDRAIL AND GUARDRAIL POST ALTERNATIVES

ORIGINAL BY: J HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE:
 CHECKED BY: DATE:
 FILE SPEC.:

CONTRACT STANDARDS
 AND DEVELOPMENT UNIT
 Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED




04-MAY-2017 15:21
 S:\Contracts\2017\Special Details\Standard Drawings\Details in Lieu of Standards\Division 8\862d01 862d03 862d03\862d02.dgn
 Jhowerton - N1 CSP-21593


STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 8 OF 8
862D02



SECTION X-X



BUFFERED END SECTION

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 8 OF 8
862D02

STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 8 OF 8
862D02


STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION


SHEET 7 OF 8
862D02



TYPICAL END SHOE



BREAKAWAY TERMINAL POST SLEEVE



SOIL PLATE

STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 7 OF 8
862D02


STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION


SHEET 7 OF 8
862D02




DETAIL OF STANDARD WASHER




BEARING PLATE




DETAIL OF STANDARD HEX BOLT AND NUT




DETAIL OF BUTTON HEAD BOLT AND NUT




ANCHOR PLATE ASSEMBLY



SWAGED CABLE



ANCHOR PLATE



CABLE ASSEMBLY

STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 7 OF 8
862D02

STATE OF
 NORTH CAROLINA
 DEPT. OF TRANSPORTATION
 DIVISION OF HIGHWAYS
 RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION


SHEET 7 OF 8
862D02

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

CONTRACT STANDARDS AND DEVELOPMENT UNIT
 Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK


ORIGINAL BY: J HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE:
 CHECKED BY: DATE:
 FILE SPEC.:



STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ENGLISH DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
RAIL ON BRIDGE - SUB REGIONAL TIER

SHEET 2 OF 7
862d03



NOTE:
 **POST NOT REQUIRED FOR SKEW ANGLES GREATER THAN 150° OR LESS THAN 30° UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
 *THE DISTANCE FROM END OF BRIDGE RAIL TO CENTER LINE OF THE FIRST POST SHOULD BE 11 1/2" IF CONCRETE BACKWALL IS NOT PRESENT.
 -SHOULDER BERM GUTTER MUST BE INSTALLED TO THE LIMITS 8" x 4" LIP CURB IS SHOWN IF ANCHOR UNIT IS NOT ADJACENT TO AN APPROACH SLAB.
 -MEASURE GUARDRAIL HEIGHT FROM THE TOP OF ADJACENT SURFACE (SHOULDER, BERM, OR GUTTER).
 -LAP JOINTS IN THE DIRECTION OF TRAFFIC FLOW.
 -SEE SHEET 5 FOR POST SECTIONS 1 THRU 9.

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.


ENGLISH DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO RAIL ON BRIDGE - SUB REGIONAL TIER

SHEET 2 OF 7
862d03

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ENGLISH DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III

SHEET 3 OF 7
862d03



STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ENGLISH DETAIL DRAWING FOR
STRUCTURE ANCHOR UNITS
GUARDRAIL ANCHOR UNIT, TYPE III

SHEET 3 OF 7
862d03

CONTRACT STANDARDS AND DEVELOPMENT UNIT
Office 919-707-6950 FAX 919-250-4119

SEE TITLE BLOCK

ORIGINAL BY: J HOWERTON DATE: 06-22-12
 MODIFIED BY: DATE:
 CHECKED BY: DATE:
 FILE SPEC.:

*****SYTIME*****
 *****DON*****
 *****USER*****

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL
TOTAL SHOULDER WIDTH = DISTANCE FROM EDGE OF TRAVEL LANE TO SHOULDER BREAK POINT.
FLARE LENGTH = DISTANCE FROM LAST SECTION OF PARALLEL GUARDRAIL TO END OF GUARDRAIL.
W = TOTAL WIDTH OF FLARE FROM BEGINNING OF TAPER TO END OF GUARDRAIL.
G = GATING IMPACT ATTENUATOR TYPE 350
NG = NON-GATING IMPACT ATTENUATOR TYPE 350

GUARDRAIL SUMMARY

SURVEY LINE	BEG. STA.	END STA.	LOCATION	LENGTH			WARRANT POINT		"N" DIST. FROM E.O.L.	TOTAL SHOULDER WIDTH	FLARE LENGTH		W		ANCHORS						IMPACT ATTENUATOR TYPE 350			REMARKS					
				STRAIGHT	SHOP CURVED	DOUBLE FACED	APPROACH END	TRAILING END			APPROACH END	TRAILING END	APPROACH END	TRAILING END	AT-1	GREU TL-3	TYPE III	PERMITTED											
																		NO.	G	NG									
-L-	5+85 +/-	9+58.00	RT	312.50'	75.00'		TIE TO EXIST	8+50.00	6'	9'	50'	1'																TIE TO EXISTING GUARDRAIL; 345' OF GR REMOVAL	
-L-	14+13.63	14+94.88	RT	81.25'			14+94.88		6'	9'	50'	1'																	
-L-	14+13.63	14+94.88	LT	81.25'				14+94.88	10.5'	13.5'	50'	1'																	
-L-	15+67.13	16+73.38	RT	106.25'			15+67.13	16+50.00	6'	9'	50'	1'																	
-L-	15+67.13	16+48.38	LT	81.25'			15+67.13		10.5'	13.5'	50'	1'																	
SUBTOTAL				662.50'	75.00'																								
LESS ANCHOR DEDUCTIONS																													
GREU TL-3 5 x 50.00' =				-250.00'																									
TYPE III 4 x 18.75' =				-75.00'																									
TOTAL				337.50'	75.00'																	5	4						

SHOULDER BERM GUTTER SUMMARY



SURVEY LINE	BEG. STA.	END STA.	LENGTH
-L- LT	14+42.00	14+84.00	42.00'
TOTAL			42.00'
SAY			45.00'

SUMMARY OF EARTHWORK IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
-L- 5+85.00 TO 14+94.88 (BEGIN BRIDGE)	1113		919		194
-L- 15+67.13 (END BRIDGE) TO 18+00.00	157		395	238	
SUBTOTAL	1270		1314	238	194
WASTE IN LIEU OF BORROW				-194	-194
PROJECT TOTAL	1270		1314	44	0
5% TO REPLACE BORROW				47	
GRAND TOTAL	1270		1314	47	0
SAY	1340			50	


NOTE: Approximate quantities only. Unclassified Excavation, Borrow Excavation, Fine Grading, Clearing and Grubbing and Removal of Existing Asphalt Pavement will be paid for at the contract Lump Sum price for "Grading".

PROJECT REFERENCE		SHEET NO.	
17BP.5.R.54 - DURHAM 117		4	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
<p>DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED</p>			
<p>Prepared in the Office of: MOTT MACDONALD</p>			
<p>PO Box 700 Fuquay-Varina, NC 27526 www.mottmac.com</p>		<p>ICA Engineering, Inc. 3121 Kingdom Way, Suite 100 Raleigh, NC 27407 NC License No. F-02528</p>	
<p>ICAH</p>			
<p>HORIZONTAL SCALE 25' 0 25' 50'</p>			



NOTE: ALL CHANNEL RELOCATION WORK BETWEEN 8+05 RT AND 8+90 RT WILL NEED TO BE COMPLETED IN THE DRY. UTILIZE IMPERVIOUS DIKES AND CLEAN WATER DIVERSIONS OR A PUMP AROUND WITH SPECIAL STILLING BASINS TO ENSURE THERE IS NO SEDIMENT TRANSPORT OUTSIDE OF PROJECT LIMITS. ONCE ALL CHANNEL RELOCATION WORK HAS BEEN COMPLETED AND STABILIZED WATER CAN BE DIVERTED INTO THE NEW CHANNEL LOCATION, ALL CHANNEL RELOCATION WORK TO BE CONSIDERED INCIDENTAL TO CONSTRUCTION.


- NOTES
- NO GAS IN PROJECT LIMITS ACCORDING TO PSNC ENERGY (CONTACT: STEVE CAIN 919-367-2710/SCAIN@SCANA.COM)
 - U/G TELEPHONE & U/G TELEVISION POSSIBLY ABANDONED ACCORDING TO FRONTIER COMMUNICATIONS (CONTACT: RALPH PERRY 919-323-9376/RPERRY@SMOSE.COM)
 - TWO TELEPHONE DROPS ON POLE (UNTRACABLES) POSSIBLY ABANDONED ACCORDING TO FRONTIER COMMUNICATIONS (CONTACT: RALPH PERRY 919-323-9376/RPERRY@SMOSE.COM)
 - THE AERIAL LINES ARE AS FOLLOWS:
 - NCDOT FIBER OPTIC
 - FRONTIER COMMUNICATIONS (FIBER OPTIC & COPPER)



11/6/2011 11:26:43 AM
 R:\Roadway\Proje\310117_rdy_psh.dgn
 ID: 66165

-L-	
PI Sta 8+23.15	PI Sta 16+39.48
$\Delta = 2' 18'' 32.2''$ (RT)	$\Delta = 3' 59'' 42.6''$ (LT)
$D = 1' 13'' 27.4''$	$D = 3' 06'' 50.0''$
$L = 188.60'$	$L = 128.30'$
$T = 94.31'$	$T = 64.18'$
$R = 4,680.00'$	$R = 1,840.00'$

PROJECT REFERENCE		SHEET NO.	
17BP.5.R.54 - DURHAM 117		5	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED			
Prepared in the Office of:		M PO Box 700 FAYETTEVILLE, NC 27526 MOTT MACDONALD www.mottmac.com	
VERTICAL SCALE 5' 0 5' 10'		HORIZONTAL SCALE 25' 0 25' 50'	



BEGIN GRADE
STA. 5+85.00
EL = 325.07'

PI = 6+25.00
EL = 323.39'
VC = 80'
K = 15
DS = 25 MPH

PI = 10+30.00
EL = 284.25'
VC = 450'
K = 51
DS = 35 MPH

PI = 13+90.00
EL = 281.01'
VC = 180'
K = 128
DS = 55 MPH

PI = 16+95.00
EL = 282.57'
VC = 210'
K = 83
DS = 45 MPH

END GRADE
STA. 18+00.00
EL = 285.75'

BRIDGE @ STA. 15+31 -L-
SINGLE SPAN 24' PCCS
w/4' DEEP CAPS
1 @ 70' SKEW 90°
GP ELEV. = 281.73'

REMOVE EXISTING BRIDGE

3.5' KEY DEPTH (TYP.)

CLASS II RIP RAP
SLOPE 1.5:1 (2 FT. THICK)
(NORMAL TO CAP) (TYP.)

ELEV. = 275.0'

ELEV. = 275.0'

NORMAL WS
ELEV. = 270.5'

EXCAVATION = 130 CY
(STRUCTURE PAY ITEM)

BM #1 ELEVATION = 278.92'
RR SPIKE IN 20 INCH OAK
L STATION 12+86.00 32' LT
(SEE SHEET 1C-1)

BM #2 ELEVATION = 276.55'
RR SPIKE IN 24 INCH GUM
L STATION 15+94.00 36' LT
(SEE SHEET 1C-1)

BRIDGE HYDRAULIC DATA	
DESIGN DISCHARGE	= 2460 CFS
DESIGN FREQUENCY	= 50 YRS
DESIGN HW ELEVATION	= 279.8 FT
BASE DISCHARGE	= 2820 CFS
BASE FREQUENCY	= 100 YRS
BASE HW ELEVATION	= 280.7 FT
OVERTOPPING DISCHARGE	= 2900 CFS
OVERTOPPING FREQUENCY	= 100+ YRS
OVERTOPPING ELEVATION	= 281.3 FT
DATE OF SURVEY	= 10-30-2014
W.S. ELEVATION AT DATE OF SURVEY	= 270.5 FT



11/6/2017 11:26:46 AM
 R:\Roadway\Proje\310117_rdy_psh_pfl.dgn
 ID: 66165

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

TRANSPORTATION MANAGEMENT PLAN


DURHAM COUNTY

BRIDGE NO. 117 OVER MUD CREEK ON SR 1308 (CORNWALLIS ROAD)



SHEET NO.	TITLE
TMP-1	TITLE SHEET AND INDEX OF SHEETS
TMP-2	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, LEGEND, GENERAL NOTES AND PHASING
TMP-3	TEMPORARY TRAFFIC CONTROL PLAN
TMP-4	SPECIAL SIGN DESIGN

11/6/2017 11:30:47 AM
R:\Roadway\Proj\310117_TC_TMP_1.dgn
jor66165



PREPARED IN THE OFFICE OF MOTT MACDONALD
FOR NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

TIM JORDAN, PE *TRAFFIC CONTROL PROJECT ENGINEER*

BRIAN PHILLIPS *TRAFFIC CONTROL DESIGN ENGINEER*



M M
MOTT
MACDONALD


PO Box 700
Fuquay-Varina, NC 27526
(919) 552-2253
(919) 552-2254 (Fax)
www.mottmac.com/americas

LICENSE NO. F-0669

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

APPROVED: James Timothy Jordan
DATE: 11/7/2017

SEAL



17BP.5.R.54

TIP PROJECT:

TRAFFIC MANAGEMENT PLAN

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS, AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS OR RESULT IN DUPLICATE OR UNDESIRE OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING, OR REMOVAL OF DEVICES AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

LANE AND SHOULDER CLOSURE REQUIREMENTS

- A) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN 15 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN SHOULDER USING ROADWAY STANDARD DRAWING NO. 1101.04 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL OR A LANE CLOSURE IS INSTALLED.

TRAFFIC PATTERN ALTERATIONS

- B) NOTIFY THE ENGINEER, SCHOOLS AND EMS THIRTY (30) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.

SIGNING

- C) PROVIDE SIGNING AND DEVICES REQUIRED TO CLOSE THE ROAD ACCORDING TO THE ROADWAY STANDARD DRAWINGS AND TRAFFIC CONTROL PLANS.

PROVIDE SIGNING REQUIRED FOR THE OFF-SITE DETOUR ROUTE AS SHOWN IN THE TRAFFIC CONTROL PLANS.

- D) COVER OR REMOVE ALL SIGNS AND DEVICES REQUIRED TO CLOSE THE ROAD WHEN ROAD CLOSURE IS NOT IN OPERATION.

COVER OR REMOVE ALL SIGNS REQUIRED FOR THE OFF-SITE DETOUR WHEN THE DETOUR IS NOT IN OPERATION.

- E) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.

TRAFFIC CONTROL DEVICES

- F) PLACE TYPE III BARRICADES, WITH "ROAD CLOSED" SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.

PAVEMENT MARKINGS AND MARKERS

- G) INSTALL PAVEMENT MARKINGS AND MARKERS ON THE FINAL SURFACE ACCORDING TO THE ROADWAY STANDARD DRAWINGS.

- H) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

MISCELLANEOUS

- I) MAINTAIN ACCESS TO ALL RESIDENCES AND BUSINESSES BETWEEN THE CLOSURE POINTS AT ALL TIMES DURING CONSTRUCTION.

NCDOT ROADWAY STANDARD DRAWINGS



THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - HIGHWAY DESIGN BRANCH- N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:


STD. NO.	TITLE
1101.03	TEMPORARY ROAD CLOSURES
1101.04	TEMPORARY SHOULDER CLOSURES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1110.02	PORTABLE WORK ZONE SIGNS
1135.01	CONES
1145.01	BARRICADES
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION

PHASING

- STEP 1: PLACE MESSAGE SIGNS USING ROADWAY STANDARD DRAWING NUMBERS 1101.04, SHEET 1 OF 1, 1101.11, SHEET 1 OF 4, 1101.03, SHEET 1 OF 9, AND SHEET TMP-3, INSTALL AND COVER DETOUR SIGNING.
- STEP 2: USING ROADWAY STANDARD DRAWING NUMBER 1101.03, SHEET 1 OF 9, UNCOVER OFF-SITE DETOUR SIGNING AND INSTALL TYPE III BARRICADES TO CLOSE CORNWALLIS ROAD TO THRU TRAFFIC.
- STEP 3: PLACE TRAFFIC ONTO OFF-SITE DETOUR. PERFORM PROPOSED BRIDGE AND ROADWAY CONSTRUCTION. PLACE FINAL PAVEMENT MARKINGS AND MARKERS.
- STEP 4: REMOVE TYPE III BARRICADES FROM CORNWALLIS ROAD AND REOPEN ROADWAY TO TRAFFIC. REMOVE ALL DETOUR SIGNING.



11/6/2017 11:30:50 AM
 R:\Roadway\Proj\310117_TC_TMP-2.dgn
 jor66165

<p style="text-align: center; font-weight: bold; font-size: 1.2em;">M M</p> <p style="text-align: center; font-weight: bold; font-size: 0.8em;">MOTT MACDONALD</p> <p style="font-size: 0.7em;">PO Box 100 Fuquay-Varina, NC 27526 (919) 552-2253 (919) 552-2254 (Fax) www.hatchmott.com LICENSE NO. F-0669</p>	<p>APPROVED: <i>James Timothy Jarboe</i> DATE: 11/7/2017</p> <div style="text-align: center;">  <p>SEAL</p> </div>	<div style="text-align: center;">  <p>DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION WORK ZONE TRAFFIC CONTROL</p> </div>	<p>GENERAL NOTES ROADWAY STANDARD DRAWINGS PHASING</p>
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED			



NOTES: REFER TO ROADWAY STANDARD DRAWING NO. 1101.03, SHEET 1 OF 9, FOR ADDITIONAL SIGN SPACING REQUIREMENTS APPROACHING PROJECT SITE CLOSURE POINT.



* SEE SHEET TMP-4 FOR SPECIAL SIGN DESIGNS



USE CHANGEABLE MESSAGE SIGNS FOR A 7-DAY COUNTDOWN ROAD CLOSURE NOTICE PRIOR TO CLOSING CORNWALLIS ROAD TO THRU TRAFFIC.

INSTALL CHANGEABLE MESSAGE SIGNS AT THE DETOUR POINTS AND AS DIRECTED BY THE ENGINEER.

TRAFFIC CONTROL TEMPORARY SIGNING AND DEVICES



M M MOTT MACDONALD <small>PO Box 100 Fuquay-Varina, NC 27526 (919) 552-2253 (919) 552-2254 (Fax) www.hotchmott.com LICENSE NO. F-0669</small>	APPROVED: <i>James Timothy Jordan</i> DATE: 11/7/2017 		CORNWALLIS ROAD OFF-SITE DETOUR TRAFFIC CONTROL TEMPORARY SIGNING AND DEVICES
	SEAL DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		

11/6/2017 11:30:53 AM
 R:\Roadway\Proj\310117_TC_TMP-TMP-3.dgn
 jor66165

SIGN NUMBER: SD-1 TYPE: D QUANTITY: SEE PLANS SIGN WIDTH: 4'-6" HEIGHT: 2'-6" TOTAL AREA: 11.3 Sq.Ft. BORDER TYPE: INSET RECESS: 0.47" WIDTH: 0.63" RADII: 1.5" NO. Z BARS: LENGTH:	BACKG COLOR: Fluorescent Orange COPY COLOR: Black SYMBOL X Y WID HT MAT'L: 0.125" (3.2 mm) ALUMINUM	DESIGN BY: JTD PROJECT ID: 17BP.5.R.54	CHECKED BY: NKP DIV: 5	DATE: Jul 22, 2014
--	--	---	---------------------------	--------------------

BORDER
R=1.5"
TH=0.63"
IN=0.47"

Spacing Factor is 1 unless specified otherwise

LETTER POSITIONS

Letter locations are panel edge to lower left corner

Letter locations are panel edge to lower left corner											Series/Size	
C	O	R	N	W	A	L	L	I	S			Text Length
6.8	11.3	16	20.4	24.6	29.5	34.2	38.1	42	43.8			C 2000 40.4
R	O	A	D									Series/Size
18.7	23	27.2	31.9									C 2000 16.6


FILENAME: 310117_TC_TMP_SD1

NORTH CAROLINA D.O.T. SIGN DETAIL

11/6/2017 11:30:55 AM
R:\Roadway\Proj\310117_TC_TMP_4.dgn
jpr66165

<p>M M</p> <p>MOTT MACDONALD</p> <p>PO Box 100 Fuquay-Varina, NC 27526 (919) 552-2253 (919) 552-2254 (Fax) www.mottmac.com LICENSE NO. F-0669</p>	<p>APPROVED: <i>Russell W. Thompson</i> DATE: 11/7/2017</p> <p>SEAL</p>	<p>DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION WORK ZONE TRAFFIC CONTROL</p>	<p>SIGN DESIGN</p>
	<p>DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED</p>		

NAD 83/NA 2011



BEGIN CONSTRUCTION
-L- POT Sta. 5+00.00

NCDOT ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - HIGHWAY DESIGN BRANCH- N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTI-LANE ROADWAYS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.05	PAVEMENT MARKINGS - TURN LANES
1205.08	PAVEMENT MARKINGS - SYMBOLS AND WORD MESSAGES
1205.12	PAVEMENT MARKINGS - BRIDGES
1250.01	RAISED PAVEMENT MARKERS - INSTALLATION SPACING
1251.01	RAISED PAVEMENT MARKERS - PERMANENT AND TEMPORARY

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	QUANTITY
TA	THERMOPLASTIC WHITE EDGELINE (4", 90 MILS)	2,430 LF
TD	THERMOPLASTIC 3 FT.-9FT./SP MINISKIP (4", 120 MILS)	60 LF
TE	THERMOPLASTIC WHITE SOLID LANE LINE (4", 120 MILS)	75 LF
TI	THERMOPLASTIC YELLOW DOUBLE CENTER (4", 120 MILS)	2,430 LF
T2	THERMOPLASTIC WHITE STOPBAR (24", 120 MILS)	45 LF
UA	THERMOPLASTIC PAVEMENT MARKING SYMBOL-LEFT TURN ARROW (90 MILS)	1 EA
UE	THERMOPLASTIC PAVEMENT MARKING SYMBOL-COMBO STRAIGHT/RIGHT (90 MILS)	1 EA
MA	PERMANENT RAISED PAVEMENT MARKERS (YELLOW & YELLOW)	15 EA

11/7/2017 6:56:38 AM
 R:\Roadway\Proj\310117_TC_TMP_PMP-1.dgn
 jpr66165

<p>M M MOTT MACDONALD</p> <p>PO Box 100 Fuquay-Varina, NC 27526 (919) 552-2253 (919) 552-2254 (Fax) www.hatchmott.com LICENSE NO. F-0669</p>	<p>APPROVED: <i>Russell W. Thompson</i> DATE: 11/7/2017</p> <p>SEAL</p>		<p>PAVEMENT MARKING PLANS PAVEMENT MARKING STANDARDS PAVEMENT MARKING SCHEDULE</p>
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED			



STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.5.R.54	EC-1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	

TIP PROJECT: 17BP.5.R.54

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS
 PLAN FOR PROPOSED
 HIGHWAY EROSION CONTROL

DURHAM COUNTY

BRIDGE NO.117 OVER MUD CREEK ON
 SR 1508 (CORNWALLIS ROAD)



EROSION AND SEDIMENT CONTROL MEASURES


Std. #	Description	Symbol
1630.03	Temporary Silt Ditch	TD
1630.05	Temporary Diversion	TD
1605.01	Temporary Silt Fence	
1606.01	Special Sediment Control Fence	▾ ▾ ▾ ▾ ▾ ▾ ▾
1622.01	Temporary Berms and Slope Drains	— — — — —
1630.02	Silt Basin Type B	▭
1633.01	Temporary Rock Silt Check Type-A	▭ with mesh pattern
	Temporary Rock Silt Check Type-A with Matting and Polyacrylamide (PAM)	▭ with mesh and PAM symbol
1633.02	Temporary Rock Silt Check Type-B	▭ with wattle symbol
	Wattle / Coir Fiber Wattle	▭ with wattle symbol
	Wattle / Coir Fiber Wattle with Polyacrylamide (PAM)	▭ with wattle and PAM symbol
1634.01	Temporary Rock Sediment Dam Type-A	▭ with dam symbol
1634.02	Temporary Rock Sediment Dam Type-B	▭ with dam symbol
1635.01	Rock Pipe Inlet Sediment Trap Type-A	U-shape symbol
1635.02	Rock Pipe Inlet Sediment Trap Type-B	U-shape symbol
1630.04	Stilling Basin	▭ with basin symbol
1630.06	Special Stilling Basin	▭ with basin symbol
	Rock Inlet Sediment Trap:	
1632.01	Type A	A
1632.02	Type B	B
1632.03	Type C	C
	Skimmer Basin	▭ with skimmer symbol
	Tiered Skimmer Basin	▭ with tiered skimmer symbol
	Infiltration Basin	▭ with infiltration symbol

THIS PROJECT CONTAINS EROSION CONTROL PLANS FOR CLEARING AND GRUBBING PHASE OF CONSTRUCTION.

THIS PROJECT HAS BEEN DESIGNED TO SENSITIVE WATERSHED STANDARDS.

ENVIRONMENTALLY SENSITIVE AREA(S) EXIST ON THIS PROJECT
 Refer To E. C. Special Provisions for Special Considerations.

GRAPHIC SCALE



THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY WITH THE REGULATIONS SET FORTH BY THE NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011 AND ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES DIVISION OF WATER RESOURCES.

Prepared In the Office of:
ICA ENGINEERING
 5121 KINGDOM WAY, SUITE 100
 RALEIGH NC 27607
 NC License No. F-0258

Designed by:
KYLE M. STOFFER, EI **3844**

NAME LEVEL III CERTIFICATION NO.

Reviewed In the Office of:
ROADSIDE ENVIRONMENTAL UNIT
 1 South Wilmington St.
 Raleigh, NC 27611

2012 STANDARD SPECIFICATIONS

Reviewed by:
DONALD R. PEARSON, EI

Roadway Standard Drawings


The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N. C. Department of Transportation - Raleigh, N. C., dated January 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

1604.01 Railroad Erosion Control Detail	1632.01 Rock Inlet Sediment Trap Type A
1605.01 Temporary Silt Fence	1632.02 Rock Inlet Sediment Trap Type B
1606.01 Special Sediment Control Fence	1632.03 Rock Inlet Sediment Trap Type C
1607.01 Gravel Construction Entrance	1633.01 Temporary Rock Silt Check Type A
1622.01 Temporary Berms and Slope Drains	1633.02 Temporary Rock Silt Check Type B
1630.01 Riser Basin	1634.01 Temporary Rock Sediment Dam Type A
1630.02 Silt Basin Type B	1634.02 Temporary Rock Sediment Dam Type B
1630.03 Temporary Silt Ditch	1635.01 Rock Pipe Inlet Sediment Trap Type A
1630.04 Stilling Basin	1635.02 Rock Pipe Inlet Sediment Trap Type B
1630.05 Temporary Diversion	1640.01 Coir Fiber Baffle
1630.06 Special Stilling Basin	1645.01 Temporary Stream Crossing
1631.01 Matting Installation	


_LIBR_2014_11/16/2017_11:54:38 AM ERN... \cadda\31017_hyd_erosion..._tah.dgn

PROJECT REFERENCE NO. 17BP.5.R.54	SHEET NO. EC-2
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

TEMPORARY ROCK SILT CHECK TYPE 'A' WITH EXCELSIOR MATTING AND POLYACRYLAMIDE (PAM)



PLAN



SECTION A-A


NOTES:

INSTALL TEMPORARY ROCK SILT CHECK TYPE A IN ACCORDANCE WITH ROADWAY STANDARD DRAWING NO. 1633.01.


USE EXCELSIOR FOR MATTING MATERIAL AND ANCHOR MATTING SECTION AT TOP AND BOTTOM WITH CLASS B STONE.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH ROCK SILT CHECK.

INITIALLY APPLY 4 OUNCES OF POLYACRYLAMIDE (PAM) TO TOP OF MATTING SECTION AND AFTER EVERY RAINFALL EVENT THAT EQUALS OR EXCEEDS 0.50 INCHES.



INSET A



SECTION B-B

NOT TO SCALE


DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

PROJECT REFERENCE NO. <i>17BP.5.R.54</i>	SHEET NO. <i>EC-3A</i>
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER


SOIL STABILIZATION TIMEFRAMES

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

**CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 04**



NAD 83/NA 2011



NOTE: ALL CHANNEL RELOCATION WORK BETWEEN 8+05 RT AND 8+90 RT WILL NEED TO BE COMPLETED IN THE DRY. UTILIZE IMPERVIOUS DIKES AND CLEAN WATER DIVERSIONS OR A PUMP AROUND WITH SPECIAL STILLING BASINS TO ENSURE THERE IS NO SEDIMENT TRANSPORT OUTSIDE OF PROJECT LIMITS. ONCE ALL CHANNEL RELOCATION WORK HAS BEEN COMPLETED AND STABILIZED WATER CAN BE DIVERTED INTO THE NEW CHANNEL LOCATION. ALL CHANNEL RELOCATION WORK TO BE CONSIDERED INCIDENTAL TO CONSTRUCTION.

- NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE: PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING R/W OR EASEMENT.



-L-	
PI Sta 8+23.15	PI Sta 16+39.48
$\Delta = 2' 18" 32.2" (RT)$	$\Delta = 3' 59" 42.6" (LT)$
$D = 1' 13" 27.4"$	$D = 3' 06" 50.0"$
$L = 188.60'$	$L = 128.30'$
$T = 94.31'$	$T = 64.18'$
$R = 4,680.00'$	$R = 1,840.00'$

\$DATE\$\$ 11/6/2017
 J:\Hydro\DDC\Division-5-L\IBR-2014\310117\Hydraulics\Erosion Contr-ol\cadd\310117-hyd-erosion-c&g.dgn
 ICA ENGINEERING, INC.





LEVEL III CERTIFIED BY:
 KYLE M. STOFFER, E.I.
 CERTIFICATION NUMBER: 3844
 ISSUED: SEPTEMBER 8, 2017

Prepared in the Office of:

 Mott MacDonald



 ICA Engineering, Inc.
 3121 Kingdom Way, Suite 100
 Raleigh, NC 27407
 NC License No. F-0258

HORIZONTAL SCALE
 25' 0 25' 50'



NAD 83/NA 2011

FINAL EROSION CONTROL
 FOR CONSTRUCTION SHEET 04



NOTE: ALL CHANNEL RELOCATION WORK BETWEEN 8+05 RT AND 8+90 RT WILL NEED TO BE COMPLETED IN THE DRY. UTILIZE IMPERVIOUS DIKES AND CLEAN WATER DIVERSIONS OR A PUMP AROUND WITH SPECIAL STILLING BASINS TO ENSURE THERE IS NO SEDIMENT TRANSPORT OUTSIDE OF PROJECT LIMITS. ONCE ALL CHANNEL RELOCATION WORK HAS BEEN COMPLETED AND STABILIZED WATER CAN BE DIVERTED INTO THE NEW CHANNEL LOCATION. ALL CHANNEL RELOCATION WORK TO BE CONSIDERED INCIDENTAL TO CONSTRUCTION.

-L- PI Sta 8+23.15	PI Sta 16+39.48
Δ = 2° 18' 32.2" (RT)	Δ = 3° 59' 42.6" (LT)
D = 1' 13' 27.4"	D = 3' 06' 50.0"
L = 188.60'	L = 128.30'
T = 94.31'	T = 64.18'
R = 4,680.00'	R = 1,840.00'

11/6/2017
 J:\Hydro\DDC\05\vision_5.L\IBR_2014\310117\Hydraulics\Erosion Contr-ol\cadd\310117-hyd-erosion_final.dgn
 ICA ENGINEERING, INC.


STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.5.R.54	RF-1	
STATE PROJ.NO.	F.A.PROJ.NO.	DESCRIPTION	

PLANTING DETAILS


SEEDLING / LINER BAREROOT PLANTING DETAIL

HEALING IN


1. Locate a healing-in site in a shady, well protected area.
2. Excavate a flat bottom trench 12 inches deep and provide drainage.




3. Backfill the trench with 2 inches well rotted sawdust. Place a 2 inch layer of well rotted sawdust at a sloping angle at one end of the trench.



4. Place a single layer of plants against the sloping end so that the root collar is at ground level.




5. Place a 2 inch layer of well rotted sawdust over the roots maintaining a sloping angle.




6. Repeat layers of plants and sawdust as necessary and water thoroughly.

DIBBLE PLANTING METHOD USING THE KBC PLANTING BAR



1. Insert planting bar as shown and pull handle toward planter.
2. Remove planting bar and place seedling at correct depth.
3. Insert planting bar 2 inches toward planter from seedling.




4. Pull handle of bar toward planter, firming soil at bottom.
5. Push handle forward firming soil at top.
6. Leave compaction hole open. Water thoroughly.

PLANTING NOTES:

PLANTING BAG
During planting, seedlings shall be kept in a moist canvas bag or similar container to prevent the root systems from drying.



KBC PLANTING BAR
Planting bar shall have a blade with a triangular cross section, and shall be 12 inches long, 4 inches wide and 1 inch thick at center.



ROOT PRUNING
All seedlings shall be root pruned, if necessary, so that no roots extend more than 10 inches below the root collar.

REFORESTATION

- TREE REFORESTATION SHALL BE PLANTED 6 FT. TO 10 FT. ON CENTER, RANDOM SPACING, AVERAGING 8 FT. ON CENTER, APPROXIMATELY 680 PLANTS PER ACRE.

REFORESTATION


MIXTURE, TYPE, SIZE, AND FURNISH SHALL CONFORM TO THE FOLLOWING:

25%	LIRIODENDRON TULIPIFERA	TULIP POPLAR	12 in - 18 in BR
25%	PLATANUS OCCIDENTALIS	SYCAMORE	12 in - 18 in BR
25%	FRAXINUS PENNSYLVANICA	GREEN ASH	12 in - 18 in BR
25%	BETULA NIGRA	RIVER BIRCH	12 in - 18 in BR


REFORESTATION DETAIL SHEET

N.C.D.O.T. - ROADSIDE ENVIRONMENTAL UNIT

PHASING DIAGRAM



EV PREEMPT PHASES



PHASING DIAGRAM DETECTION LEGEND

- DETECTED MOVEMENT
- ◄ UNDETECTED MOVEMENT (OVERLAP)
- ◄ UNSIGNALIZED MOVEMENT
- ◄ PEDESTRIAN MOVEMENT

TABLE OF OPERATION

SIGNAL FACE	PHASE			
	02+6	04+8	EVB (08)	FLASH
21,22	G	R	R	Y
41,42	R	G	R	R
61,62	G	R	R	Y
81	R	G	←	R
82	R	G	G	R

W - Walk
DW - Don't Walk
DRK - Dark

2033 SOFTWARE w/ 2070 CONTROLLER
LOOP & DETECTOR UNIT INSTALLATION CHART

LOOP NO.	SIZE (ft)	TURNS	DIST. FROM STOPBAR (ft)	NEW EXISTING	NEMA PHASE	DETECTOR PROGRAMMING												STATUS											
						TIMING		ATTRIBUTES										NEW	EXISTING										
						DELAY	CARRY (STRETCH)	1	2	3	4	5	6	7	8	9	10			11	12								
2A	6X6	4	300	-X	2	- SEC.	- SEC.	-	-	-	-	-	-	-	-	-	-	-	-	X	-								
4A	6X6	4	300	-X	4	- SEC.	2.0 SEC.	-	-	-	-	-	-	-	-	-	-	-	-	-	-	X							
4B	6X50	2-4-2	+5	-X	4	5 SEC.	- SEC.	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	X						
4C	6X60	2-4-2	+5	-X	4	10 SEC.	- SEC.	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	X					
6A	6X6	4	300	-X	6	- SEC.	- SEC.	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	X				
8A	6X6	4	300	-X	8	- SEC.	2.0 SEC.	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	X			
8B	6X40	2-4-2	+5	-X	8	5 SEC.	- SEC.	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	X		
8C	6X40	2-4-2	+5	-X	8	10 SEC.	- SEC.	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	X	
8D	6X6	4	0	-X	8	15 SEC.	- SEC.	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	X



2 Phase Fully Actuated w/ Fire Preemption (Durham Signal System)

NOTES

- Refer to "Roadway Standard Drawings NCDOT" dated July 2012 and "Standard Specifications for Roads and Structures" dated July 2012.
- Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supercede these values.
- When in flashing mode, all signal heads for the same approach shall flash concurrently.
- Fire Preempt approach WB Route #111.
- Install 2070E controller into existing cabinet.
- Pavement markings are existing.
- Do not program signal for late night flashing operations unless otherwise directed by the Engineer.
- Reposition existing signal heads numbered #41 and 42.
- Set all detector units to presence mode.
- This intersection features an optical preemption system. Shown locations of optical detectors are conceptual only.

SIGNAL FACE I.D.

All Heads L.E.D.



2033 SOFTWARE w/ 2070 CONTROLLER

PHASE	02	04	06	08
MINIMUM INITIAL *	15 SEC.	7 SEC.	15 SEC.	7 SEC.
VEHICLE EXTENSION *	2.0 SEC.	1.0 SEC.	2.0 SEC.	1.0 SEC.
YELLOW CHANGE INT.	4.6 SEC.	4.7 SEC.	4.4 SEC.	4.5 SEC.
RED CLEARANCE	1.3 SEC.	1.0 SEC.	1.2 SEC.	1.0 SEC.
MAXIMUM LIMIT *	60 SEC.	30 SEC.	60 SEC.	30 SEC.
RECALL POSITION	VEH. RECALL	NONE	VEH. RECALL	NONE
VEHICLE CALL MEMORY	YELLOW LOCK	NONLOCK	YELLOW LOCK	NONLOCK
DOUBLE ENTRY	OFF	ON	OFF	ON
WALK *	- SEC.	- SEC.	- SEC.	- SEC.
FLASHING DON'T WALK	- SEC.	- SEC.	- SEC.	- SEC.
TYPE 3 LIMIT	- SEC.	- SEC.	- SEC.	- SEC.
ALTERNATE EXTENSION	- SEC.	- SEC.	- SEC.	- SEC.
ADD PER VEHICLE *	- SEC.	- SEC.	- SEC.	- SEC.
MAXIMUM INITIAL *	- SEC.	- SEC.	- SEC.	- SEC.
MAXIMUM GAP*	7.0 SEC.	1.0 SEC.	7.0 SEC.	1.0 SEC.
REDUCE 0.1 SEC EVERY *	1.5 SEC.	- SEC.	1.5 SEC.	- SEC.
MINIMUM GAP	- SEC.	1.0 SEC.	- SEC.	1.0 SEC.

2033 EV PREEMPTION TIMING

FUNCTION	EVB (08) SECONDS
DELAY BEFORE PREEMPT	0
PED. CLEAR BEFORE PREEMPT	-
MIN. GREEN BEFORE PREEMPT	1
CLEARANCE TIME	7
PREEMPT EXTEND**	2.0

** Program Timing on Optical Detector Unit

LEGEND

PROPOSED	EXISTING

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not be lower than 4 seconds.

SIGNAL UPGRADE

MOTT MACDONALD
750 N. Greenfield Pkwy, Garner, NC 27529
P: (919) 552-2253
F: (919) 552-2254
www.mottmac.com/america
License No. F-0655

Prepared in the Offices of:
TRANSPORTATION MOBILITY AND SAFETY DIVISION
DEPARTMENT OF TRANSPORTATION
STATE OF NORTH CAROLINA
Signal Design Section

SR 1306 (Erwin Rd)
at
SR 1308 (W. Cornwallis Rd)

Division 5 Durham County Durham

PLAN DATE: SEPTEMBER 2017 REVIEWED BY: RWT

PREPARED BY: RTP REVIEWED BY:

REVISIONS

INIT. DATE

Seal: RUSSELL W. THOMPSON, PROFESSIONAL ENGINEER, SEAL 032711


DocuSigned by: Russell W. Thompson 09/27/2017

SIG. INVENTORY NO. 05-1438

9/26/2017 2:40:35 PM J:\17BP.5.R.54\roadway\Traffic Signal\Cornwallis @ Erwin.dgn User: JAT78450

EDI MODEL 2010ECL-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
- Make sure jumpers SEL2-SEL5 are present on the monitor board.

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Ensure that Red Enable is active at all times during normal operation. To prevent Red Failure on unused monitor channels, tie unused red monitor unputs 1,3, 5,7,9,10,11,12,13,14,15 & 16 to load switch AC+ per the cabinet manufacturer's instructions.
- Program controller to startup in phase 2 green.
- Set power-up flash time to 10 seconds and implement within the controller programming.
- Enable simultaneous gap-out feature for all phases.
- Set the Red Revert interval on the controller unit to 1 second.
- Program phases 4 and 8 on the controller unit for Double Entry.
- Ensure startup flash phases are coordinated with flash program block assignments.
- This controller and cabinet are part of the Durham City System.

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET332 W/ AUX FILE
 SOFTWAREECONOLITE OASIS
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS..18 (12-STD, 6-AUX)
 LOAD SWITCHES USED....S2,S4,S6,S8
 PHASES USED.....2,4,6,8
 OVERLAPS.....NONE

SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S2P	S3	S4	S4P	S5	S6	S6P	S7	S8	S8P	S9	S10	S11	S12	S13	S14
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OLA	OLB	SPARE	OLC	OLD	SPARE
SIGNAL HEAD NO.	NU	21,22	NU	NU	41,42	NU	NU	61,62	NU	NU	81,82	NU	NU	NU	NU	NU	NU	NU
RED		128			101			134			107							
YELLOW		129			102			135			108							
GREEN		130			103			136			109							
RED ARROW																		
YELLOW ARROW																		
GREEN ARROW																		
Hand icon																		
Person icon																		

NU = Not Used


EMERGENCY VEHICLE PREEMPTION PROGRAMMING

E. V. PREEMPT	OPTICAL DETECTOR	TERMINAL
EVB	B	TB9-7,9

- PROGRAM PREEMPTION INPUT PIN AS FOLLOWS:
 MAIN MENU > (5) INPUTS > (3) PREEMPTS
 EVB = 72
- PROGRAM CLEARANCE PHASES AND TIMING AS FOLLOWS:
 MAIN MENU > (2) PREEMPTS > (4) EMERGENCY VEHICLE
 EVB DELAY = 0
 EVB CLEAR = 1
 EVB CLEARANCE PHASE = 2
- PROGRAM MINIMUM GREEN BEFORE PREEMPT AS FOLLOWS:
 MAIN MENU > (2) PREEMPTS > (6) MISC PREEMPTION PARAMETERS
 MIN TIME BEFORE PE FORCEOFF = 1
- PROGRAM EXTEND TIME ON OPTICAL DETECTOR UNIT FOR 2 SEC.

INPUT FILE POSITION LAYOUT

(front view)




EX.: 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE
 ST = STOP TIME
 PRE = PREEMPT

INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND TIME	DELAY TIME	DETECTOR TYPE
2A	TB2-5,6	I2U	39	1	2	YES			S
4A	TB4-9,10	I6U	41	3	4	YES	2,75		S
4B	TB4-11,12	I6L	45	7	4	YES		5	S
4C	TB6-1,2	I7U	65	23	4	YES		10	S
6A	TB3-5,6	J2U	40	2	6	YES			S
8A	TB5-9,10	J6U	42	4	8	YES	2,75		S
8B	TB5-11,12	J6L	46	8	8	YES		5	S
8C	TB7-1,2	J7U	66	24	8	YES		10	S
8D	TB7-3,4	J7L	79	32	8	YES		15	S


INPUT FILE POSITION LEGEND: J2L



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 05-1438
 DESIGNED: AUGUST 2017
 SEALED: XX/XX/2017
 REVISED: N/A

TYPICAL TOMAR FIELD WIRE DETAIL

(input file, rear view)



Electrical Details

MOTT MACDONALD
 PO Box 700
 Fuquay-Varina, NC 27526
 www.mtd11nc.com
 License No. F-0669

SR 1306 (Erwin Rd)
 at
 SR 1308 (Cornwallis Rd)

Division 5 Durham County Durham

PLAN DATE: AUGUST 2017 REVIEWED BY: RWT

PREPARED BY: RTP REVIEWED BY:


REVISIONS	INIT.	DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED


SIGNATURE: _____ DATE: _____

SIG. INVENTORY NO. 05-1438

NOTE:
ALL PROPOSED UTILITY WORK SHOWN ON THIS SHEET WILL BE DONE BY OTHERS




UTILITIES BY OTHERS




11/6/2017 11:59:00 AM
 I:\Projects\Hatch_Mott_MacDonald\17BP5R54_Durham_117\310117_Rw_Plans_Revise\Second\310117_util_Uo0_sketch.dgn
 harris


-L-	-L-
PI Sta 8+23.15	PI Sta 16+39.48
Δ = 2' 18" 32.2" (RT)	Δ = 3' 59" 42.6" (LT)
D = 1' 13" 27.4"	D = 3' 06" 50.0"
L = 188.60'	L = 128.30'
T = 94.31'	T = 64.18'
R = 4,680.00'	R = 1,840.00'

- NOTES
- NO GAS IN PROJECT LIMITS ACCORDING TO PSNC ENERGY (CONTACT: STEVE CAIN 919-367-2710/SCAIN@SCANA.COM)
 - U/G TELEPHONE & U/G TELEVISION POSSIBLY ABANDONED ACCORDING TO FRONTIER COMMUNICATIONS (CONTACT: RALPH PERRY 919-323-9376/RPERRY@SMOSE.COM)
 - TWO TELEPHONE DROPS ON POLE (UNTRACABLES) POSSIBLY ABANDONED ACCORDING TO FRONTIER COMMUNICATIONS (CONTACT: RALPH PERRY 919-323-9376/RPERRY@SMOSE.COM)
 - THE AERIAL LINES ARE AS FOLLOWS:
-NCDOT FIBER OPTIC
-FRONTIER COMMUNICATIONS (FIBER OPTIC & COPPER)







10/17/2017 6:11:09 AM
 R:\G:\p05045\Xsc\Xpl\310117_rdy_xpl.dgn
 0/60/03




150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150




9 + 00.00




8 + 50.00




8 + 00.00




7 + 50.00




150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150




10/17/2017 6:11:10 AM
 R:\G:\p05045\Xsc\Xpl\310117-rdy-xpl.dgn
 dwg 60103



10/17/2017 6:11:10 AM
 R:\G00000000\Xsc\Xpl\310117_rdy_xpl.dgn
 0/6000



150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



16+00.00
END BRIDGE 15+67.13

15+50.00


15+00.00
BEGIN BRIDGE 14+94.88

14+50.00

14+10.00

10/17/2017 6:11:10 AM
 R:\G00000000\Xsc\Xpl\310117-rdy-xpl.dgn
 0:60:00

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150




10/17/2017 6:11:10 AM
 R:\G00000000\Xsc\Xpl\310117_rdy_xpl.dgn
 0/6000


11/6/2017 12:04:03 PM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401.17BP5R54_SMJ_GD.dgn

PROJ:17BP.5.R.54

DRAWN BY: T. BANKOVICH DATE: 10-17
 CHECKED BY: B.S. COX DATE: 10-17
 DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17



SECTION ALONG Q SURVEY -L-



PLAN
(PILES NOT SHOWN IN PLAN VIEW)

GRADE DATA -L-

(-0.9000%	(+0.5115%
PVI STA. 13+90.00 EL. = 281.01 VC = 180'	
(+0.5115%	(+3.0286%
PVI STA. 16+95.00 EL. = 282.57 VC = 210'	

HYDRAULIC DATA:

DESIGN DISCHARGE	= 2460 CFS
FREQUENCY OF DESIGN FLOOD	= 50 YEAR
DESIGN HIGH WATER ELEVATION	= 279.8
DRAINAGE AREA	= 3.4 SQ. MI.
BASE DISCHARGE (Q 100)	= 2820 CFS
BASE HIGH WATER ELEVATION	= 280.7

OVERTOPPING FLOOD DATA:

OVERTOPPING DISCHARGE	= 2900
FREQUENCY OF OVERTOPPING FLOOD	= 100+ YEAR
OVERTOPPING FLOOD ELEVATION	= 281.3 **
** OVERTOPPING OCCURS AT ROADWAY STA. 14+15.00 -L- HIGH SIDE (RIGHT)	

HORIZONTAL CURVE DATA

PI STA. 16+39.48 -L-
$\Delta = 3^{\circ}-59'-42.6''$ (LT.)
$D = 3^{\circ}-06'-50.0''$
$L = 128.30'$
$T = 64.18'$
$R = 1840.00'$

I HEREBY CERTIFY THESE PLANS ARE THE AS-BUILT PLANS

PROJECT NO. 17BP.5.R.54
 DURHAM COUNTY
 STATION: 15+31.00 -L-


SHEET 1 OF 2 REPLACES BRIDGE #117

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

GENERAL DRAWING

FOR BRIDGE ON SR 1308 (CORNWALLIS RD.) OVER MUD CREEK BETWEEN SR 1306 AND US 15/501
 36'-6" CLEAR ROADWAY - 90° SKEW


PLANS PREPARED BY:
SE & A
 IMPSON ENGINEERS ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.slmpsonengr.com
 LICENSURE NO. C-2521



REVISIONS				SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

TOTAL SHEETS: 18

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



LOCATION SKETCH

NOTES:

- ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING.
- THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.
- THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.
- FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.
- FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.
- REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED SO AS NOT TO ALLOW DEBRIS TO FALL INTO THE WATER. THE CONTRACTOR SHALL REMOVE THE BRIDGE AND SUBMIT PLANS FOR DEMOLITION IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.
- THE MATERIAL SHOWN IN THE CROSS-HATCHED AREA SHALL BE EXCAVATED FOR A DISTANCE OF 45 FT. LEFT AND 40 FT. RIGHT OF CENTERLINE ROADWAY AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR UNCLASSIFIED STRUCTURE EXCAVATION. SEE SECTION 412 OF THE STANDARD SPECIFICATIONS.
- THE EXISTING STRUCTURE CONSISTS OF 3 SPANS, 1 @ 17'-4", 1 @ 17'-1" AND 1 @ 17'-8". THE SUPERSTRUCTURE HAS A CLEAR ROADWAY WIDTH OF 25'-2" WITH TIMBER DECK ON TIMBER JOISTS. THE END BENTS AND INTERIOR BENTS CONSIST OF TIMBER CAPS ON TIMBER PILES (SOME WITH CONCRETE ENCASEMENT). THE EXISTING STRUCTURE, WHICH IS LOCATED AT THE SITE OF THE PROPOSED STRUCTURE, SHALL BE REMOVED. THE EXISTING BRIDGE IS PRESENTLY POSTED FOR LOAD LIMIT. SHOULD THE STRUCTURAL INTEGRITY OF THE BRIDGE DETERIORATE DURING CONSTRUCTION OF THE PROPOSED BRIDGE, THE LOAD LIMIT MAY BE REDUCED AS FOUND NECESSARY DURING THE LIFE OF THE PROJECT.
- THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.
- THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH "HEC 18-EVALUATING SCOUR AT BRIDGES."
- FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.
- FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
- FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
- FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
- ASPHALT WEARING SURFACE IS INCLUDED IN ROADWAY QUANTITY ON ROADWAY PLANS.
- FOR ASBESTOS ASSESSMENT FOR BRIDGE DEMOLITION AND RENOVATION ACTIVITIES, SEE SPECIAL PROVISIONS.
- AT THE CONTRACTOR'S OPTION, PRESTRESSED CONCRETE END BENT CAPS MAY BE SUBSTITUTED IN PLACE OF THE CAST-IN-PLACE CAPS. THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER TO RECEIVE REVISED PLANS AND DETAILS FROM THE STRUCTURES MANAGEMENT UNIT. THE REDESIGN AND ANY ADDITIONAL MATERIALS NEEDED WILL BE AT NO ADDITIONAL COST TO THE CONTRACTOR.
- THE EFFECTS OF THE HORIZONTAL CURVE ARE NEGLIGIBLE IN THE CONSTRUCTION OF THE APPROACH SLAB AT END BENT 2.
- CONTRACTOR MUST COMPLETELY REMOVE EXISTING TIMBER PILES OR AT LEAST ONE FOOT BELOW THE MUD LINE.

TOTAL BILL OF MATERIAL

	REMOVAL OF EXISTING STRUCTURE	UNCLASSIFIED STRUCTURE EXCAVATION	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL	PILE DRIVING EQUIPMENT SETUP FOR HP 12 X 53 STEEL PILES	HP 12 X 53 STEEL PILES		STEEL PILE POINTS	TWO BAR METAL RAIL	1'-2" X 2'-9/2" CONCRETE PARAPET	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE	ELASTOMERIC BEARINGS	3'-0" X 2'-0" PRESTRESSED CONCRETE CORED SLABS		ASBESTOS ASSESSMENT
							NO.	LF							NO.	LF	
SUPERSTRUCTURE	LS	LS	CY	LS	LB	EA											
END BENT 1		LS	24.2		2,924	7	7	105	7	125.00	140.00	90	100	LS	13	910.00	
END BENT 2		LS	24.2		2,924	7	7	105	7			95	105				
TOTAL	LS	LS	48.4	LS	5,848	14	14	210	14	125.00	140.00	185	205	LS	13	910.00	LS

FOR PILES, SEE GEOTECHNICAL SPECIAL PROVISIONS AND SECTION 450 OF THE STANDARD SPECIFICATIONS.

PILES AT END BENT 1 AND END BENT 2 ARE DESIGNED FOR A FACTORED RESISTANCE OF 88 TONS PER PILE.

DRIVE PILES AT END BENT 1 AND END BENT 2 TO A REQUIRED DRIVING RESISTANCE OF 150 TONS PER PILE.

STEEL H-PILE POINTS ARE REQUIRED FOR STEEL H-PILES AT END BENT 1 AND END BENT 2. FOR STEEL PILE POINTS, SEE SECTION 450 OF THE STANDARD SPECIFICATIONS.


IT HAS BEEN ESTIMATED THAT A HAMMER WITH AN EQUIVALENT RATED ENERGY IN THE RANGE OF 35 TO 45 FT-KIPS PER BLOW WILL BE REQUIRED TO DRIVE PILES AT END BENT 1 AND END BENT 2. THIS ESTIMATED ENERGY RANGE DOES NOT RELEASE THE CONTRACTOR FROM PROVIDING DRIVING EQUIPMENT IN ACCORDANCE WITH SUBARTICLE 450-3(D)(2) OF THE STANDARD SPECIFICATIONS.

PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
 STATION: 15+31.00 -L-

SHEET 2 OF 2

PLANS PREPARED BY:

SIMPSON ENGINEERS & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

GENERAL DRAWING

FOR BRIDGE ON SR 1308
 (CORNWALLIS RD.) OVER
 MUD CREEK
 BETWEEN SR 1306 AND US 15/501
 36'-6" CLEAR ROADWAY - 90° SKEW

REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			S-2
2			4			TOTAL SHEETS 18

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

11/6/2017 12:04:03 PM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SML_GD.dgn

10/17/2017 11:47:28 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SML_LRFR.dgn

LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR PRESTRESSED CONCRETE GIRDERS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE										SERVICE III LIMIT STATE					COMMENT NUMBER			
						MOMENT					SHEAR					MOMENT								
						LIVELOAD FACTORS	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	LIVELOAD FACTORS	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN		GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	
DESIGN LOAD RATING	HL-93(Inv)	N/A	1	1.006	--	1.75	0.273	1.03	70'	EL	34.5	0.507	1.32	70'	EL	6.9	0.80	0.273	1.01	70'	EL	34.5		
	HL-93(0pr)	N/A	--	1.341	--	1.35	0.273	1.34	70'	EL	34.5	0.507	1.72	70'	EL	6.9	N/A	--	--	--	--	--		
	HS-20(Inv)	36.000	2	1.306	47.02	1.75	0.273	1.34	70'	EL	34.5	0.507	1.65	70'	EL	6.9	0.80	0.273	1.31	70'	EL	34.5		
	HS-20(0pr)	36.000	--	1.74	62.64	1.35	0.273	1.74	70'	EL	34.5	0.507	2.14	70'	EL	6.9	N/A	--	--	--	--	--		
LEGAL LOAD RATING	SV	SNSH	13.500	--	2.917	39.379	1.4	0.273	3.75	70'	EL	34.5	0.507	4.87	70'	EL	6.9	0.80	0.273	2.92	70'	EL	34.5	
		SNGARBS2	20.000	--	2.187	43.741	1.4	0.273	2.81	70'	EL	34.5	0.507	3.47	70'	EL	6.9	0.80	0.273	2.19	70'	EL	34.5	
		SNAGRIS2	22.000	--	2.077	45.69	1.4	0.273	2.67	70'	EL	34.5	0.507	3.23	70'	EL	6.9	0.80	0.273	2.08	70'	EL	34.5	
		SNCOTTS3	27.250	--	1.452	39.565	1.4	0.273	1.87	70'	EL	34.5	0.507	2.43	70'	EL	6.9	0.80	0.273	1.45	70'	EL	34.5	
		SNAGGRS4	34.925	--	1.218	42.554	1.4	0.273	1.57	70'	EL	34.5	0.507	2.03	70'	EL	6.9	0.80	0.273	1.22	70'	EL	34.5	
		SNS5A	35.550	--	1.191	42.346	1.4	0.273	1.53	70'	EL	34.5	0.507	2.06	70'	EL	6.9	0.80	0.273	1.19	70'	EL	34.5	
		SNS6A	39.950	--	1.095	43.747	1.4	0.273	1.41	70'	EL	34.5	0.507	1.88	70'	EL	6.9	0.80	0.273	1.10	70'	EL	34.5	
	TTST	SNS7B	42.000	--	1.043	43.801	1.4	0.273	1.34	70'	EL	34.5	0.507	1.85	70'	EL	6.9	0.80	0.273	1.04	70'	EL	34.5	
		TNAGRIT3	33.000	--	1.336	44.087	1.4	0.273	1.72	70'	EL	34.5	0.507	2.23	70'	EL	6.9	0.80	0.273	1.34	70'	EL	34.5	
		TNT4A	33.075	--	1.342	44.401	1.4	0.273	1.72	70'	EL	34.5	0.507	2.17	70'	EL	6.9	0.80	0.273	1.34	70'	EL	34.5	
		TNT6A	41.600	--	1.1	45.746	1.4	0.273	1.41	70'	EL	34.5	0.507	1.98	70'	EL	6.9	0.80	0.273	1.10	70'	EL	34.5	
		TNT7A	42.000	--	1.106	46.462	1.4	0.273	1.42	70'	EL	34.5	0.507	1.94	70'	EL	6.9	0.80	0.273	1.11	70'	EL	34.5	
		TNT7B	42.000	--	1.147	48.18	1.4	0.273	1.47	70'	EL	34.5	0.507	1.8	70'	EL	6.9	0.80	0.273	1.15	70'	EL	34.5	
		TNAGRIT4	43.000	--	1.089	46.838	1.4	0.273	1.4	70'	EL	34.5	0.507	1.74	70'	EL	6.9	0.80	0.273	1.09	70'	EL	34.5	
TNAGT5A	45.000	--	1.026	46.175	1.4	0.273	1.32	70'	EL	34.5	0.507	1.74	70'	EL	6.9	0.80	0.273	1.03	70'	EL	34.5			
TNAGT5B	45.000	3	1.013	45.579	1.4	0.273	1.3	70'	EL	34.5	0.507	1.66	70'	EL	6.9	0.80	0.273	1.01	70'	EL	34.5			

LOAD FACTORS:

DESIGN LOAD RATING FACTORS	LIMIT STATE	γ_{DC}	γ_{DW}
	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

NOTES:

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.
 ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.
 DISTANCE FROM LEFT END OF SPAN IS MEASURED FROM C BEARING.

CONTROLLING LOAD RATING

① DESIGN LOAD RATING (HL-93)


② DESIGN LOAD RATING (HS-20)

③ LEGAL LOAD RATING ***

*** SEE CHART FOR VEHICLE TYPE

GIRDER LOCATION

I - INTERIOR GIRDER
 EL - EXTERIOR LEFT GIRDER
 ER - EXTERIOR RIGHT GIRDER



PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
 STATION: 15+31.00 -L-

DRAWN BY: T. BANKOVICH DATE: 10-17
 CHECKED BY: B.S. COX DATE: 10-17
 DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17

PLANS PREPARED BY:

SE & A
 SIMPSON ENGINEERS & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**LRFR SUMMARY FOR
 70' CORED SLAB UNIT
 90° SKEW
 (NON-INTERSTATE TRAFFIC)**

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-3
1			3			TOTAL SHEETS
2			4			18


**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

10/17/2017 11:47:29 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Dur-ham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401-17BP5R54_SMU_SUPER.dgn




TYPICAL SECTION
 HALF SECTION (AT INTERMEDIATE DIAPHRAGMS) HALF SECTION (THROUGH VOIDS)

* - THE MAXIMUM CONCRETE PARAPET HEIGHTS AND ASPHALT THICKNESS ARE SHOWN. THE HEIGHT OF THE CONCRETE PARAPET AND ASPHALT THICKNESS VARIES WHILE THE TOP OF THE CONCRETE PARAPET FOLLOWS THE PROFILE OF THE GUTTERLINE.



EXTERIOR SLAB SECTION
 (FOR PRESTRESSED STRAND LAYOUT, SEE INTERIOR SLAB SECTION.)




INTERIOR SLAB SECTION (70'-0" UNIT)
 (28 STRANDS REQUIRED)


0.6" Ø LOW RELAXATION STRAND LAYOUT

◆ BOND SHALL BE BROKEN ON THESE STRANDS FOR A DISTANCE OF 12'-0" FROM END OF CORED SLAB UNIT. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.


DEBONDING LEGEND




SECTION AT END BENT




THREADED INSERT DETAIL



END ELEVATION
 SHOWING PLACEMENT OF DOUBLE STIRRUPS AND LOCATION OF DOWEL HOLES. (STRAND LAYOUT NOT SHOWN.) INTERIOR SLAB UNIT SHOWN-EXTERIOR SLAB UNIT SIMILAR EXCEPT SHEAR KEY LOCATION.



GROUTED RECESS AT END OF POST-TENSIONED STRAND FOR CORED SLABS




SHEAR KEY DETAIL
 NOTE: OMIT SHEAR KEY ON OUTSIDE FACE OF EXTERIOR CORED SLABS.

PROJECT NO. 17BP.5.R.54
 DURHAM COUNTY
 STATION: 15+31.00 -L-

SHEET 1 OF 4

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUPERSTRUCTURE
 3'-0" X 2'-0"
 PRESTRESSED CONCRETE
 CORED SLAB UNIT
 90° SKEW




PLANS PREPARED BY:
SIMPSON & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-4
1			3			TOTAL SHEETS
2			4			18


DRAWN BY: T. BANKOVICH DATE: 10-17
 CHECKED BY: B.S. COX DATE: 10-17
 DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

10/17/2017 11:47:29 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SMU_SUPER.dgn




PLAN OF SPAN A



DETAIL "A"

(TYPICAL EACH END OF UNIT)
NOTE: EXTERIOR UNIT SHOWN - INTERIOR UNIT SIMILAR EXCEPT OMIT #5 S12 BARS.



DETAIL "B"

#4 S11 BARS MAY BE SHIFTED AS NECESSARY TO MAINTAIN 1" CLEAR TO GROUDED RECESS AND 2 1/2" Ø TRANSVERSE POST-TENSIONING STRAND HOLES

PLANS PREPARED BY:

SE & A
IMPSON ENGINEERS ASSOCIATES
5640 Dillard Drive
Suite 200
Cary, NC 27518
(919) 852-0468
(919) 852-0598 (Fax)
www.slmpsonengr.com
LICENSURE NO. C-2521



PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
STATION: 15+31.00 -L-

SHEET 2 OF 4

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
SUPERSTRUCTURE
PLAN OF SPAN A
(70'-0" UNIT)
36'-6" CLEAR ROADWAY
90° SKEW


REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			S-5
2			4			TOTAL SHEETS 18

DRAWN BY: T. BANKOVICH DATE: 10-17
CHECKED BY: B.S. COX DATE: 10-17
DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

10/17/2017 11:47:29 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54_Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SMU_SUPER.dgn



FIXED END
(TYPE I - 26 REQ'D)


ELASTOMERIC BEARING DETAILS

ELASTOMER IN ALL BEARINGS SHALL BE 60 DUROMETER HARDNESS.

CORED SLABS REQUIRED			
	NUMBER	LENGTH	TOTAL LENGTH
70' UNIT			
EXTERIOR C.S.	2	70'-0"	140'-0"
INTERIOR C.S.	11	70'-0"	770'-0"
TOTAL	13	70'-0"	910'-0"

DEAD LOAD DEFLECTION AND CAMBER	
	3'-0" x 2'-0"
70' CORED SLAB UNIT	0.6" Ø L.R. STRAND
CAMBER (SLAB ALONE IN PLACE)	2 1/4" ↑
DEFLECTION DUE TO SUPERIMPOSED DEAD LOAD**	3/4" ↓
FINAL CAMBER	1 1/2" ↑

** INCLUDES FUTURE WEARING SURFACE



ALL BAR DIMENSIONS ARE OUT TO OUT

NOTES:

ALL PRESTRESSING STRANDS SHALL BE 7-WIRE LOW RELAXATION GRADE 270 STRANDS AND SHALL CONFORM TO AASHTO M203 EXCEPT FOR SAMPLING REQUIREMENTS WHICH SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

ALL REINFORCING STEEL CAST WITH THE CORED SLAB SECTIONS SHALL BE GRADE 60 AND SHALL BE INCLUDED IN THE UNIT PRICE BID FOR PRESTRESSED CONCRETE CORED SLABS.

RECESSES FOR TRANSVERSE STRANDS SHALL BE GROUTED AFTER THE TENSIONING OF THE STRANDS.

THE 2 1/2" Ø DOWEL HOLES AT FIXED ENDS OF SLAB SECTIONS SHALL BE FILLED WITH NON-SHRINK GROUT.

THE BACKER RODS SHALL CONFORM TO THE REQUIREMENTS OF TYPE M BOND BREAKER. SEE SECTION 1028 OF THE STANDARD SPECIFICATIONS.

WHEN CORED SLABS ARE CAST, AN INTERNAL HOLD-DOWN SYSTEM SHALL BE EMPLOYED TO PREVENT VOIDS FROM RISING OR MOVING SIDEWAYS. AT LEAST SIX WEEKS PRIOR TO CASTING CORED SLABS, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER FOR REVIEW AND COMMENT, DETAILED DRAWINGS OF THE PROPOSED HOLD-DOWN SYSTEM. IN ADDITION TO STRUCTURAL DETAILS, LOCATION AND SPACING OF THE HOLD-DOWNS SHALL BE INDICATED.

THE TRANSFER OF LOAD FROM THE ANCHORAGES TO THE CORED SLAB UNIT SHALL BE DONE WHEN THE CONCRETE HAS REACHED A COMPRESSIVE STRENGTH OF NOT LESS THAN THE REQUIRED STRENGTH SHOWN IN THE "CONCRETE RELEASE STRENGTH" TABLE.

ALL REINFORCING STEEL IN CONCRETE PARAPET SHALL BE EPOXY COATED.

PRESTRESSING STRANDS SHALL BE CUT FLUSH WITH THE CORED SLAB UNIT ENDS.

APPLY EPOXY PROTECTIVE COATING TO CORED SLAB UNIT ENDS.

GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE PARAPET AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. A CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN PARAPET EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF PARAPET SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.

FLAME CUTTING OF THE TRANSVERSE POST-TENSIONING STRAND IS NOT ALLOWED.

MAINTAIN A SYMMETRIC TENSION FORCE BETWEEN EACH PAIR OF TRANSVERSE POST TENSIONING STRANDS IN THE DIAPHRAGM.

THE #4 S11 STIRRUPS MAY BE SHIFTED AS NECESSARY TO MAINTAIN 1" CLEAR TO THE GROUTED RECESS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

THE PERMITTED THREADED INSERTS ARE DETAILED AS AN OPTION FOR THE CONTRACTOR TO ATTACH FALSEWORK AND FORMWORK DURING CONSTRUCTION.

THE PERMITTED THREADED INSERTS IN THE EXTERIOR UNITS SHALL BE SIZED BY THE CONTRACTOR, SPACED AT 4'-0" CENTERS AND GALVANIZED IN ACCORDANCE WITH SECTION 1076 OF THE STANDARD SPECIFICATIONS. STAINLESS STEEL THREADED INSERTS MAY BE USED AS AN ALTERNATE.

THE PERMITTED THREADED INSERTS SHALL BE GROUTED BY THE CONTRACTOR IMMEDIATELY FOLLOWING REMOVAL OF THE FALSEWORK.

THE COST OF THE PERMITTED THREADED INSERTS SHALL BE INCLUDED IN THE PRICE BID FOR THE PRECAST UNITS.


BILL OF MATERIAL FOR ONE 70' CORED SLAB UNIT							
BAR	NUMBER	SIZE	TYPE	EXTERIOR UNIT		INTERIOR UNIT	
				LENGTH	WEIGHT	LENGTH	WEIGHT
B22	6	#4	STR	24'-6"	98	24'-6"	98
S10	8	#5	3	4'-9"	40	4'-9"	40
S11	144	#4	3	5'-10"	561	5'-10"	561
*S12	95	#5	1	5'-9"	570		
S14	4	#4	3	5'-7"	15	5'-7"	15
S15	4	#5	3	7'-1"	30	7'-1"	30
REINFORCING STEEL				LBS.	744		744
* EPOXY COATED REINFORCING STEEL				LBS.	570		
7000 P.S.I. CONCRETE				CU. YDS.	11.8		11.8
0.6" Ø L.R. STRANDS				No.	28		28

CONCRETE RELEASE STRENGTH	
UNIT	PSI
70' UNITS	5500

GRADE 270 STRANDS	
	0.6" Ø L.R.
AREA (SQUARE INCHES)	0.217
ULTIMATE STRENGTH (LBS. PER STRAND)	58,600
APPLIED PRESTRESS (LBS. PER STRAND)	43,950

PLANS PREPARED BY:

SE & A
IMPSON ENGINEERS ASSOCIATES
5640 Dillard Drive
Suite 200
Cary, NC 27518
(919) 852-0468
(919) 852-0538 (Fax)
www.slmpsonengr.com
LICENSURE NO. C-2521



PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
STATION: 15+31.00 -L-

SHEET 3 OF 4


STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
SUPERSTRUCTURE
3'-0" X 2'-0"
PRESTRESSED CONCRETE
CORED SLAB UNIT
90° SKEW

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			TOTAL SHEETS
2			4			18


DRAWN BY: T. BANKOVICH DATE: 10-17
CHECKED BY: B.S. COX DATE: 10-17
DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**


10/17/2017 11:47:29 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401-17BP5R54_SMU_SUPER.dgn




ELEVATION AT EXPANSION JOINTS




PLAN OF PARAPET



PLAN OF END POST



END VIEW



ELEVATION

PARAPET AND END POST FOR TWO BAR METAL RAIL

** #5 S12 BARS ARE INCLUDED IN THE BILL OF MATERIAL FOR CORED SLAB UNIT


BAR TYPES		BILL OF MATERIAL				
		PARAPET AND END POSTS				
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT	
*B25	48	5	STR	22'-11"	1147	
*E1	8	7	STR	2'-11"	48	
*E2	8	7	STR	3'-4"	55	
*E3	8	7	STR	3'-10"	63	
*E4	8	7	STR	4'-4"	71	
*E5	8	7	STR	4'-9"	78	
*F1	8	6	STR	1'-11"	23	
*F2	8	6	STR	3'-1"	37	
*F3	8	6	STR	4'-0"	48	
*S13	190	5	1	5'-9"	1139	
* EPOXY COATED REINFORCING STEEL					2709 LB	
CLASS "AA" CONCRETE					17.3 CY	
1'-2" X 2'-9 1/2" CONCRETE PARAPET					140.0 LF	

ALL BAR DIMENSIONS ARE OUT TO OUT

GUTTERLINE ASPHALT THICKNESS & PARAPET HEIGHT		
	ASPHALT OVERLAY THICKNESS @ MID-SPAN	PARAPET HEIGHT @ MID-SPAN
70' UNITS	2"	2'-8"

PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
 STATION: 15+31.00 -L-
 SHEET 4 OF 4

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUPERSTRUCTURE
 CONCRETE PARAPET
 DETAILS FOR
 2 BAR METAL RAIL




PLANS PREPARED BY:
SIMPSON ENGINEERS ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

DRAWN BY: T. BANKOVICH DATE: 10-17
 CHECKED BY: B.S. COX DATE: 10-17
 DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-7
1			3			TOTAL SHEETS
2			4			18

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

10/17/2017 11:47:30 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401-17BP5R54_SMU_SUPER.dgn



ELEVATION

NOTE : FOR ATTACHMENT OF METAL RAIL TO END POST, SEE "RAIL POST SPACING AND END OF RAIL DETAILS" SHEET.

NOTES:

AT THE CONTRACTOR'S OPTION, METAL RAIL MAY BE EITHER ALUMINUM OR GALVANIZED STEEL IN ACCORDANCE WITH THE REQUIREMENTS OF THE GENERAL NOTES AND THE FOLLOWING SPECIFICATIONS FOR THE ALTERNATE MATERIALS; HOWEVER, THE CONTRACTOR WILL BE REQUIRED TO USE THE SAME RAIL MATERIAL ON ALL STRUCTURES ON THE PROJECT FOR WHICH METAL RAIL IS DESIGNATED.

UNLESS OTHERWISE REQUIRED IN THE CONTRACT DOCUMENTS, THE CONTRACTOR HAS THE OPTION TO USE AN ALTERNATE TO THE 2 BAR METAL RAIL. THE ALTERNATE RAIL SHALL MEET THE REQUIREMENTS OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS AND MUST BE LISTED ON THE DEPARTMENT'S APPROVED PRODUCTS LIST (APL) UNDER "2 BAR METAL RAIL ALTERNATE". ADJUSTMENTS TO THE CONCRETE PARAPET WILL NOT BE ALLOWED.

ALUMINUM RAILS:

MATERIAL FOR POSTS, BASES AND RAILS, EXPANSION BARS AND CLAMP BARS SHALL BE ASTM B-221 ALLOY 6061-T6. MATERIAL FOR RIVETS SHALL BE ASTM B316 ALLOY 6061-T6. RIVETS SHALL BE STANDARD BUTTON HEAD AND CONE POINT COLD DRIVEN AS PER DRAWING.

THE BASE OF RAIL POSTS, OR ANY OTHER ALUMINUM SURFACE IN CONTACT WITH CONCRETE SHALL BE THOROUGHLY COATED WITH AN ALUMINUM IMPREGNATED CAULKING COMPOUND OF APPROVED QUALITY.

MATERIAL FOR SHIMS TO BE ASTM B209 ALLOY 6061-T6.

GALVANIZED STEEL RAILS:

MATERIAL AND GALVANIZING ARE TO CONFORM TO THE FOLLOWING SPECIFICATIONS:

POST, POST BASES, RAILS, EXPANSION BARS AND CLAMP BARS: AASHTO M270 GRADE 36 STRUCTURAL STEEL - GALVANIZED TO AASHTO M111.

RIVETS: RIVETS SHALL MEET THE REQUIREMENTS OF ASTM A502 FOR GRADE 1 RIVETS.

THE CUT ENDS OF GALVANIZED STEEL RAILING, AFTER GRINDING SMOOTH SHALL BE GIVEN TWO COATS OF ZINC RICH PAINT MEETING THE REQUIREMENTS OF FEDERAL SPECIFICATION MIL-P-26915 USAF TYPE 1, OR OF FEDERAL SPECIFICATIONS TT-P-641.

SHIMS: SHIMS SHALL MEET THE REQUIREMENTS OF ASTM A570 FOR GRADE 33 OR A611 FOR GRADE C AND SHALL BE GALVANIZED IN ACCORDANCE WITH AASHTO M111.

RAIL CAPS: RAIL CAPS SHALL MEET THE REQUIREMENTS OF ASTM A570 FOR GRADE 33 OR A611 FOR GRADE C AND SHALL BE GALVANIZED IN ACCORDANCE WITH AASHTO M111.

GENERAL NOTES:

RAILING SHALL BE CONTINUOUS FROM END POST TO END POST OF BRIDGE. EACH JOINT IN RAIL LENGTH SHALL BE SPLICED AS DETAILED. PANEL LENGTHS OF RAIL SHALL BE ATTACHED TO A MINIMUM OF THREE POSTS.

FOR END OF RAIL TO CLEAR FACE OF CONCRETE END POST DIMENSION, SEE "RAIL POST SPACING AND END OF RAIL DETAILS" SHEET.

CAP SCREWS SHALL BE ASTM F593 ALLOY 305 STAINLESS STEEL. WASHERS SHALL MEET THE REQUIREMENTS OF ASTM F844 EXCEPT THEY SHALL BE MADE FROM ALLOY 304 STAINLESS STEEL.

CERTIFIED MILL REPORTS ARE REQUIRED FOR RAILS AND POSTS. SHOP INSPECTION IS NOT REQUIRED.

METAL RAIL POSTS SHALL BE SET NORMAL TO CURB GRADE.

METHOD OF MEASUREMENT FOR METAL RAILS: FOR LENGTH OF METAL RAILS TO BE PAID FOR, SEE THE STANDARD SPECIFICATIONS.

CURVED RAIL USAGE: WHERE RAILS ARE TO BE USED ON BRIDGES ON HORIZONTAL AND/OR VERTICAL CURVATURE THE CONTRACTOR MAY, AT HIS OPTION, HAVE THE REQUIRED CURVATURE IN THE RAIL FORMED IN THE SHOP OR IN THE FIELD. IN EITHER EVENT, THE RAIL SHALL CONFORM WITHOUT BUCKLING OR KINKING TO THE REQUIRED CURVATURE IN A UNIFORM MANNER ACCEPTABLE TO THE ENGINEER.


TO INSURE FUTURE IDENTIFICATION OF THE FABRICATOR, A PERMANENT IDENTIFYING MARK SHALL BE PLACED ON EACH POST. THE METHOD OF MARKING AND LOCATION SHALL BE SUCH THAT IT DOES NOT DETRACT FROM THE APPEARANCE OF THE POST, BUT REMAINS VISIBLE AFTER RAIL PLACEMENT.

SHIMS SHALL BE USED AS NECESSARY FOR POST ALIGNMENT.


ALLOY 6351-T5 MAY BE SUBSTITUTED FOR ALLOY 6061-T6 WHERE APPLICABLE.

MINOR VARIATIONS IN DETAILS OF METAL RAIL WILL BE CONSIDERED. DETAILS OF SUCH VARIATIONS, IF DESIRED, SHALL BE SUBMITTED FOR APPROVAL.


GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE PARAPET AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. A CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN PARAPET EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF PARAPET SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.




DETAILS OF POST




SECTION THRU PARAPET AND RAIL



RIVET DETAIL



PLAN



FRONT ELEVATION

SIDE ELEVATION

POST BASE DETAILS

PAY LENGTH = 125.00 LF

PROJECT NO. 17BP.5.R.54
 DURHAM COUNTY
 STATION: 15+31.00 -L-

SHEET 1 OF 2

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUPERSTRUCTURE

2 BAR METAL RAIL

PLANS PREPARED BY:

S&A
 SIMPSON ENGINEERS & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521




REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-8
1			3			TOTAL SHEETS
2			4			18

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

DRAWN BY: T. BANKOVICH DATE: 10-17
 CHECKED BY: B.S. COX DATE: 10-17
 DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17

10/17/2017 11:47:30 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401-17BP5R54_SMU_SUPER.dgn




4-BOLT METAL RAIL ANCHOR ASSEMBLY
 (28 ASSEMBLIES REQUIRED)


- STRUCTURAL CONCRETE ANCHOR ASSEMBLY NOTES:**
- THE STRUCTURAL CONCRETE ANCHOR ASSEMBLY SHALL CONSIST OF THE FOLLOWING COMPONENTS :
- FERRULES SHALL BE MADE FROM STEEL MEETING THE REQUIREMENTS OF AASHTO M169, GRADE 12L14 AND SHALL HAVE A MINIMUM LENGTH OF THREADS OF 2" FOR 3/4" FERRULES.
 - 4 - 3/4" Ø X 2 1/2" BOLTS WITH WASHERS. BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307. BOLTS AND WASHERS SHALL BE GALVANIZED. AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 3/4" Ø X 2 1/2" GALVANIZED BOLTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.
 - WIRE STRUT SHOWN IN THE CONCRETE ANCHOR ASSEMBLY DETAIL IS THE MINIMUM ALLOWABLE SIZE AND SHALL HAVE A MINIMUM TENSILE STRENGTH OF 100,000 PSI. AS AN OPTION, A 1/6" Ø WIRE STRUT WITH A MINIMUM TENSILE STRENGTH OF 90,000 PSI IS ACCEPTABLE.
 - THE METAL RAIL ANCHOR ASSEMBLIES TO BE HOT DIPPED GALVANIZED TO CONFORM TO REQUIREMENTS OF AASHTO M111.
 - THE COST OF THE METAL RAIL ANCHOR ASSEMBLY WITH BOLTS AND WASHERS COMPLETE IN PLACE SHALL BE INCLUDED IN THE PRICE BID FOR LINEAR FEET OF METAL RAIL.
 - BOLTS TO BE TIGHTENED ONE-HALF TURN WITH A WRENCH FROM A FINGER-TIGHT POSITION.

THE CONTRACTOR MAY USE ADHESIVELY ANCHORED ANCHOR BOLTS IN PLACE OF THE METAL RAIL ANCHOR ASSEMBLY. LEVEL ONE FIELD TESTING IS REQUIRED, AND THE YIELD LOAD OF THE 3/4" Ø BOLT IS 10 KIPS. FOR ADHESIVELY ANCHORED ANCHOR BOLTS OR DOWELS, SEE THE STANDARD SPECIFICATIONS.

WHEN ADHESIVELY ANCHORED ANCHOR BOLTS ARE USED, BOLTS SHALL MEET THE REQUIREMENTS OF ASTM F593 ALLOY 304 STAINLESS STEEL WITH MINIMUM 75,000 PSI ULTIMATE STRENGTH. NUTS SHALL MEET THE REQUIREMENTS OF ASTM F594 ALLOY 304 STAINLESS STEEL AND WASHERS SHALL MEET THE REQUIREMENTS OF ASTM F844 EXCEPT THEY SHALL BE MADE FROM ALLOY 304 STAINLESS STEEL.




EXPANSION BAR DETAILS





SHIM DETAILS

NOTE :
 SHIMS MAY BE CUT ALONG PERMITTED CUTLINE OR SLOTTED TO EDGE OF PLATE TO FACILITATE PLACEMENT.



CLAMP BAR DETAIL
 (4 REQUIRED PER POST)




PROJECT NO. 17BP.5.R.54
 DURHAM COUNTY
 STATION: 15+31.00 -L-
 SHEET 2 OF 2

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUPERSTRUCTURE

2 BAR METAL RAIL

PLANS PREPARED BY:
SEA & A
 SIMPSON ENGINEERS ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521



REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-9
1			3			TOTAL SHEETS
2			4			18

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

10/17/2017 11:47:30 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SMU_SUPER.dgn

STRUCTURAL CONCRETE INSERT NOTES:

- THE STRUCTURAL CONCRETE INSERT ASSEMBLY SHALL CONSIST OF THE FOLLOWING COMPONENTS:
- A. FERRULES SHALL BE MADE FROM STEEL MEETING THE REQUIREMENTS OF AASHTO M169, GRADE 12L14 AND SHALL HAVE A MINIMUM LENGTH OF THREADS OF 1/2".
 - B. 1 - 3/4" Ø X 1 5/8" BOLT WITH WASHER. BOLT SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307. BOLT AND WASHER SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLT AND WASHER MAY BE USED AS AN ALTERNATE FOR THE 3/4" Ø X 1 5/8" GALVANIZED BOLT AND WASHER. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)
 - C. WIRE STRUT SHOWN IN THE CONCRETE INSERT ASSEMBLY DETAIL IS THE MINIMUM ALLOWABLE SIZE AND SHALL HAVE A MINIMUM TENSILE STRENGTH OF 100,000 PSI. AS AN OPTION, A 1/16" Ø WIRE STRUT WITH A MINIMUM TENSILE STRENGTH OF 90,000 PSI IS ACCEPTABLE.

METAL RAIL TO END POST CONNECTION NOTES:


- THE METAL RAIL TO END POST CONNECTION SHALL CONSIST OF THE FOLLOWING COMPONENTS:
- A. 1/2" PLATES SHALL CONFORM TO AASHTO M270 GRADE 36 AND SHALL BE GALVANIZED AFTER FABRICATION.
 - B. 3/4" STRUCTURAL CONCRETE INSERT SHALL HAVE A WORKING LOAD SHEAR CAPACITY OF 4800 LBS. THE FERRULES SHALL ENGAGE A 3/4" Ø X 1 5/8" BOLT WITH 2" O.D. WASHER IN PLACE. THE 3/4" Ø X 1 5/8" BOLT SHALL HAVE N.C. THREADS.
 - C. CAP SCREWS FOR RAIL ATTACHMENT TO ANGLE SHALL CONFORM TO THE REQUIREMENTS OF ASTM F593 ALLOY 305 STAINLESS STEEL. CAP SCREWS TO BE CENTERED IN SLOTS AT 60° F.
 - D. STANDARD CLAMP BARS (SEE METAL RAIL SHEET).
 - E. 1/2" Ø PIPE SLEEVES (IF REQUIRED) TO BE GALVANIZED.

THE COST OF THE STANDARD CLAMP BARS AND CAP SCREWS USED IN THE METAL RAIL TO END POST CONNECTION SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR LINEAR FEET OF 1 OR 2 BAR METAL RAILS.





THE 3/4" STRUCTURAL CONCRETE INSERT WITH BOLT SHALL BE ASSEMBLED IN THE SHOP.

THE COST OF THE 3/4" STRUCTURAL CONCRETE INSERT ASSEMBLY, AND THE 1/2" PLATES COMPLETE IN PLACE SHALL BE INCLUDED IN THE VARIOUS PAY ITEMS.


THE CONTRACTOR, AT HIS OPTION, MAY USE AN ADHESIVE BONDING SYSTEM IN LIEU OF THE STRUCTURAL CONCRETE INSERT EMBEDDED IN THE END POST. IF THE ADHESIVE BONDING SYSTEM IS USED, THE 3/4" Ø X 1 5/8" BOLT WITH WASHER SHALL BE REPLACED WITH A 3/4" Ø X 6 1/2" BOLT AND 2" O.D. WASHER. ALL SPECIFICATIONS THAT APPLY TO THE 3/4" Ø X 1 5/8" BOLT SHALL APPLY TO THE 3/4" Ø X 6 1/2" BOLT. FIELD TESTING OF THE ADHESIVE BONDING SYSTEM IS NOT REQUIRED.



PLAN OF RAIL POST SPACING
(RIGHT EXTERIOR UNIT SHOWN, LEFT EXTERIOR UNIT SIMILAR)



PLAN - RAIL AND END POST




STRUCTURAL CONCRETE INSERT

* EACH WELDED ATTACHMENT OF WIRE TO FERRULE SHALL DEVELOP THE TENSILE STRENGTH OF THE WIRE.

PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
 STATION: 15+31.00 -L-

PLANS PREPARED BY:
SIMPSON ENGINEERS & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUPERSTRUCTURE
RAIL POST SPACING AND END OF RAIL DETAILS FOR TWO BAR METAL RAILS

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	5-10
1			3			TOTAL SHEETS
2			4			18

DRAWN BY: T. BANKOVICH	DATE: 10-17
CHECKED BY: B.S. COX	DATE: 10-17
DESIGN ENGINEER OF RECORD: T.J. BEACH	DATE: 10-17

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

10/17/2017 11:47:30 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SMU_SUPER.dgn



GUARDRAIL ANCHOR ASSEMBLY DETAILS

NOTES:

THE GUARDRAIL ANCHOR ASSEMBLY SHALL CONSIST OF A 1/4" HOLD DOWN PLATE AND 7 - 7/8" Ø BOLTS WITH NUTS AND WASHERS.

THE HOLD-DOWN PLATE SHALL CONFORM TO AASHTO M270 GRADE 36. AFTER FABRICATION, THE HOLD-DOWN PLATE SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH AASHTO M111.

BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307 AND NUTS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M291. BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED. AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS, NUTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 7/8" Ø GALVANIZED BOLTS, NUTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.


THE GUARDRAIL ANCHOR ASSEMBLY IS REQUIRED AT ALL POINTS WHERE APPROACH GUARDRAIL IS TO BE ATTACHED TO THE END OF THE PARAPET. FOR POINTS OF ATTACHMENT, SEE SKETCH.

AFTER INSTALLATION, THE EXPOSED THREAD OF THE BOLT SHALL BE BURRED WITH A SHARP POINTED TOOL.


THE COST OF THE GUARDRAIL ANCHOR ASSEMBLIES WITH BOLTS, NUTS AND WASHERS COMPLETE IN PLACE, SHALL BE INCLUDED IN THE VARIOUS PAY ITEMS.

THE VERTICAL REINFORCING BARS MAY BE SHIFTED SLIGHTLY IN THE END POST TO CLEAR ASSEMBLY BOLTS.

THE 1 1/4" Ø HOLES SHALL BE FORMED OR DRILLED WITH A CORE BIT. IMPACT TOOLS WILL NOT BE PERMITTED. ANY CONCRETE DAMAGED BY THIS WORK SHALL BE REPAIRED TO THE SATISFACTION OF THE ENGINEER.



LOCATION OF GUARDRAIL ANCHOR AT END POST



PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
 STATION: 15+31.00 -L-

DRAWN BY: T. BANKOVICH DATE: 10-17
 CHECKED BY: B.S. COX DATE: 10-17
 DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17

PLANS PREPARED BY:
SE & A
 SIMPSON ENGINEERS ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUPERSTRUCTURE
**GUARDRAIL ANCHORAGE
 DETAILS
 FOR METAL RAILS**


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-11
1			3			TOTAL SHEETS
2			4			18

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

10/17/2017 11:47:30 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SMU_EB.dgn



PLAN



ELEVATION

WINGS NOT SHOWN FOR CLARITY.
FOR SECTION A-A, SEE SHEET 4 OF 4.
CONCRETE COLLARS FOR STEEL PILES NOT SHOWN IN PLAN AND ELEVATION VIEWS FOR CLARITY.
SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL", SHEET 4 OF 4.

NOTES:

- STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR DOWELS.
- THE CONCRETE IN THE SHADED AREA OF THE WING SHALL BE POURED AFTER THE CONCRETE PARAPET IS CAST IF SLIP FORMING IS USED.
- FOR PILE SPLICE DETAILS, SEE SHEET 4 OF 4.
- FOR WING DETAILS, SEE SHEET 3 OF 4.
- INSTALL 4" DIAMETER DRAIN PIPE THROUGH THE WINGWALL AS REQUIRED FOR REINFORCED BRIDGE APPROACH FILLS, SEE THE ROADWAY PLANS. REINFORCING STEEL IN THE WING WALL MAY BE SHIFTED AS NECESSARY TO CLEAR THE DRAIN PIPE.


TOP OF PILE ELEVATIONS	
①	276.47
②	276.68
③	276.89
④	277.10
⑤	277.31
⑥	277.52
⑦	277.73

PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
 STATION: 15+31.00 -L-

SHEET 1 OF 4

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE

END BENT 1




PLANS PREPARED BY:
SE & A
 SIMPSON ENGINEERS & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

DRAWN BY: T. BANKOVICH DATE: 10-17
 CHECKED BY: B.S. COX DATE: 10-17
 DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17


REVISIONS						SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:	S-12	
1			3			TOTAL SHEETS	
2			4			18	

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

10/17/2017 11:47:31 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SML_EB.dgn



PLAN



ELEVATION

WINGS NOT SHOWN FOR CLARITY.
FOR SECTION A-A, SEE SHEET 4 OF 4.
CONCRETE COLLARS FOR STEEL PILES NOT SHOWN IN PLAN AND ELEVATION VIEWS FOR CLARITY.
SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL", SHEET 4 OF 4.

NOTES:

- STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR DOWELS.
- THE CONCRETE IN THE SHADED AREA OF THE WING SHALL BE POURED AFTER THE CONCRETE PARAPET IS CAST IF SLIP FORMING IS USED.
- FOR PILE SPLICE DETAILS, SEE SHEET 4 OF 4.
- FOR WING DETAILS, SEE SHEET 3 OF 4.
- INSTALL 4" DIAMETER DRAIN PIPE THROUGH THE WINGWALL AS REQUIRED FOR REINFORCED BRIDGE APPROACH FILLS, SEE THE ROADWAY PLANS. REINFORCING STEEL IN THE WING WALL MAY BE SHIFTED AS NECESSARY TO CLEAR THE DRAIN PIPE.

TOP OF PILE ELEVATIONS	
①	276.82
②	277.03
③	277.24
④	277.45
⑤	277.66
⑥	277.87
⑦	278.08

PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
 STATION: 15+31.00 -L-

SHEET 2 OF 4


STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE

END BENT 2

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-13
1			3			TOTAL SHEETS
2			4			18


DRAWN BY: T. BANKOVICH DATE: 10-17
 CHECKED BY: B.S. COX DATE: 10-17
 DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17

PLANS PREPARED BY:
SE & A
 IMPSON ENGINEERS & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.slmpsonengr.com
 LICENSURE NO. C-2521




**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**


10/17/2017 11:47:31 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SML_EB.dgn




PLAN OF WING (W1)




PLAN OF WING (W2)




ELEVATION OF WING (W1)



ELEVATION OF WING (W2)



SECTION X-X



SECTION Y-Y

PROJECT NO. 17BP.5.R.54
 DURHAM COUNTY
 STATION: 15+31.00 -L-

SHEET 3 OF 4

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 SUBSTRUCTURE

END BENT
 WING DETAILS

PLANS PREPARED BY:

SEA & A
 SIMPSON ENGINEERS & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521



10/17/2017


DRAWN BY: T. BANKOVICH	DATE: 10-17
CHECKED BY: B.S. COX	DATE: 10-17
DESIGN ENGINEER OF RECORD: T.J. BEACH	DATE: 10-17

WING DETAILS

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-14
1			3			TOTAL SHEETS
2			4			18

10/17/2017 11:47:31 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SMU_EB.dgn




BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.


BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.


TEMPORARY DRAINAGE AT END BENT



PILE SPLICE DETAILS




BILL OF MATERIAL FOR ONE END BENT					
BAR NO.	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	#9		47'-0"	1278
B2	28	#4	STR	23'-7"	441
B3	12	#4	STR	2'-5"	19
D1	26	#6	STR	1'-6"	59
H1	40	#4		9'-4"	249
K1	16	#4	STR	3'-2"	34
S1	56	#4	3	10'-5"	390
S2	56	#4	4	3'-2"	118
S3	28	#4	5	6'-6"	122
V1	52	#4	STR	6'-2"	214
REINFORCING STEEL (FOR ONE END BENT)					2924 LBS.
CLASS A CONCRETE BREAKDOWN (FOR ONE END BENT)					
POUR 1	CAP, LOWER PART OF WINGS & COLLARS				21.9 C.Y.
POUR 2	UPPER PART OF WINGS				2.3 C.Y.
TOTAL CLASS A CONCRETE					24.2 C.Y.




CORROSION PROTECTION FOR STEEL PILES DETAIL

(END BENT 2 SHOWN, END BENT 1 SIMILAR BY ROTATION)



(END BENT 1 SHOWN, END BENT 2 SIMILAR BY ROTATION)



(CONCRETE COLLAR NOT SHOWN FOR CLARITY. SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL.")

END BENT 1		
HP 12 X 53 STEEL PILES		
NO: 7	LIN. FT.= 105	
STEEL PILE POINTS	NO: 7	
PILE DRIVING EQUIPMENT SETUP FOR HP 12 X 53 STEEL PILES	EA: 7	
END BENT 2		
HP 12 X 53 STEEL PILES		
NO: 7	LIN. FT.= 105	
STEEL PILE POINTS	NO: 7	
PILE DRIVING EQUIPMENT SETUP FOR HP 12 X 53 STEEL PILES	EA: 7	

PROJECT NO. 17BP.5.R.54

DURHAM COUNTY

STATION: 15+31.00 -L-

SHEET 4 OF 4

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
SUBSTRUCTURE

**END BENT 1 & 2
DETAILS**

REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

SHEET NO. S-15
TOTAL SHEETS 18


DRAWN BY: T. BANKOVICH	DATE: 10-17
CHECKED BY: B.S. COX	DATE: 10-17
DESIGN ENGINEER OF RECORD: T.J. BEACH	DATE: 10-17

PLANS PREPARED BY:
SEA & A
SIMPSON ENGINEERS ASSOCIATES
5640 Dillard Drive
Suite 200
Cary, NC 27518
(919) 852-0468
(919) 852-0538 (Fax)
www.simpsonengr.com
LICENSURE NO. C-2521




**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

10/17/2017 11:47:31 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401-17BP5R54_SML_RR.dgn




ESTIMATED QUANTITIES		
BRIDGE @ STA. 15+31.00 -L-	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE
	TONS	SQUARE YARDS
END BENT 1	90	100
END BENT 2	95	105


PLAN OF RIP RAP



SECTION H-H



SECTION BERM RIP RAPPED




SECTION C-C

PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
 STATION: 15+31.00 -L-

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

RIP RAP DETAILS




PLANS PREPARED BY:
S&A ENGINEERS ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-16
1			3			TOTAL SHEETS
2			4			18

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

DRAWN BY: T. BANKOVICH DATE: 10-17
 CHECKED BY: B.S. COX DATE: 10-17
 DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17

10/17/2017 11:47:32 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Dur-ham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401_17BP5R54_SMU_AS.dgn



PLAN @ END BENT 1 PLAN @ END BENT 2
DIMENSIONS SHOWN ARE TYPICAL FOR BOTH APPROACH SLABS

NOTES:

FOR REINFORCED BRIDGE APPROACH FILL INCLUDING GEOTEXTILE, IMPERMEABLE GEOMEMBRANE, 4" Ø DRAINAGE PIPE, #78M STONE, AND SELECT MATERIAL, SEE ROADWAY PLANS.


AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

APPROACH SLAB GROOVING IS NOT REQUIRED.


THE EFFECTS OF THE HORIZONTAL CURVE ARE NEGLIGIBLE IN THE CONSTRUCTION OF THE APPROACH SLAB AT END BENT 2.

BILL OF MATERIAL					
APPROACH SLAB AT EB 1					
BAR NO.	NO.	SIZE	TYPE	LENGTH	WEIGHT
* A1	26	#4	STR	19'-9"	343
A2	26	#4	STR	19'-8"	342
* B1	76	#5	STR	11'-2"	885
B2	76	#6	STR	11'-8"	1332
REINFORCING STEEL					LBS. 1674
* EPOXY COATED REINFORCING STEEL					LBS. 1228
CLASS AA CONCRETE					C. Y. 22.9
APPROACH SLAB AT EB 2					
BAR NO.	NO.	SIZE	TYPE	LENGTH	WEIGHT
* A1	26	#4	STR	19'-9"	343
A2	26	#4	STR	19'-8"	342
* B1	76	#5	STR	11'-2"	885
B2	76	#6	STR	11'-8"	1332
REINFORCING STEEL					LBS. 1674
* EPOXY COATED REINFORCING STEEL					LBS. 1228
CLASS AA CONCRETE					C. Y. 22.9

SPLICE CHART		
BAR SIZE	EPOXY COATED	UNCOATED
#4	2'-0"	1'-9"
#5	2'-6"	2'-2"
#6	3'-10"	2'-7"



SECTION THRU SLAB




CURB DETAILS

PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
 STATION: 15+31.00 -L-
 SHEET 1 OF 2

DRAWN BY: T. BANKOVICH DATE: 10-17
 CHECKED BY: B.S. COX DATE: 10-17
 DESIGN ENGINEER OF RECORD: T.J. BEACH DATE: 10-17

PLANS PREPARED BY:
SE & A
 SIMPSON ENGINEERS & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0598 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521




STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
**BRIDGE APPROACH
 SLAB FOR PRESTRESSED
 CONCRETE CORED
 SLAB UNIT**
 (SUB-REGIONAL TIER)-90° SKEW

REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		

SHEET NO. S-17
TOTAL SHEETS 18


**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

10/17/2017 11:47:32 AM G:\Projects\2016\Division 5 (Mott Macdonald)\17BP5R54 Durham #117 (90 24CS 2BMR)\Structures\Drawings\Final\401-17BP5R54_SMU_AS.dgn



TEMPORARY BERM AND SLOPE DRAIN DETAILS

(TO BE USED WHEN SHOULDER BERM GUTTER IS REQUIRED)



PROJECT NO. 17BP.5.R.54
DURHAM COUNTY
 STATION: 15+31.00 -L-


SHEET 2 OF 2

STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

BRIDGE APPROACH SLAB DETAILS

PLANS PREPARED BY:

SEA & A
 SIMPSON ENGINEERS & ASSOCIATES
 5640 Dillard Drive
 Suite 200
 Cary, NC 27518
 (919) 852-0468
 (919) 852-0538 (Fax)
 www.simpsonengr.com
 LICENSURE NO. C-2521



REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			S-18
2			4			TOTAL SHEETS 18

DRAWN BY: T. BANKOVICH	DATE: 10-17
CHECKED BY: B.S. COX	DATE: 10-17
DESIGN ENGINEER OF RECORD: T.J. BEACH	DATE: 10-17

**DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED**

STANDARD NOTES

DESIGN DATA:

SPECIFICATIONS	-----	A.A.S.H.T.O. (CURRENT)
LIVE LOAD	-----	SEE PLANS
IMPACT ALLOWANCE	-----	SEE A.A.S.H.T.O.
STRESS IN EXTREME FIBER OF		
STRUCTURAL STEEL - AASHTO M270 GRADE 36	-	20,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50W	-	27,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50	-	27,000 LBS. PER SQ. IN.
REINFORCING STEEL IN TENSION		
	GRADE 60	-- 24,000 LBS. PER SQ. IN.
CONCRETE IN COMPRESSION	-----	1,200 LBS. PER SQ. IN.
CONCRETE IN SHEAR	-----	SEE A.A.S.H.T.O.
STRUCTURAL TIMBER - TREATED OR		
UNTREATED - EXTREME FIBER STRESS	-----	1,800 LBS. PER SQ. IN.
COMPRESSION PERPENDICULAR TO GRAIN OF TIMBER		
	-----	375 LBS. PER SQ. IN.
EQUIVALENT FLUID PRESSURE OF EARTH	-----	30 LBS. PER CU. FT.
		(MINIMUM)

MATERIAL AND WORKMANSHIP:

EXCEPT AS MAY OTHERWISE BE SPECIFIED ON PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2012 "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" OF THE N. C. DEPARTMENT OF TRANSPORTATION.

STEEL SHEET PILING FOR PERMANENT OR TEMPORARY APPLICATIONS SHALL BE HOT ROLLED.

CONCRETE:

UNLESS OTHERWISE REQUIRED ON PLANS, CLASS A CONCRETE SHALL BE USED FOR ALL PORTIONS OF ALL STRUCTURES WITH THE EXCEPTION THAT: CLASS AA CONCRETE SHALL BE USED IN BRIDGE SUPERSTRUCTURES, ABUTMENT BACKWALLS, AND APPROACH SLABS; AND CLASS B CONCRETE SHALL BE USED FOR SLOPE PROTECTION AND RIP RAP.

CONCRETE CHAMFERS:

UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4" WITH THE FOLLOWING EXCEPTIONS: TOP CORNERS OF CURBS MAY BE ROUNDED TO 1-1/2" RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A 1/4" FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A 1/4" RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE REQUIRED ON PLANS.

DOWELS:

DOWELS WHEN INDICATED ON PLANS AS FOR CULVERT EXTENSIONS, SHALL BE EMBEDDED AT LEAST 12" INTO THE OLD CONCRETE AND GROUTED INTO PLACE WITH 1:2 CEMENT MORTAR.

ALLOWANCE FOR DEAD LOAD DEFLECTION, SETTLEMENT: ETC. IN CASTING SUPERSTRUCTURES:

BRIDGES SHALL BE BUILT ON THE GRADE OR VERTICAL CURVE SHOWN ON PLANS. SLABS, CURBS AND PARAPETS SHALL CONFORM TO THE GRADE OR CURVE.

ALL DIMENSIONS WHICH ARE GIVEN IN SECTION AND ARE AFFECTED BY DEAD LOAD DEFLECTIONS ARE DIMENSIONS AT CENTER LINE OF BEARING UNLESS OTHERWISE NOTED ON PLANS. IN SETTING FORMS FOR STEEL BEAM BRIDGES AND PRESTRESSED CONCRETE GIRDER BRIDGES, ADJUSTMENTS SHALL BE MADE DUE TO THE DEAD LOAD DEFLECTIONS FOR THE ELEVATIONS SHOWN. WHERE BLOCKS ARE SHOWN OVER BEAMS FOR BUILDING UP TO THE SLAB, THE VERTICAL DIMENSIONS OF THE BLOCKS SHALL BE ADJUSTED BETWEEN BEARINGS TO COMPENSATE FOR DEAD LOAD DEFLECTIONS, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. WHERE BOTTOM OF SLAB IS IN LINE WITH BOTTOM OF TOP FLANGES, DEPTH OF SLAB BETWEEN BEARINGS SHALL BE ADJUSTED TO COMPENSATE FOR DEAD LOAD DEFLECTION, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER.

IN SETTING FALSEWORK AND FORMS FOR REINFORCED CONCRETE SPANS, AN ALLOWANCE SHALL BE MADE FOR DEAD LOAD DEFLECTIONS, SETTLEMENT OF FALSEWORK, AND PERMANENT CAMBER WHICH SHALL BE PROVIDED FOR IN ADDITION TO THE ELEVATIONS SHOWN. AFTER REMOVAL OF THE FALSEWORK, THE FINISHED STRUCTURES SHALL CONFORM TO THE PROFILE AND ELEVATIONS SHOWN ON THE PLANS AND CONSTRUCTION ELEVATIONS FURNISHED BY THE ENGINEER.

DETAILED DRAWINGS FOR FALSEWORK OR FORMS FOR BRIDGE SUPERSTRUCTURE AND ANY STRUCTURE OR PARTS OF A STRUCTURE AS NOTED ON THE PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL BEFORE CONSTRUCTION OF THE FALSEWORK OR FORMS IS STARTED.

REINFORCING STEEL:

ALL REINFORCING STEEL SHALL BE DEFORMED. DIMENSIONS RELATIVE TO PLACEMENT OF REINFORCING ARE TO CENTERS OF BARS UNLESS OTHERWISE INDICATED IN THE PLANS. DIMENSIONS ON BAR DETAILS ARE TO CENTERS OF BARS OR ARE OUT TO OUT AS INDICATED ON PLANS.

WIRE BAR SUPPORTS SHALL BE PROVIDED FOR REINFORCING STEEL WHERE INDICATED ON THE PLANS. WHEN BAR SUPPORT PIECES ARE PLACED IN CONTINUOUS LINES, THEY SHALL BE SO PLACED THAT THE ENDS OF THE SUPPORTING WIRES SHALL BE LAPPED TO LOCK LEGS ON ADJOINING PIECES.

STRUCTURAL STEEL:

AT THE CONTRACTOR'S OPTION, HE MAY SUBSTITUTE 7/8" Ø SHEAR STUDS FOR THE 3/4" Ø STUDS SPECIFIED ON THE PLANS. THIS SUBSTITUTION SHALL BE MADE AT THE RATE OF 3 - 7/8" Ø STUDS FOR 4 - 3/4" Ø STUDS, AND STUD SPACING CHANGES SHALL BE MADE AS NECESSARY TO PROVIDE THE SAME EQUIVALENT NUMBER OF 7/8" Ø STUDS ALONG THE BEAM AS SHOWN FOR 3/4" Ø STUDS BASED ON THE RATIO OF 3 - 7/8" Ø STUDS FOR 4 - 3/4" Ø STUDS. STUDS OF THE LENGTH SPECIFIED ON THE PLANS MUST BE PROVIDED. THE MAXIMUM SPACING SHALL BE 2'-0".

EXCEPT AT THE INTERIOR SUPPORTS OF CONTINUOUS BEAMS WHERE THE COVER PLATE IS IN CONTACT WITH BEARING PLATE, THE CONTRACTOR MAY, AT HIS OPTION, SUBSTITUTE FOR THE COVER PLATES DESIGNATED ON THE PLANS COVER PLATES OF THE EQUIVALENT AREA PROVIDED THESE PLATES ARE AT LEAST 5/16" IN THICKNESS AND DO NOT EXCEED A WIDTH EQUAL TO THE FLANGE WIDTH LESS 2" OR A THICKNESS EQUAL TO 2 TIMES THE FLANGE THICKNESS. THE SIZE OF FILLET WELDS SHALL CONFORM TO THE REQUIREMENTS OF THE CURRENT ANSI/AASHTO/AWS "BRIDGE WELDING CODE". ELECTROSLAG WELDING WILL NOT BE PERMITTED.

WITH THE SOLE EXCEPTION OF EDGES AT SURFACES WHICH BEAR ON OTHER SURFACES, ALL SHARP EDGES AND ENDS OF SHAPES AND PLATES SHALL BE SLIGHTLY ROUNDED BY SUITABLE MEANS TO A RADIUS OF APPROXIMATELY 1/16 INCH OR EQUIVALENT FLAT SURFACE AT A SUITABLE ANGLE PRIOR TO PAINTING, GALVANIZING, OR METALLIZING.

HANDRAILS AND POSTS:

METAL STANDARDS AND FACES OF THE CONCRETE END POSTS FOR THE METAL RAIL SHALL BE SET NORMAL TO THE GRADE OF THE CURB, UNLESS OTHERWISE SHOWN ON PLANS. THE METAL RAIL AND TOPS OF CONCRETE POSTS USED WITH THE ALUMINUM RAIL SHALL BE BUILT PARALLEL TO THE GRADE OF THE CURB.

METAL HANDRAILS SHALL BE IN ACCORDANCE WITH THE PLANS. RAILS SHALL BE AS MANUFACTURED FOR BRIDGE RAILING. CASTINGS SHALL BE OF A UNIFORM APPEARANCE. FINS AND OTHER DEFORMATIONS RESULTING FROM CASTING OR OTHERWISE SHALL BE REMOVED IN A MANNER SO THAT A UNIFORM COLORING OF THE COMPLETED CASTING SHALL BE OBTAINED. CASTINGS WITH DISCOLORATIONS OR OF NON-UNIFORM COLORING WILL NOT BE ACCEPTED. CERTIFIED MILL REPORTS ARE REQUIRED FOR METAL RAILS AND POSTS.

SPECIAL NOTES:

GENERALLY, IN CASE OF DISCREPANCY, THIS STANDARD SHEET OF NOTES SHALL GOVERN OVER THE SPECIFICATIONS, BUT THE REMAINDER OF THE PLANS SHALL GOVERN OVER NOTES HEREON, AND SPECIAL PROVISIONS SHALL GOVERN OVER ALL. SEE SPECIFICATIONS ARTICLE 105-4.

ENGLISH

JANUARY, 1990