

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	9,810 CY		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	6,200 SY		
0007	0335200000-E	305	15" DRAINAGE PIPE	92 LF		
0008	0335300000-E	305	18" DRAINAGE PIPE	20 LF		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	176 LF		
0010	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (48")	48 LF		
0011	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	52 LF		
0012	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	52 LF		
0013	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	36 LF		
0014	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	132 LF		
0015	0448700000-E	310	42" RC PIPE CULVERTS, CLASS IV	52 LF		
0017	0995000000-E	340	PIPE REMOVAL	307 LF		
0018	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1121000000-E	520	AGGREGATE BASE COURSE	17,500 TON		
0020	1231000000-E	560	SHOULDER BORROW	2,260 CY		
0021	1330000000-E	607	INCIDENTAL MILLING	180 SY		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,990 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	205 TON		
0024	2209000000-E	838	ENDWALLS	25 CY		
0025	3030000000-E	862	STEEL BEAM GUARDRAIL	1,443.75 LF		
0026	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	8 EA		
0027	3628000000-E	876	RIP RAP, CLASS I	105 TON		
0028	3649000000-E	876	RIP RAP, CLASS B	155 TON		
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	890 SY		
0030	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (TYPE E)	12.5 SF		
0031	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	20 LF		
0032	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (TYPE E)	2 EA		
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	2 EA		
0034	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	2 EA		
0035	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	64 SF		

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	99,290 LF		
0038	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	50 LF		
0039	6000000000-E	1605	TEMPORARY SILT FENCE	6,065 LF		
0040	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,790 TON		
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	550 TON		
0043	6015000000-E	1615	TEMPORARY MULCHING	13.5 ACR		
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,000 LB		
0045	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	5 TON		
0046	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0047	6029000000-E	SP	SAFETY FENCE	320 LF		
0048	6030000000-E	1630	SILT EXCAVATION	2,920 CY		
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	22,695 SY		
0050	6037000000-E	SP	COIR FIBER MAT	100 SY		
0051	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,500 SY		
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	520 LF		

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	6070000000-N	1639	SPECIAL STILLING BASINS	3 EA		
0054	6071020000-E	SP	POLYACRYLAMIDE (PAM)	120 LB		
0055	6071030000-E	1640	COIR FIBER BAFFLE	20 LF		
0056	6084000000-E	1660	SEEDING & MULCHING	15 ACR		
0057	6087000000-E	1660	MOWING	9 ACR		
0058	6090000000-E	1661	SEED FOR REPAIR SEEDING	150 LB		
0059	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0060	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	375 LB		
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	10.75 TON		
0062	6111000000-E	SP	IMPERVIOUS DIKE	155 LF		
0063	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0065	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0066	0036000000-E	225	UNDERCUT EXCAVATION	3,000 CY		
0067	0996000000-N	350	PIPE CLEAN OUT	2 EA		
0068	0248000000-N	SP	GENERIC GRADING ITEM STATE SUPPLIED ALUMINUM BOX CULVERT @ STATION 113+42 -L- (15'4" X 6'5")	Lump Sum	L.S.	
0069	0248000000-N	SP	GENERIC GRADING ITEM STATE SUPPLIED PIPE @ STATION 49+43 -L- (87" X 63")	Lump Sum	L.S.	

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	0987000000-E	310	GENERIC PIPE ITEM 64" X 43" CAA PIPE ARCH CULVERT, 0.135" THICK	52 LF		

1022/Nov30/Q184889/D237506150000/E69

Total Amount Of Bid For Entire Project :
