

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1.1 ACR		
0004	0036000000-E	225	UNDERCUT EXCAVATION	100 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	550 SY		
0008	0241000000-E	SP	GENERIC GRADING ITEM GEOTEXTILE FOR SUBGRADE STABILIZATION	900 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	30 TON		
0010	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	80 SY		
0011	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	108 LF		
0012	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	40 LF		
0013	0448700000-E	310	42" RC PIPE CULVERTS, CLASS IV	88 LF		
0014	0995000000-E	340	PIPE REMOVAL	134 LF		
0015	1099500000-E	505	SHALLOW UNDERCUT	450 CY		
0016	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	900 TON		
0017	1110000000-E	510	STABILIZER AGGREGATE	10 TON		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1220000000-E	545	INCIDENTAL STONE BASE	60 TON		
0019	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1.5")	520 SY		
0020	1330000000-E	607	INCIDENTAL MILLING	1,000 SY		
0021	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,770 TON		
0022	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,525 TON		
0023	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,425 TON		
0024	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	240 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	11 TON		
0026	1736000000-E	723	SELECT MATERIAL, CLASS IV	600 TON		
0027	2022000000-E	815	SUBDRAIN EXCAVATION	68 CY		
0028	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	300 SY		
0029	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	51 CY		
0030	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
0031	2070000000-N	815	SUBDRAIN PIPE OUTLET	2 EA		
0032	2077000000-E	815	6" OUTLET PIPE	12 LF		
0033	2209000000-E	838	ENDWALLS	4.5 CY		
0034	2753000000-E	846	GENERIC PAVING ITEM (3" ROLLED CURB)	370 LF		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	340 LF		
0036	2591000000-E	848	4" CONCRETE SIDEWALK	60 SY		
0037	2605000000-N	848	CONCRETE CURB RAMPS	6 EA		
0038	2612000000-E	848	6" CONCRETE DRIVEWAY	60 SY		
0039	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	30 SY		
0040	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	740 SY		
0041	2738000000-E	SP	GENERIC PAVING ITEM 10" JOINTED CONC TRUCK APRON	370 SY		
0042	3030000000-E	862	STEEL BEAM GUARDRAIL	325 LF		
0043	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	50 LF		
0044	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0045	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0046	3287000000-N	862	GUARDRAIL END UNITS, TYPE TL-3	1 EA		
0047	3628000000-E	876	RIP RAP, CLASS I	40 TON		
0048	3649000000-E	876	RIP RAP, CLASS B	11 TON		
0049	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	475 SY		
0050	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	210 SF		
0051	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	50 SF		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	443 LF		
0053	4102000000-N	904	SIGN ERECTION, TYPE E	36 EA		
0054	4108000000-N	904	SIGN ERECTION, TYPE F	4 EA		
0055	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	18 EA		
0056	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	799 SF		
0057	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	256 SF		
0058	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	208 SF		
0059	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	6 EA		
0060	4430000000-N	1130	DRUMS	23 EA		
0061	4435000000-N	1135	CONES	47 EA		
0062	4445000000-E	1145	BARRICADES (TYPE III)	128 LF		
0063	4447000000-E	SP	PEDESTRIAN CHANNELIZING DEVICES	32 LF		
0064	4455000000-N	1150	FLAGGER	25 DAY		
0065	4510000000-N	1190	LAW ENFORCEMENT	40 HR		
0066	4516000000-N	1180	SKINNY DRUM	8 EA		
0067	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM PEDESTRIAN TRANSPORT SERVICE	4 EA		
0068	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	10,320 LF		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	84 LF		
0070	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	500 LF		
0071	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	190 LF		
0072	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	31 EA		
0073	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	860 LF		
0074	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,380 LF		
0075	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	100 LF		
0076	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	110 LF		
0077	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	88 EA		
0078	5265000000-E	SP	GENERIC LIGHTING ITEM INSTALL 2" ELEC CONDUIT - DIRECT BURY	2,400 LF		
0079	6000000000-E	1605	TEMPORARY SILT FENCE	4,430 LF		
0080	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0081	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	620 TON		
0082	6012000000-E	1610	SEDIMENT CONTROL STONE	255 TON		
0083	6015000000-E	1615	TEMPORARY MULCHING	8 ACR		
0084	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	600 LB		
0085	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	3 TON		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400 LF		
0087	6029000000-E	SP	SAFETY FENCE	320 LF		
0088	6030000000-E	1630	SILT EXCAVATION	900 CY		
0089	6036000000-E	1631	MATTING FOR EROSION CONTROL	12,500 SY		
0090	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	440 SY		
0091	6042000000-E	1632	1/4" HARDWARE CLOTH	375 LF		
0092	6070000000-N	1639	SPECIAL STILLING BASINS	1 EA		
0093	6071002000-E	1642	FLOCCULANT	247 LB		
0094	6071010000-E	1642	WATTLE	70 LF		
0095	6071030000-E	1640	COIR FIBER BAFFLE	25 LF		
0096	6084000000-E	1660	SEEDING & MULCHING	9.6 ACR		
0097	6087000000-E	1660	MOWING	6.5 ACR		
0098	6090000000-E	1661	SEED FOR REPAIR SEEDING	150 LB		
0099	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0100	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	250 LB		
0101	6108000000-E	1665	FERTILIZER TOPDRESSING	5.8 TON		
0102	6111000000-E	SP	IMPERVIOUS DIKE	64 LF		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	6114500000-N	1667	SPECIALIZED HAND MOWING	20 MHR		
0104	6114800000-N	SP	MANUAL LITTER REMOVAL	4 MHR		
0105	6114900000-E	SP	LITTER DISPOSAL	1 TON		
0106	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	30 EA		
0107	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	3 EA		
0108	6141000000-E	SP	GENERIC EROSION CONTROL ITEM COIR FIBER MAT	100 SY		
0109	6147000000-E	SP	GENERIC EROSION CONTROL ITEM COIR FIBER WATTLE	360 LF		
0110	7060000000-E	1705	SIGNAL CABLE	550 LF		
0111	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	5 EA		
0112	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	1 EA		
0113	7264000000-E	1710	MESSENGER CABLE (3/8")	225 LF		
0114	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	425 LF		
0115	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	3 EA		
0116	7360000000-N	1720	WOOD POLE	1 EA		
0117	7372000000-N	1721	GUY ASSEMBLY	4 EA		
0118	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	350 LF		
0119	7456100000-E	1726	LEAD-IN CABLE (14-2)	1,000 LF		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0120	7481000000-N	SP	SITE SURVEY	1 EA		
0121	7481200000-N	SP	LUMINAIRE ARM FOR VIDEO SYSTEM	1 EA		
0122	7481240000-N	SP	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT	1 EA		
0123	7481260000-N	SP	EXTERNAL LOOP EMULATOR PROCESSING UNIT	1 EA		
0124	7744000000-N	1751	DETECTOR CARD (TYPE 170)	1 EA		
0125	7980000000-N	SP	GENERIC SIGNAL ITEM 2070LX CONTROLLER	1 EA		
0126	7980000000-N	SP	GENERIC SIGNAL ITEM RECTANGULAR RAPID FLASHING BEACON	4 EA		

0752/Mar03/Q57589/D528238442000/E126

Total Amount Of Bid For Entire Project :