PROPOSED ALIGNMENT CONTROL SHEET

PROJECT REFERENCE NO.	SHEET NO.
HL-0008Q	RW02D-1
Location and Surveys	

GEL Engineering of NC, Inc. C-1938

GEL SOLUTIONS
an Affiliate of THE GEL GROUP, INC.
2700 SUMNER BLVD.
SUITE 106
RALEIGH,NC 27616
(919) 544-1100
WWW.GEL-SOLUTIONS.COM

NORTH CAROLINA GEL ENGINEERING OF NC, INC. NO. C-1938 CERTIFICATE OF AUTHORIZATION

NORTH CAROLINA PROFESSIONAL SEAL L-3996 LAND SURVEYOR PARKS H. ICENHOUR JR.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

I, Parks H. Icenhour Jr., PLS, certify that the data compiled came from available surveys/mapping performed by others and provided to me by NCDOT and do not certify to the accuracy or quality of the individual data sources.

This 17th day of November, 2025.

Digitally signed by Parks H. Icenhour, Jr.
Date: 2025.11.17 14:38:34 -05'00'

Professional Land Surveyor L-3996

L

TYPE	STATION	NORTH	EAST
POT	10+00.00	695464.1592	2074784.3786
PC	11+55.70	695430.2247	2074936.3353
PT	14+17.86	695352.8881	2075186.5352
PC	17+95.52	695212.8561	2075537.2767
PT	20+29.36	695137.7402	2075758.6037
PC	22+05.94	695089.8705	2075928.5741
PT	25+97.57	695019.7127	2076313.2874
PC	26+49.72	695015.2209	2076365.2437
PT	29+21.25	695002.3454	2076636.3906
POT	29+70.17	695001.9217	2076685.3162

Y

TYPE	STATION	NORTH	EAST
POT	100+00.00	696016.7235	2075574.6072
PC	101+43.13	695874.0534	2075563.1907
PT	104+59.19	695561.5739	2075596.4599
PC	108+87.10	695151.7800	2075719.6356
PT	114+83.92	694598.2581	2075941.6603
POT	119+00.00	694223.2017	2076121.8072

NOTES:

1. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
2. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
3. RIGHT OF WAY MONUMENTATION ESTABLISHED 10/20/2025 TO 10/27/2025.

REVISIONS

6/2/99

17-NOV-2025 08:52
C:\NCDOT\HL-0008Q\RIGHTOFWAAY\TRY\HL0008Q_LS_RW2D_GEL-2_251104.dgn
jason.revette
AT PREVATTE)