| STATE PROJ. REFERENCE NO. | SHEET NO. |
|---|---|
| W-5206Z | SIGN-1 |

APPROVED: [signature]

DATE: 1/26/2015

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 033822 ENGINEER JONATHAN P. SOIKA

# STATE OF NORTH CAROLINA
# DEPARTMENT OF TRANSPORTATION

# SIGNING PLAN
# CUMBERLAND COUNTY

***LOCATION: SR 1103 (Galatia Church Rd) at SR 1102 (Gillis Hill Rd)***
***SR 1103 (Galatia Church Rd) at SR 1112 (Stoney Point Rd)***
***and SR 1112 (Stoney Point Rd) at SR 1102 (Gillis Hill Rd)***

## ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|---|---|
| 904.10 | ORIENTATION OF GROUND MOUNTED SIGNS |
| 904.50 | MOUNTING OF TYPE 'D', 'E', AND 'F' SIGNS ON 'U' CHANNEL POSTS |

## PROJECT NOTES

1. DISPOSAL OF SIGN SYSTEM, U CHANNEL
2. SIGN ERECTION, RELOCATED, TYPE "E" SIGN
3. DISPOSAL OF SUPPORT, U CHANNEL

## GENERAL NOTES

. SIGNS FURNISHED BY STATE

. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.

. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER

. WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.

. THE BACKGROUND FOR TYPE E SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

. SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTURCTION SIGNING OR PAVEMENT MARKINGS. SEE TRAFFIC CONTROL PLANS.

## SUMMARY OF QUANTITIES

| ITEM NO. | | ITEM DESCRIPTION | QUANTITY | UNIT |
|---|---|---|---|---|
| DESC. NO. | SECT. NO. | | | |
| 4072000000 | 903 | SUPPORTS, 3 LB STEEL U-CHANNEL | 257 | L.F. |
| 4102000000 | 904 | SIGN ERECTION, TYPE E | 16 | EA. |
| 4116100000 | 904 | SIGN ERECTION, RELOCATE SIGN TYPE E | 8 | EA. |
| 4155000000 | 907 | DISPOSAL OF SIGN SYSTEM, U-CHANNEL | 16 | EA. |
| 4192000000 | 907 | DISPOSAL OF SUPPORT, U-CHANNEL | 4 | EA. |

## INDEX


| SHEET NO. | DESCRIPTION |
|---|---|
| SIGN-1 | TITLE SHEET |
| SIGN-2 | E SHEET |
| SIGN-3-5 | SIGN DETAIL SHEETS |



***PLAN PREPARED BY: VHB Engineering NC, P.C.***

*Jonathan P. Soika, PE* PROJECT ENGINEER

vhb Engineers | Scientists | Planners | Designers
4000 WestChase Boulevard, Suite 530 Raleigh, NC 27607
NC License No. C-3705


**PROJECT: 45336.2.FD26 T.I.P.: W-5206Z**

1/23/2015
W5206Z_TC_SIGN_01.dgn
sbrown