



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

June 30, 2015

NOTICE TO PROSPECTIVE BIDDERS

Subject: Invitation to Bid
TIP No.: U-5524
Federal Aid: HPP-0627(7)
WBS: 50067.3.FD1
County: Robeson
Description: Grading, Drainage, Paving, Signing, & Pavement Markings

The North Carolina Department of Transportation is requesting bids for grading, drainage, paving, signing and pavement markings on Water Street (SR 1536) from 5th Street (SR 1600) to 8th Street in Robeson County. The project will include the approximate quantities as attached. The Contractor is to furnish labor, materials, equipment, and traffic control.

The availability date for this project is September 14, 2015.

The completion date is June 22, 2016.

Sealed bids must be received in the Division Proposals Engineer's Office at 558 Gillespie Street, Fayetteville, NC, 28301 by **10:00 AM on Wednesday, July 22, 2015**. Bids must be submitted on the official bid sheet included in the proposal and display the following statements on the front of the sealed envelope:

- 1. QUOTATION FOR WORK ORDER 50067.3.FD1, U-5524, GRADING, DRAINAGE, PAVING, SIGNING & PAVEMENT MARKINGS ON SR 1536 WITH IMPROVEMENTS FROM SR 1600 TO 8TH ST. IN ROBESON COUNTY, TO BE OPENED AT 10:00 AM ON WEDNESDAY, JULY 22, 2015.**
- 2. THE BIDDING CONTRACTOR'S NAME, ADDRESS & PHONE NUMBER.**

In accordance with NC General Statute G.S. 44A-26, a Performance Bond and a Payment Bond in the amount of one hundred percent (100%) of the contract amount, conditioned upon the faithful performance of the contract in accordance with the specifications and conditions of the contract, are required for construction contracts of \$500,000 or more. Such bond shall be solely for the protection of the North Carolina Department of Transportation and the State of North Carolina.

MAILING ADDRESS:
NC DEPT. OF TRANSPORTATION
DIVISION SIX
PO Box 1150
FAYETTEVILLE, NC 28302

PHONE: 910-486-1493
FAX: 910-486-1959
WEBSITE: WWW.NCDOT.ORG

LOCATION:
NC DEPT. OF TRANSPORTATION
DIVISION SIX
558 GILLESPIE ST.
FAYETTEVILLE, NC 28301

The North Carolina Department of Transportation, in accordance with the provisions of Title VI of the Civil Rights of 1964 (78 Stat.252) and the Regulations of the Department of Transportation (49 C.F.R., Part 21), issued pursuant to such act, hereby notifies all bidders that it will affirmatively insure that the contract entered into pursuant to this notice will be awarded to the lowest responsible bidder without discrimination on the grounds of sex, race, color, or national origin.

Any firm that wishes to bid as a prime contractor shall be prequalified as a Bidder or PO Prime Contractor prior to submitting a bid. Information regarding prequalification can be found at:
<https://connect.ncdot.gov/business/Prequal/Pages/default.aspx>.

In addition, the prime contractor and/or subcontractor(s) shall be prequalified in the work code(s) for which they identify as work items in the prime contractor's construction progress schedule that they will complete themselves. Any contractor identified as working outside their expertise may be considered in default of contract.

Statements of Disadvantaged Business Enterprise (DBE) participation must be presented with the bids.


Proposals may be obtained from the Division Six web site:

https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=6

Should you have questions, need additional information concerning this project, or need additional information pertaining to the bidding or bidding process, please contact Allen Waddell, Division Proposals Engineer at (910)-486-1493.

Sincerely,

DocuSigned by:


F06892B7CB3147E...

R. Allen Waddell, P.E.
Division Proposals Engineer

Attachment

cc: Greg Burns, P.E.
Ken Murphy, P.E.
Randy Wise, P.E.
Jerry Bradley, P.E.
Scott Pridgen
Mike Parker
Chuck Miller, P.E.

PROJECT NUMBER: 50067.3.FD1

COUNTY: Robeson

DESCRIPTION: Grading, Drainage, Paving, Signing, & Pavement Markings

BID DATE: July 22, 2015

LINE #	ITEM NUMBER	SEC #	DESCRIPTION	QTY	UNIT
1	0000100000-N	800	Mobilization	1	LS
2	0000400000-N	801	Construction Surveying	1	LS
3	0000960000-E	SP	Concrete Dye	770	SY
4	0000960000-E	SP	Decorative Crosswalk (TPPM)	225	SY
5	0008000000-E	200	Supplementary Clearing and Grubbing	1	ACR
6	0036000000-E	226	Undercut Excavation	450	CY
7	0043000000-N	226	Grading	1	LS
8	0106000000-E	230	Borrow Excavation	4,500	CY
9	0196000000-E	270	Geotextile for Soil Stabilization	750	CY
10	0255000000-E	SP	Stockpiling Contaminated Soil	15	TON
11	0318000000-E	300	Foundation Conditioning Material, Minor Structures	190	TON
12	0320000000-E	300	Foundation Conditioning Geotextile	580	SY
13	0448000000-E	310	48" RC Pipe Culverts, Class IV	324	LF
14	0448200000-E	310	15" RC Pipe Culverts, Class IV	620	LF
15	0448300000-E	310	18" RC Pipe Culverts, Class IV	204	LF
16	0448400000-E	310	24" RC Pipe Culverts, Class IV	100	LF
17	0986000000-E	SP	15" HDPE Pipe Culvert	336	LF
18	0986000000-E	SP	18" HDPE Pipe Culvert	136	LF
19	0995000000-E	340	Pipe Removal	316	LF
20	1099500000-E	505	Shallow Undercut	100	CY
21	1099700000-E	505	Class IV Subgrade Stabilization	200	TON
22	1121000000-E	520	Aggregate Base Course	122	TON
23	1220000000-E	545	Incidental Stone	100	TON
24	1308000000-E	607	Milling Asphalt Pavement, 0" TO 1 1/2"	1,430	SY
25	1330000000-E	607	Incidental Milling	450	SY
26	1489000000-E	610	Asphalt Concrete Base Course, Type B25.0B	1,070	TON
27	1498000000-E	610	Asphalt Concrete Intermediate Course, Type I19.0B	980	TON
28	1519000000-E	610	Asphalt Concrete Surface Course, Type S9.5B	780	TON
29	1575000000-E	620	Asphalt Binder for Plant Mix	145	TON
30	1693000000-E	654	Asphalt Plant Mix, Pavement Repair	100	TON

31	1891000000-E	SP	6" Concrete Apron (PCC)-Dyed	350	SY
32	2264000000-E	840	Pipe Plugs	1.1	CY
33	2275000000-E	SP	Flowable Fill	75	CY
34	2286000000-E	840	Masonry Drainage Structures	35	EA
35	2364000000-N	840	Frame with Two Grates, Std 840.16	10	EA
36	2366000000-N	840	Frame with Two Grates, Std 840.24	1	EA
37	2367000000-N	840	Frame with Two Grates, Std 840.29	2	EA
38	2374000000-N	840	Frame with Grate & Hood, Std 840.03 Type "E"	8	EA
39	2374000000-N	840	Frame with Grate & Hood, Std 840.03 Type "F"	7	EA
40	2374000000-N	840	Frame with Grate & Hood, Std 840.03 Type "G"	5	EA
41	2396000000-N	840	Frame with Cover, Std 840.54	2	EA
42	2535000000-E	846	9"x18" Concrete Curb	300	LF
43	2538000000-E	846	1'-6" Concrete Curb and Gutter (Drives - vertical face)	227	LF
44	2542000000-E	846	1'-6" Concrete Curb & Gutter (mountable median curb)	372	LF
45	2549000000-E	846	2'-6" Concrete Curb and Gutter	1,600	LF
46	2591000000-E	848	4" Concrete Sidewalk	920	SY
47	2605000000-E	848	Concrete Curb Ramp	10	EA
48	2612000000-E	848	6" Concrete Driveway	32	SY
49	2655000000-E	852	5" Monolithic Concrete Island (Keyed In)-Dyed	420	SY
50	3656000000-E	876	Geotextile for Drainage	340	SY
51	4026000000-E	901	Department Furnished, Type E Sign	188	SF
52	4072000000-E	903	Supports, 3 LB Steel U-Channel	405	LF
53	4102000000-N	904	Sign Erection, Type 'E'	44	EA
54	4155000000-N	907	Disposal of Sign System, U-Channel	5	EA
55	4400000000-E	1110	Stationary Work Zone Signs	558	SF
56	4410000000-E	1110	Barricade Mounted Work Zone Signs	144	SF
57	4445000000-E	1145	Barricades (Type III)	282	LF
58	4685000000-E	1205	Thermoplastic (4", 90 Mils)	911	LF
59	4686000000-E	1205	Thermoplastic (4", 120 Mils)	1,940	LF
60	4695000000-E	1205	Thermoplastic (8", 90 Mils)	255	LF
61	4697000000-E	1205	Thermoplastic (8", 120 Mils)	375	LF
62	4710000000-E	1205	Thermoplastic (24", 120 Mils)	23	LF

63	4721000000-E	1205	Thermoplastic Pavement Marking Character (120 Mils)	4	EA
64	4725000000-E	1205	Thermoplastic Pavement Marking Symbol (90 Mils)	22	EA
65	4900000000-N	1251	Permanent Raised Pavement Markers	35	EA
66	5888000000-E	SP	4" PVC Conduit	300	LF
67	6000000000-E	1605	Temporary Silt Fence	1,500	LF
68	6006000000-E	1610	Erosion Control Stone, Class A	115	TON
69	6009000000-E	1610	Erosion Control Stone, Class B	50	TON
70	6012000000-E	1610	Sediment Control Stone	260	TON
71	6015000000-E	1615	Temporary Mulching	1.50	ACR
72	6018000000-E	1620	Seed for Temporary Seeding	100	LB
73	6021000000-E	1620	Fertilizer for Temporary Seeding	0.50	TON
74	6024000000-E	1622	Temporary Slope Drains	200	LF
75	6029000000-E	SP	Safety Fence	1,000	LF
76	6030000000-E	1630	Silt Excavation	40	CY
77	6036000000-E	1631	Matting for Erosion Control	2,500	SY
78	6042000000-E	1632	1/4" Hardware Cloth	1,170	LF
79	6048000000-E	SP	Floating Turbidity Curtain	45	SY
80	6071012000-E	SP	Coir Fiber Wattle	45	LF
81	6071030000-E	1640	Coir Fiber Baffle	30	LF
82	6084000000-E	1660	Seeding and Mulching	3.00	ACR
83	6087000000-E	1660	Mowing	3.00	ACR
84	6090000000-E	1661	Seed for Repair Seeding	50	LB
85	6093000000-E	1661	Fertilizer for Repair Seeding	0.25	TON
86	6096000000-E	1662	Seed for Supplemental Seeding	50	LB
87	6108000000-E	1665	Fertilizer for Topdressing	1.25	TON
88	6114500000-N	1667	Specialized Hand Mowing	10	MHR
89	6117000000-N	SP	Response for Erosion Control	25	EA
90	7444000000-E	1725	Inductive Loop Sawcut	325	LF
91	7948000000-E	1757	Traffic Signal Removal	1	EA