



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

July 8, 2015

NOTICE TO PROSPECTIVE BIDDERS

Subject: Invitation to Bid
TIP No.: NA
Federal Aid: NA
WBS: 36052.103
County: Cumberland
Description: Grading, Paving, Drainage, Utility Construction, & Pavement Markings

The North Carolina Department of Transportation is requesting bids for grading, paving, drainage, utility construction and pavement markings on Russell St (SR 2299) from Gillespie Street to Cross Creek Street in Cumberland County. The project will include the approximate quantities as attached. The Contractor is to furnish labor, materials, equipment, and traffic control.

The availability date for this project is August 10, 2015.

The completion date is December 1, 2015.

Sealed bids must be received in the Division Proposals Engineer's Office at 558 Gillespie Street, Fayetteville, NC, 28301 by **10:00 AM on Wednesday, July 22, 2015**. Bids must be submitted on the official bid sheet included in the proposal and display the following statements on the front of the sealed envelope:

- 1. QUOTATION FOR DF00100 – WBS 36052.103
GRADING, PAVING, DRAINAGE, UTILITY CONSTRUCTION & PAVEMENT
MARKINGS TO BE OPENED AT 10:00 AM ON WEDNESDAY, JULY 22, 2015.**
- 2. THE BIDDING CONTRACTOR'S NAME, ADDRESS & PHONE NUMBER.**

Potential Bidders should take note of the following special conditions for this contract:

- 1. A performance bond in the amount of one hundred percent (100%) of the contract amount, conditioned upon the faithful performance of the contract in accordance with specifications and conditions of the contract shall be required.**
- 2. A payment bond in the amount of one hundred percent (100%) of the contract amount, conditioned upon the prompt payment for all labor or materials for which the Contractor, or his subcontractors, is liable, shall be required.**

MAILING ADDRESS:
NC DEPT. OF TRANSPORTATION
DIVISION SIX
PO Box 1150
FAYETTEVILLE, NC 28302

PHONE: 910-486-1493
FAX: 910-486-1959
WEBSITE: WWW.NCDOT.ORG

LOCATION:
NC DEPT. OF TRANSPORTATION
DIVISION SIX
558 GILLESPIE ST.
FAYETTEVILLE, NC 28301

3. **Required Railroad Protective Liability Insurance**, in addition to the standard NCDOT Insurance requirements. See “**CSX RAILROAD SPECIAL PROVISIONS**”, beginning on page 67 in the Contract Proposal.

The North Carolina Department of Transportation, in accordance with the provisions of Title VI of the Civil Rights of 1964 (78 Stat.252) and the Regulations of the Department of Transportation (49 C.F.R., Part 21), issued pursuant to such act, hereby notifies all bidders that it will affirmatively insure that the contract entered into pursuant to this notice will be awarded to the lowest responsible bidder without discrimination on the grounds of sex, race, color, or national origin.

Any firm that wishes to bid as a prime contractor shall be prequalified as a Bidder or PO Prime Contractor prior to submitting a bid. Information regarding prequalification can be found at:
<https://connect.ncdot.gov/business/Prequal/Pages/default.aspx>.

In addition, the prime contractor and/or subcontractor(s) shall be prequalified in the work code(s) for which they identify as work items in the prime contractor's construction progress schedule that they will complete themselves. Any contractor identified as working outside their expertise may be considered in default of contract.

Statements of Minority Business Enterprise (MBE) & Women Business Enterprise (WBE) participation must be presented with the bids.


Proposals may be obtained from the Division Six web site:

https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=6

Should you have questions, need additional information concerning this project, or need additional information pertaining to the bidding or bidding process, please contact Allen Waddell, Division Proposals Engineer at (910)-486-1493.

Sincerely,

DocuSigned by:



F06892B7CB3147E...

R. Allen Waddell, P.E.
Division Proposals Engineer

Attachment

cc: Greg Burns, P.E.
Ken Murphy, P.E.
Randy Wise, P.E.
Jerry Bradley, P.E.
Scott Pridgen
Jason Salisbury

PROJECT NUMBER: 36052.103
COUNTY: Cumberland
DESCRIPTION: Grading, Paving, Drainage, Utility Construction & Pavement Markings
BID DATE: July 22, 2015

LINE #	ITEM NUMBER	SEC #	DESCRIPTION	QTY	UNIT
1	0000100000-N	800	Mobilization	1	LS
2	0000400000-N	801	Construction Surveying	1	LS
3	0036000000-E	226	Undercut Excavation	150	CYD
4	0043000000-N	226	Grading	1	LS
5	0106000000-N	226	Borrow Excavation	730	CYD
6	0194000000-E	SP	Select Granular Material, Class III	160	CYD
7	0318000000-E	300	Foundation Conditioning Material, Minor Structures	150	TON
8	0320000000-E	300	Foundation Conditioning Geo-Textile	270	SYD
9	0448200000-E	310	15" RC Pipe Culverts Class IV	64	LFT
10	0448300000-E	310	18" RC Pipe Culverts Class IV	24	LFT
11	0448400000-E	310	24" RC Pipe Culverts Class IV	24	LFT
12	0448600000-E	310	36" RC Pipe Culverts Class IV	696	LFT
13	0995000000-E	340	Pipe Removal	161	LFT
14	1077000000-E	SP	Stone # 57	1,150	TON
15	1220000000-E	545	Incidental Stone Base	100	TON
16	1308000000-E	607	Milling Asphalt Pavement, 1 1/2"	1,325	SYD
17	1330000000-E	607	Incidental Milling	835	SYD
18	1491000000-E	610	Asphalt Conc Base Course, Type B25.0C	325	TON
19	1503000000-E	610	Asphalt Conc Intermediate Course, TYPE I19.0C	225	TON
20	1523000000-E	610	Asphalt Conc Surface Course, TYPE S9.5C	375	TON
21	1575000000-E	620	Asphalt Binder For Plant Mix PG64-22	50	TON
22	1693000000-E	654	Asphalt Plant Mix, Pavement Repair	50	TON
23	2253000000-E	840	Pipe Collars	3.5	CY
24	2264000000-E	840	Pipe Plugs	1.1	CY

25	2275000000-E	SP	Flowable Fill	50	CY
26	2286000000-N	840	Masonry Drainage Structures	18	EA
27	2297000000-E	840	Masonry Drainage Structures	58	LF
28	2374000000-N	840	Frame With Grate & Hood, STD 840.03 Type F	7	EA
29	2396000000-N	840	Frame With Cover, STD 840.54	11	EA
30	2549000000-E	846	2'-6" Concrete Curb & Gutter	570	LFT
31	2591000000-E	848	4" Concrete Sidewalk	250	SYD
32	2605000000-N	848	Concrete Curb Ramp	4	EA
33	2612000000-E	848	6" Concrete Driveways	100	SY
34	2920000000-N	859	Convert Existing Drop Inlet To Catch Basin	2	EA
35	3656000000-E	876	Geotextile For Drainage	2,000	SYD
36	4400000000-E	1110	Work Zone Signs (Stationary)	115	SF
37	4405000000-E	1110	Work Zone Signs (Portable)	109	SF
38	4410000000-E	1110	Barricade Mounted Work Zone Signs	122	SF
39	4415000000-N	1115	Flashing Arrow Board	1	EA
40	4420000000-N	1120	Portable Changeable Message Sign	6	EA
41	4422000000-N	1120	Portable Changeable Message Sign (Short Term)	6	DAY
42	4430000000-N	1130	Drums	106	EA
43	4445000000-E	1145	Barricades (Type III)	304	LF
44	4510000000-N	SP	Law Enforcement	30	HR
45	4686000000-E	1205	Thermoplastic (4", 120 Mils)	350	LF
46	4697000000-E	1205	Thermoplastic (8", 120 Mils)	180	LF
47	4710000000-E	1205	Thermoplastic (24", 120 Mils)	60	LF
48	4725000000-E	1205	Thermoplastic Pavement Marking Symbol (90 Mils)	2	EA
49	4900000000-N	1251	Permanent Raised Pavement Markers	25	EA
50	5325400000-E	1510	4" RJDIP Water Line	14	LF
51	5325600000-E	1510	6" RJDIP Water Line	23	LF
52	5325800000-E	1510	8" RJDIP Water Line	86	LF

53	5326200000-E	1510	12" DIP Water Line	320	LF
54	5326200000-E	1510	12" RJDIP Water Line	614	LF
55	5538000000-E	1515	4" Gate Valve	1	EA
56	5540000000-E	1515	6" Gate Valve	2	EA
57	5643000000-E	1515	1" Water Meter, Copper Tubing	5	EA
58	5546000000-E	1515	8" Gate Valve	4	EA
59	5649000000-N	1515	Reconnect Water Meter, 1" Copper Tubing	5	EA
60	5558000000-E	1515	12" Gate Valve	3	EA
61	5666000000-E	1515	Fire Hydrant	3	EA
62	5689000000-E	1515	Generic Utility Item, Abandon Water Mains	3	EA
63	5689000000-E	1515	Generic Utility Item, Abandon Valves	9	EA
64	5691100000-E	1520	4" DIP Sanitary Sewer	3	LF
65	5691300000-E	1520	8" DIP Sanitary Sewer Main, 10'-12' Depth	27	LF
66	6000000000-E	1605	Temporary Silt Fence	500	LF
67	6009000000-E	1610	Erosion Control Stone, Class B	10	TON
68	6012000000-E	1610	Sediment Control Stone	15	TON
69	6015000000-E	1615	Temporary Mulching	.25	ACR
70	6018000000-E	1620	Seed for Temporary Seeding	15	LB
71	6021000000-E	1620	Fertilizer for Temporary Seeding	0.1	TON
72	6029000000-E	SP	Safety Fence	500	LF
73	6042000000-E	1632	1/4" Hardware Cloth	250	LF
74	6084000000-E	1660	Seeding and Mulching	0.25	ACR
75	6090000000-E	1661	Seed for Repair Seeding	50	LB
76	6093000000-E	1661	Fertilizer for Repair Seeding	.25	TON
77	6096000000-E	1662	Seed for Supplemental Seeding	25	LB
78	6108000000-E	1665	Fertilizer for Topdressing	0.25	TON
79	6117000000-N	SP	Response for Erosion Control	3	EA
80	7444000000-E	1725	Inductive Loop Sawcut	250	LF