




**CAROLINAS
GEOTECHNICAL
GROUP**

Structure Foundation Recommendations, REV. 1

Prepared for:

TGS Engineers, Inc.
201 West Marion Street, Suite 200
Shelby, North Carolina 28150

February 28, 2023





2400 Crownpoint Executive Drive
Suite 800
Charlotte, NC 28227

(980) 339-8684
contact@carolinasgeotech.com
www.carolinasgeotech.com

February 28, 2023

Mr. Jimmy L. Terry, P.E.
TGS Engineers, Inc.
201 West Marion Street, Suite 200
Shelby, North Carolina 28150

WBS ELEMENT: 50347.1.1
T.I.P. NO.: HB-0007
I.D. NO.: SF-770300
COUNTY: Robeson
DESCRIPTION: Bridge No. 300 on SR 1529 (Mt. Olive Church Road) over Saddletree Swamp

SUBJECT: Structure Foundation Recommendations, REV. 1

Dear Mr. Terry:

Carolinas Geotechnical Group, PLLC (CG2) has completed the Structure Foundation Recommendations for the proposed replacement of Bridge No. 770300 on SR 1529 (Mt. Olive Church Road) over Saddletree Swamp in Robeson County, North Carolina. The revised Structure Foundation Recommendations are attached. The supporting calculations will be submitted under separate cover.

CG2 is pleased to have the opportunity to provide these services to you and looks forward to working with you on your project. If you have questions concerning the content of this letter, or if CG2 can be of further service, please contact CG2 at (980) 339-8684.

Sincerely,
Carolinas Geotechnical Group, PLLC

DocuSigned by:

D. Matthew Brewer

386129C0A4C1462...

D. Matthew Brewer, P.E.
Senior Project Engineer

DocuSigned by:

Robert E. Kral

8AD703B2A8484F4...

Robert E. Kral, P.E.
Senior Project Engineer



Structure Foundation Recommendations, REV. 1

Bridge No. 300 on SR 1529 (Mt. Olive Church Road) over Saddletree Swamp

Robeson County, North Carolina

ATTACHMENTS:

Foundation Recommendation Sheet(s)

Foundation Recommendations Notes on Plans Sheet(s)

Foundation Recommendations Comments Sheet(s)

Geotechnical Foundation Tables


FOUNDATION RECOMMENDATIONS

Prepared for NCDOT by: Carolinas Geotechnical Group, PLLC (CG2)

PROJECT 50347.1.1
 TIP NO. HB-0007
 COUNTY Robeson
 STATION 14+59.50 -L-

DESCRIPTION Bridge No. 300 on SR 1529
(Mt Olive Church Road) over Saddletree Swamp

	INITIALS	DATE
DESIGN	REK	2/28/23
CHECK	DMB	2/28/23



	BENT STATION	FOUNDATION TYPE	FACTORED RESISTANCE	ADDITIONAL INFORMATION
END BENT 1	14+30.88 -L-	4'-0" Cap on HP 12 x 53 Steel H-Piles	71 Tons/Pile	Bottom of Cap Elev. = 128.20 ft Average Estimated Pile Length = 60 ft Number of Plumb Piles/Cap = 7 Pile Spacing = 6'-0"
END BENT 2	14+88.13 -L-	4'-0" Cap on HP 12 x 53 Steel H-Piles	71 Tons/Pile	Bottom of Cap Elev. = 128.20 ft Average Estimated Pile Length = 55 ft Number of Piles/Cap = 7 Pile Spacing = 6'-0"

(SEE NOTES ON PLANS AND COMMENTS ON FOLLOWING PAGES.)

FOUNDATION RECOMMENDATIONS NOTES ON PLANS

1. FOR PILES, SEE PILES PROVISION AND SECTION 450 OF THE STANDARD SPECIFICATIONS.

FOUNDATION RECOMMENDATIONS COMMENTS

1. THE STANDARD HAMMER, A DELMAG D19-32, IS SUFFICIENT TO DRIVE PILES TO THE REQUIRED DRIVING RESISTANCE AT BOTH END BENTS.
2. USE TYPE II MODIFIED BRIDGE APPROACH FILL (STANDARD DRAWING 422.02) AT END BENT 1 AND END BENT 2.
3. 1.5:1 (H:V) OR FLATTER SLOPE AT BOTH END BENTS IS OK WITH RIP RAP SLOPE PROTECTION.
4. NO WAITING PERIOD IS REQUIRED AT EITHER END BENT PRIOR TO CONSTRUCTION.
5. PDA MAY BE REQUIRED TO MONITOR DRIVING STRESSES.
6. AVERAGE PILE LENGTHS ARE BASED ON PLUMB PILES FROM THE PILE CUTOFF ELEVATION TO THE ANTICIPATED TIP ELEVATION, ROUNDED UP TO THE NEAREST 5 FEET.

SUMMARY OF PILE INFORMATION/INSTALLATION

(Blank entries indicate item is not applicable to structure)

End Bent/ Bent No, Pile(s) #-# (e.g., "Bent 1, Piles 1-5")	Factored Resistance per Pile TONS	Pile Cut-Off (Top of Pile) Elevation FT	Estimated Pile Lenth per Pile FT	Scour Critical Elevation FT	Driven Piles			Predrilling for Piles*			Drilled-In Piles		
					Min Pile Tip (Tip No Higher Than) Elev FT	Required Driving Resistance (RDR)** per Pile TONS	Total Pile Redrives Quantity EACH	Predrilling Length per Pile Lin FT	Predrilling Elevation (Elev Not To Predrill Below) FT	Maximum Predrilling Dia INCHES	Pile Excavation (Bottom of Hole) Elev FT	Pile Exc Not In Soil per Pile Lin FT	Pile Exc In Soil per Pile Lin FT
End Bent 1, Piles 1-7	71	130.20	60			120							
End Bent 2, Piles 1-7	71	130.20	55			120							

*Predrilling for Piles is required for end bents/bents with a predrilling length and at the Contractor's option for end bents/bents with predrilling information but no predrilling length.

**RDR =
$$\frac{\text{Factored Resistance} + \text{Factored Downdrag Load} + \text{Factored Dead Load}}{\text{Dynamic Resistance Factor}} + \text{Nominal Downdrag Resistance} + \frac{\text{Nominal Scour Resistance}}{\text{Scour Resistance Factor}}$$

SUMMARY OF PDA/PILE ORDER LENGTHS

(Blank entries indicate item is not applicable to structure)

Pile Driving Analyzer (PDA)				Pile Order Lengths	
End Bent/ Bent No	PDA Testing Required? YES or MAYBE	PDA Test Pile Length FT	Total PDA Testing Quantity EACH	End Bent/ Bent No(s)	Pile Order Length Basis* EST or PDA
End Bent 1	MAYBE	65	1		
End Bent 2	MAYBE	60			

*EST = Pile order lengths from estimated pile lengths; PDA = Pile order lengths based on PDA testing. For groups of end bents/bents with pile order lengths based on PDA testing, the first end bent/bent no. listed for each group is the representative end bent/bent with the PDA.

PILE DESIGN INFORMATION

(Blank entries indicate item is not applicable to structure)

End Bent/ Bent No, Pile(s) #-# (e.g., "Bent 1, Piles 1-5")	Factored Axial Load per Pile TONS	Factored Downdrag Load per Pile TONS	Factored Dead Load* per Pile TONS	Dynamic Resistance Factor	Nominal Downdrag Resistance per Pile TONS	Nominal Scour Resistance per Pile TONS	Scour Resistance Factor (Default = 1.00)
End Bent 1, Piles 1-7	71			0.60			1.00
End Bent 2, Piles 1-7	71			0.60			1.00

*Factored Dead Load is factored weight of pile above the ground line.


PROJECT NO. 50347.1.1

ROBESON COUNTY

STATION: 14+59.50 -L-

NOTES:

- The Pile Foundation Tables are based on the bridge substructure design and foundation recommendations sealed by a North Carolina Professional Engineer (Robert E. Kral, P.E. No. 042642) on 02-28-2023.
- Total Pile Driving Equipment Setup quantity (not shown in Pile Foundation Tables) equals the number of driven piles, i.e., the number of piles with a Required Driving Resistance.
- The Engineer will determine the need for PDA Testing when PDAs may be required.
- For Piles, See Piles Provision and Section 450 of the Standard Specifications.

	STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH						<p align="center">PILE FOUNDATION TABLES</p>
	SIGNATURE _____ DATE _____						
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED							TOTAL SHEETS
		REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:		
1			3				
2			4				