

2026CPT.06.05.10781.1, 51767

TIP NO SS-6206BC

13.900 MILES

FED AID NO STATE FUNDED

MILLING, PAVING, MILLED SINUSOIDAL RUMBLE STRIPES & PM

NC 211 FROM SR 1770 TO 0.77 MILES NW OF SR 1505


				JOHNSON BROTHERS UTILITY & PAVING COMPANY INC LILLINGTON, NC			BARNHILL CONTRACTING CO ROCKY MOUNT, NC		FSC II LLC DBA FRED SMITH COMPANY RALEIGH, NC	
ROADWAY ITEMS										
0001	0000100000-N	800	MOBILIZATION	Lump Sum		75,405.00		77,000.00		76,000.00
0002	1220000000-E	545	INCIDENTAL STONE BASE	105 TON	45.00	4,725.00	60.00	6,300.00	86.00	9,030.00
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	13.24 SMI	2,640.00	34,953.60	2,000.00	26,480.00	1,625.00	21,515.00
0004	1260000000-E	SP	AGGREGATE SHOULDER BORROW	2,141 TON	35.01	74,956.41	34.00	72,794.00	40.00	85,640.00
0005	1297000000-E	607	MILL ASP PVMT ***** DTH 0.75" MILLING	106,762 SY	1.60	170,819.20	1.50	160,143.00	1.00	106,762.00
0006	1297000000-E	607	MILL ASP PVMT ***** DTH 1-1/2" MILLING	5,749 SY	2.50	14,372.50	2.70	15,522.30	2.00	11,498.00
0007	1330000000-E	607	INCIDENTAL MILLING	6,110 SY	5.70	34,827.00	8.00	48,880.00	7.10	43,381.00
0008	1523000000-E	610	ASP CONC SURF CRS S9.5C	9,852 TON	55.69	548,657.88	61.00	600,972.00	68.00	669,936.00
0009	1575000000-E	620	ASP FOR PLANT MIX	592 TON	565.00	334,480.00	581.00	343,952.00	535.00	316,720.00
0010	1704000000-E	SP	PATCHING EXIST PAVEMENT	5 TON	295.00	1,475.00	300.00	1,500.00	1,760.00	8,800.00
0011	1881000000-E	SP	GENERIC PAVING ITEM (LF) GENERIC PAVING ITEM - SINUSOIDAL RUMBLE STRIPES	106,725 LF	0.36	38,421.00	0.32	34,152.00	0.28	29,883.00
0012	2830000000-N	858	ADJ MANHOLES	4 EA	975.00	3,900.00	1,000.00	4,000.00	975.00	3,900.00
0013	2845000000-N	858	ADJ METER OR VALVE BOXES	4 EA	975.00	3,900.00	1,000.00	4,000.00	975.00	3,900.00
0014	4413000000-E	SP	WORK ZONE ADV/GEN WARN SIGN	778 SF	7.00	5,446.00	7.10	5,523.80	8.55	6,651.90
0015	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum		39,930.00		22,500.00		37,000.00
0016	4688000000-E	1205	THERMO PVT MKG LINES,6"90 MILS	128,067 LF	0.73	93,488.91	0.73	93,488.91	0.76	97,330.92
0017	4700000000-E	1205	12"WIDE THERMO 90 MILS	156 LF	10.00	1,560.00	10.00	1,560.00	3.05	475.80
0018	4709000000-E	1205	24"WIDE THERMO 90 MILS	148 LF	15.00	2,220.00	15.00	2,220.00	12.10	1,790.80
0019	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	4 EA	150.00	600.00	150.00	600.00	185.00	740.00
0020	4810000000-E	1205	PAINT PVMT MARKINGS 4"	128,067 LF	0.15	19,210.05	0.15	19,210.05	0.13	16,648.71
0021	4825000000-E	1205	PAINT PVMT MARKINGS 12"	156 LF	2.50	390.00	2.50	390.00	0.32	49.92
0022	4835000000-E	1205	PAINT PVT MKG LINES 24"	148 LF	5.00	740.00	5.00	740.00	5.45	806.60
0023	4845000000-N	1205	PAINT PVT MKG SYMBOL	4 EA	60.00	240.00	60.00	240.00	94.00	376.00
0024	4900000000-N	1251	PERM RAISED PVMT MARKERS	544 EA	6.25	3,400.00	6.25	3,400.00	6.35	3,454.40
CONTRACT TOTAL					TOTAL	1,508,117.55	TOTAL	1,545,568.06	TOTAL	1,552,290.05
ROADWAY ITEMS					SUB-TOTAL	1,508,117.55	SUB-TOTAL	1,545,568.06	SUB-TOTAL	1,552,290.05

BIDDERS IN ORDER

JOHNSON BROTHERS UTILITY & PAVING COMPANY INC
 BARNHILL CONTRACTING CO
 FSC II LLC DBA FRED SMITH COMPANY

1 1,508,117.55
 2 1,545,568.06
 3 1,552,290.05

CONTRACT TOTAL

DocuSigned by:

 B42B449E08FF469...