



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

December 15, 2021

BID OPENING: JANUARY 6, 2022, AT 2:00 P.M.
CONTRACT ID: DG00546
WBS ELEMENT NO.: 17BP.7. R.126
COUNTY: ROCKINGHAM
LOCATION: SR 1902 (DIBRELL ROAD)
DESCRIPTION: REPLACE BRIDGE #106 OVER WOLF ISLAND CREEK
TYPE OF WORK: GRADING, PAVING, DRAINAGE & STRUCTURE
SUBJECT: INVITATION TO BID

This is to request quotations for replacing Bridge #106 over Wolf Island Creek on SR 1902 (Dibrell Road) in Rockingham County. The Contractor is to supply materials, equipment, and labor.

The bid opening will be January 6, 2022, at 2:00 p.m. The availability date is February 7, 2022, or no later than May 6, 2022. The completion date is 360 consecutive calendar days from the start of construction, but no later than May 1, 2023.


Questions shall be emailed to Jennifer Sour at jsour@ncdot.gov prior to the bid opening. Contact with any other NCDOT personnel concerning this project is strictly prohibited and will result in bids being considered non-responsive

The public letting will be held via conference call. You may join the conference call just prior to 2pm on 1/06/2022. Please dial 919-250-7881, announce name and company name when prompted.

Bid packages are now available on the NCDOT website at the following location: https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7. Please download and print your bid package from the website.

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:

B213233052CA46B...
Jennifer. A. Sour
DIVISION PROPOSAL ENGINEER

JAS/bcj

cc: file

cc: W. R Archer, III, PE P. P. Eason, PE P. D. Wilson, PE C. B. Smitherman, PE
T Powers, PE J. R. Julian N. Abrams Prospective Bidders Plan
Rooms

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS DIVISION 7
PO BOX 14996
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075
Fax: (336) 334-3637
Customer Service: 1-877-368-4968

Location:
1584 YANCEYVILLE STREET
GREENSBORO, NC 27405

Website: www.ncdot.gov

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** STA. 15+77.00 -L-	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	625 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	5 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	20 SY		
0008	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	20 LF		
0009	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	24 LF		
0010	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK 15", 0.064"	2 EA		
0011	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0012	1330000000-E	607	INCIDENTAL MILLING	225 SY		
0013	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	205 TON		
0014	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	280 TON		
0015	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	650 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	65 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	15 TON		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
0021	3030000000-E	862	STEEL BEAM GUARDRAIL	775 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0023	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0024	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4 EA		
0025	3635000000-E	876	RIP RAP, CLASS II	445 TON		
0026	3649000000-E	876	RIP RAP, CLASS B	43 TON		
0027	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,940 SY		
0028	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	360 SF		
0029	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0030	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0031	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,400 LF		
0032	6000000000-E	1605	TEMPORARY SILT FENCE	1,835 LF		
0033	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	65 TON		
0034	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	35 TON		
0035	6012000000-E	1610	SEDIMENT CONTROL STONE	450 TON		
0036	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0037	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		

County : Rockingham

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00546

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0039	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0040	6029000000-E	SP	SAFETY FENCE	200 LF		
0041	6030000000-E	1630	SILT EXCAVATION	70 CY		
0042	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,285 SY		
0043	6037000000-E	SP	COIR FIBER MAT	520 SY		
0044	6042000000-E	1632	1/4" HARDWARE CLOTH	490 LF		
0045	6070000000-N	1639	SPECIAL STILLING BASINS	18 EA		
0046	6071012000-E	SP	COIR FIBER WATTLE	30 LF		
0047	6071020000-E	SP	POLYACRYLAMIDE (PAM)	5 LB		
0048	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0049	6087000000-E	1660	MOWING	0.5 ACR		
0050	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0051	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0052	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0053	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0054	6111000000-E	SP	IMPERVIOUS DIKE	360 LF		
0055	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0056	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0057	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0058	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** STA. 15+77.00 -L-	Lump Sum	L.S.	
0059	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** STA. 15+77.00 -L-	Lump Sum	L.S.	
0060	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0061	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	289 LF		
0062	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	70 LF		
0063	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	124.8 LF		
0064	8112730000-N	450	PDA TESTING	1 EA		
0065	8113000000-N	411	SID INSPECTIONS	3 EA		
0066	8115000000-N	411	CSL TESTING	3 EA		
0067	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** STA. 15+77.00 -L-	Lump Sum	L.S.	
0068	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	91.4 CY		
0069	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** STA. 15+77.00 -L-	Lump Sum	L.S.	
0070	8217000000-E	425	REINFORCING STEEL (BRIDGE)	42,236 LB		
0071	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	7,719 LB		
0072	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES HP 12X53	10 EA		
0073	8364000000-E	450	HP12X53 STEEL PILES	301 LF		
0074	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	481 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	253 TON		
0076	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	282 SY		
0077	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0078	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	2,400 LF		

1037/Dec13/Q69419.95/D392708002000/E78

Total Amount Of Bid For Entire Project :