



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

December 15, 2021

BID OPENING: JANUARY 6, 2022, AT 2:00 P.M.  
CONTRACT ID: DG00555  
WBS ELEMENT NO.: 17BP.7. C.11  
COUNTY: GUILFORD  
LOCATION: SR 3426 (SHERATON PARK ROAD)  
DESCRIPTION: REPLACE PIPE #40 2221 ON SR 3426 (SHERATON PARK ROAD) 0.6 MI E.  
JCT. SR 1007 (RANDLEMAN ROAD)  
TYPE OF WORK: GRADING, PAVING, SHOULDER CONSTRUCTION, GUARDRAIL &  
CULVERT  
SUBJECT: INVITATION TO BID

This is to request quotations for replacing pipe #40 2221 on SR 3426 (Sheraton Park Road). The Contractor is to supply materials, equipment, and labor.

The bid opening will be January 6, 2022, at 2:00 p.m. The availability date is February 7, 2022, or no later than May 6, 2022. The completion date is 270 consecutive calendar days from the start of construction.

**Questions shall be emailed to Jennifer Sour at [jsour@ncdot.gov](mailto:jsour@ncdot.gov) prior to the bid opening. Contact with any other NCDOT personnel concerning this project is strictly prohibited and will result in bids being considered non-responsive**

**The public letting will be held via conference call.** You may join the conference call just prior to 2pm on 1/06/2022. Please dial 919-250-7881, announce name and company name when prompted.

**Bid packages are now available on the NCDOT website at the following location: [https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let\\_type=7](https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7). Please download and print your bid package from the website.**

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:

*Jennifer A. Sour*

B213233052CA46B...

Jennifer A. Sour

DIVISION PROPOSAL ENGINEER

JAS/bcj

cc: file

ec: W. R Archer, III, PE    P. P. Eason, PE    P. D. Wilson, PE    C. B. Smitherman, PE  
T Powers, PE    C. D. Edwards, PE    B. Cvijetic, PE    Prospective Bidders  
Plan Rooms

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS DIVISION 7  
PO BOX 14996  
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075  
Fax: (336) 334-3637  
Customer Service: 1-877-368-4968

Location:  
1584 YANCEYVILLE STREET  
GREENSBORO, NC 27405

Website: [www.ncdot.gov](http://www.ncdot.gov)

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	90 TON		
0004	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	760 SY		
0005	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0006	1330000000-E	607	INCIDENTAL MILLING	118 SY		
0007	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	200 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	40 TON		
0009	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	12 TON		
0010	3030000000-E	862	STEEL BEAM GUARDRAIL	25 LF		
0011	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4 EA		
0012	3635000000-E	876	RIP RAP, CLASS II	115 TON		
0013	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	375 SY		
0014	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	460 SF		
0015	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0016	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0017	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	360 LF		
0018	6000000000-E	1605	TEMPORARY SILT FENCE	1,225 LF		
0019	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	55 TON		

County : Guilford

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00555

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	90 TON		
0021	6012000000-E	1610	SEDIMENT CONTROL STONE	160 TON		
0022	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0023	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0024	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0025	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0026	6029000000-E	SP	SAFETY FENCE	200 LF		
0027	6030000000-E	1630	SILT EXCAVATION	10 CY		
0028	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,200 SY		
0029	6037000000-E	SP	COIR FIBER MAT	100 SY		
0030	6042000000-E	1632	1/4" HARDWARE CLOTH	130 LF		
0031	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0032	6071020000-E	SP	POLYACRYLAMIDE (PAM)	5 LB		
0033	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0034	6087000000-E	1660	MOWING	0.5 ACR		
0035	6090000000-E	1661	SEED FOR REPAIR SEEDING	5 LB		
0036	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0037	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0038	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0039	6111000000-E	SP	IMPERVIOUS DIKE	70 LF		

County : Guilford

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00555

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0040	6114500000-N	1667	SPECIALIZED HAND MOWING	10		
				MHR		
0041	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	3		
				EA		
0042	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2		
				EA		

### STRUCTURE ITEMS

0043	8804000000-N	SP	GENERIC CULVERT ITEM 63' OF 15'-4" SPAN X 10'-0" RI SE COR. ALUM. STR. PLT. PIPE & ALUM ST R PLT HDW	Lump Sum	L.S.	
------	--------------	----	--	----------	------	--

1431/Dec15/Q6408.25/D199604120000/E43

Total Amount Of Bid For Entire Project :