



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

January 12, 2023

ADDENDUM #1

MEMO TO: Plan Holders

FROM: Jennifer A. Sour
Division Proposal Engineer

DocuSigned by:
Jennifer A. Sour
B213233052CA46B...

CONTRACT ID: DG00604
WBS ELEMENT NO.: 17BP.C.20
COUNTY: GUILFORD
LOCATION: REPLACE PIPE #40 2184 ON SR 2295 (RAMBLING ROAD)
TYPE OF WORK: GRADING, DRAINAGE, PAVING AND CULVERT

To whom it may concern:

I have been advised of that there are some issues in this contract. Please see below for the items in question and the action taken to correct the issue.:

- Foundation Conditioning Material, Box Culvert 1900 tons is incorrect. The correct quantity is 90 tons.
- Concrete Washout Structure 2 each is not needed. This item has been removed.
- ABC Stone is not required on this project for backfill over the culvert. This will be done with asphalt due to the small area of the roadway that is disturbed and the difficulty in compacting the ABC.
- The contractor is not required to place stream bed material in the proposed culvert. The culvert needs to be buried at least one foot. This will allow siltation to occur naturally.

A correction has been made to the ebx file replace the file with DG00604.001x. Please remove the original T-3 sheet and replace the sheet with attached.

If you have any questions, please feel free to contact me at (336) 487-0075. Thank you.

JAS

cc: Website

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS DIVISION 7
PO BOX 14996
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075
Fax: (336) 334-3637
Customer Service: 1-877-368-4968

Location:
1584 YANCEYVILLE STREET
GREENSBORO, NC 27405

Website: ncdot.gov

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0036	6111000000-E	SP	IMPERVIOUS DIKE	41 LF		
0037	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0038	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0040	6123000000-E	1670	REFORESTATION	0.1 ACR		

CULVERT ITEMS

0041	8126000000-N	414	CULVERT EXCAVATION, STA ***** (12+94 -L-)	Lump Sum	L.S.	
0042	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	90 TON		
0043	8140000000-E	416	CHANNEL EXCAVATION	10 CY		
0044	8804000000-N	SP	GENERIC CULVERT ITEM 27'-3" X 6'-4" ABC WITH ALUMINUM HW/EW AND SILLS	Lump Sum	L.S.	