



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

January 12, 2021

BID OPENING: FEBRUARY 3, 2022, AT 2:00 P.M.
CONTRACT ID: DG00561
WBS ELEMENT NO.: 17BP.7. R.123
COUNTY: ROCKINGHAM
LOCATION: SR 1929 (ESTES ROAD)
DESCRIPTION: REPLACE BRIDGE #80 ON SR 1929 (ESTES ROAD) OVER WOLF ISLAND CREEK
TYPE OF WORK: GRADING, PAVING, DRAINAGE & STRUCTURE
SUBJECT: INVITATION TO BID

This is to request quotations for replacing bridge #80 on SR 1929 (Estes Road). The Contractor is to supply materials, equipment, and labor.

The bid opening will be February 3, 2022, at 2:00 p.m. The availability date is March 17 17, 2022, or no later than May 17, 2022. The completion date is 360 consecutive calendar days from the start of construction.

Questions shall be emailed to Jennifer Sour at jsour@ncdot.gov prior to the bid opening. Contact with any other NCDOT personnel concerning this project is strictly prohibited and will result in bids being considered non-responsive

The public letting will be held via conference call. You may join the conference call just prior to 2pm on 2/3/2022. Please dial 919-250-7881, announce name and company name when prompted.

Bid packages are now available on the NCDOT website at the following location: https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7. Please download and print your bid package from the website.

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:

Jennifer A. Sour

B213233052CA46B...

Jennifer A. Sour

DIVISION PROPOSAL ENGINEER

JAS/bcj

cc: file

W. R. Archer, III, PE	P. P. Eason, PE	P. D. Wilson, PE	C. B. Smitherman, PE
T Powers, PE	J. R. Julian	Plan Rooms	Prospective Bidders

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS DIVISION 7
PO BOX 14996
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075
Fax: (336) 334-3637
Customer Service: 1-877-368-4968

Location:
1584 YANCEYVILLE STREET
GREENSBORO, NC 27405

Website: www.ncdot.gov

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** 21+49	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA-TION	500 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRUCTURES	5 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	15 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	16 LF		
0012	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	28 LF		
0013	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0014	1099700000-E	505	CLASS IV SUBGRADE STABILIZA-TION	200 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	5 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	120 SY		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	235 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	304 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	35		TON
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	5		TON
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2		EA
0022	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2		EA
0023	2556000000-E	846	SHOULDER BERM GUTTER	30		LF
0024	3030000000-E	862	STEEL BEAM GUARDRAIL	50		LF
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0026	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4		EA
0027	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4		EA
0028	3649000000-E	876	RIP RAP, CLASS B	1		TON
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,055		SY
0030	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	369		SF
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144		SF
0032	4445000000-E	1145	BARRICADES (TYPE III)	112		LF
0033	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,100		LF
0034	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	7		EA
0035	6000000000-E	1605	TEMPORARY SILT FENCE	890		LF
0036	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	125		TON
0037	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5		TON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6012000000-E	1610	SEDIMENT CONTROL STONE	330		TON
0039	6015000000-E	1615	TEMPORARY MULCHING	1		ACR
0040	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100		LB
0041	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5		TON
0042	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200		LF
0043	6029000000-E	SP	SAFETY FENCE	200		LF
0044	6030000000-E	1630	SILT EXCAVATION	20		CY
0045	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,100		SY
0046	6037000000-E	SP	COIR FIBER MAT	205		SY
0047	6042000000-E	1632	1/4" HARDWARE CLOTH	500		LF
0048	6070000000-N	1639	SPECIAL STILLING BASINS	12		EA
0049	6084000000-E	1660	SEEDING & MULCHING	1		ACR
0050	6087000000-E	1660	MOWING	0.3		ACR
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50		LB
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25		TON
0053	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50		LB
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	1		TON
0055	6114500000-N	1667	SPECIALIZED HAND MOWING	10		MHR
0056	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13		EA
0057	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2		EA

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0058	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** 22+31	Lump Sum	L.S.	
0059	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	32 LF		
0060	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	117 LF		
0061	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	38 LF		
0062	8112730000-N	450	PDA TESTING	1 EA		
0063	8113000000-N	411	SID INSPECTIONS	1 EA		
0064	8114000000-N	411	SPT TESTING	3 EA		
0065	8115000000-N	411	CSL TESTING	1 EA		
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** 22+31	Lump Sum	L.S.	
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	78 CY		
0068	8217000000-E	425	REINFORCING STEEL (BRIDGE)	24,473 LB		
0069	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,358 LB		
0070	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES HP12X53	14 EA		
0071	8364000000-E	450	HP12X53 STEEL PILES	245 LF		
0072	8391000000-N	450	STEEL PILE POINTS	14 EA		
0073	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	321 LF		
0074	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	463 TON		
0075	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	514 SY		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	990 LF		
0078	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		
0079	8860000000-N	SP	GENERIC STRUCTURE ITEM ASBESTOS ASSESSMENT	Lump Sum	L.S.	

1204/Jan12/Q41211.05/D385688370000/E79

Total Amount Of Bid For Entire Project :