



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

DANIEL H. JOHNSON
SECRETARY

January 14, 2026

NOTICE TO PROSPECTIVE BIDDERS

Subject: Invitation to Bid

Division Seven

CONTRACT ID: DG00679
WBS ELEMENT NO.: BP7.C002.3
COUNTY: GUILFORD COUNTY
ROUTE: SR 3098 (ABERNATHY RD)
LOCATION: OVER UT TO BIG ALAMANCE CREEK
TYPE OF WORK: PAVING, GRADING, GUARDRAIL, DRAINAGE, PAVEMENT
MARKINGS & CULVERT
BID OPENING: FEBRUARY 5, 2026, AT 2:00 PM

The date of availability for this project is March 4, 2026.

The completion date for this project is January 4, 2027.

There is NO MBE/WBE Goal for this project.

The North Carolina Department of Transportation is requesting bids for **paving, grading, guardrail, drainage, pavement markings and culvert installation on SR 3098 (Abernathy Rd) over UT o Big Alamance Creek in Guilford County, NC.** All quantities are estimates. The Contractor shall furnish labor, equipment and materials.

Contractor's bidding on NCDOT contracts must sign up for the Interested Parties List for each project they intend to submit a bid. As part of this requirement, Contractors must sign up for the Interested Parties List no later than one business day prior to the Letting Date.

The North Carolina Department of Transportation, in accordance with the provisions of Title VI of the Civil Rights of 1964 (78 Stat. 252) and the Regulations of the Department of Transportation (49 C.F.R., Part 21), issued pursuant to such act, hereby notifies all bidders that it will affirmatively ensure that the contract entered into pursuant to this notice will be awarded to the lowest responsible bidder without discrimination on the grounds of sex, race, color, or national origin.

BID OPENING

Electronic bids must be received in Bid Express, by 2:00 on February 5, 2026. Bids will be opened and publicly read at NCDOT Division 7 Office, 1584 Yanceyville Street, Greensboro, NC at the above date, shortly after the time that the bids submissions are due. The As-Read Bids Summaries will be posted within 48 hours of the bid opening. Results **will not** be provided by any other means than posting to the website.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS DIVISION 7
PO BOX 14996
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075
Fax: (336) 334-3637
Customer Service: 1-877-368-4968

Location:
1584 YANCEYVILLE STREET
GREENSBORO, NC 27405

Website: www.ncdot.gov

The public letting will be held via conference call. You may join the conference call just prior to 2:00 pm on 2/5/2026. Please dial (919) 250-7881, announce name and company name when prompted.

ELECTRONIC BIDDING

Electronic bidding is required through Bid Express®. Their website is bidx.com

For electronic bidding, the following files will be located on bidx.com, exclusively. These files will **not** be included on the Bidding & Letting site on Connect.NCDOT.gov:

- EBSX files
- DBE_NC.BIN files
- EBSX addenda files

Do **NOT** submit bids for the project let by Division 7 to the NCDOT **Statewide** Project Letting Office.

Bidx related questions should be directed to **Jaci Kincaid** at **(919) 707-6920**.

Note: It takes a few minutes for Division staff to download the electronic bids before those can be read. The download does not start until 2:00 PM on the day of the letting.

BID DOCUMENTS

The contract proposal, plans and supplemental project information are available online at:

<https://connect.ncdot.gov/letting/Pages/Division.aspx>.

The printing of all bid-related documents, including the proposal, plans and any supplemental project information shall be the responsibility of the bidder. Division 7 no longer provides hard copies of bid documents.

PREQUALIFYING TO BID

All prospective bidders shall be prequalified with the Department of Transportation prior to submitting a bid. Contractors who are not prequalified may obtain information and forms for prequalifying from the Contractual Services Unit, Division of Highways, Department of Transportation, 1509 Mail Service Center, Raleigh, NC. All required prequalification statements and documents shall be filed with the Contractual Services Unit at least four weeks prior to the date of opening bids.

Applications and details on becoming a prequalified Bidder or PO Prime contractor can also be found at <https://connect.ncdot.gov/business/prequal/pages/default.aspx>.

DIVISION CONTACT

Questions shall be emailed to Jennifer Sour at jsour@ncdot.gov 7 calendar days prior to the bid opening. Contact with any other NCDOT personnel concerning this project is strictly prohibited and will result in bids being considered non-responsive.

Regards,

DocuSigned by:

Jennifer A. Sour

B213233052CA46B...

Jennifer A. Sour

DIVISION CONTRACT ENGINEER

JAS

cc: file

ec: W. R. Archer, III, PE	M. P. Whitley, PE	B. Cvijetic, PE	B.K. Ketner, PE
S. Robinson, PE	S.D. Dixon	J. Crews	N. Abrams
Plan Rooms	Prospective Bidders		

Jan 13, 2026 3:28 PM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00679

Page 1 of 5

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0005	0199000000-E	SP	TEMPORARY SHORING	1,100 SF		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0007	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	40 SY		
0008	0343000000-E	310	15" SIDE DRAIN PIPE	68 LF		
0009	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (72",0.139")	40 LF		
0010	0962000000-E	SP	*** X *** CAA STRUCTURAL PLATE PIPE ARCH, ***** THICK (12'-11" x 7'-6" CAA STRUCTURAL PLATE PIPE ARCH, 0.125" THICK)	66 LF		
0011	0995000000-E	340	PIPE REMOVAL	20 LF		
0012	1121000000-E	520	AGGREGATE BASE COURSE	98 TON		
0013	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0014	1330000000-E	607	INCIDENTAL MILLING	180 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	440 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	130 TON		
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	30 TON		

Jan 13, 2026 3:28 PM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00679

Page 2 of 5

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	2 TON		
0019	2000000000-N	806	RIGHT-OF-WAY MARKERS	3 EA		
0020	3030000000-E	862	STEEL BEAM GUARDRAIL	187.5 LF		
0021	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0022	3288000000-N	862	GUARDRAIL END UNITS, TYPE TL-2	6 EA		
0023	3360000000-E	863	REMOVE EXISTING GUARDRAIL	340 LF		
0024	3380000000-E	862	TEMPORARY STEEL BEAM GUARDRAIL	187.5 LF		
0025	3389150000-N	862	TEMPORARY GUARDRAIL END UNITS, TYPE ***** (TYPE TL-2)	4 EA		
0026	3389160000-N	862	TEMPORARY ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3628000000-E	876	RIP RAP, CLASS I	80 TON		
0028	3649000000-E	876	RIP RAP, CLASS B	21 TON		
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	339 SY		
0030	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	48 SF		
0031	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	108 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	108 SF		
0033	4424500000-N	SP	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	6 EA		
0034	4435000000-N	1135	CONES	6 EA		

Jan 13, 2026 3:28 PM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00679

Page 3 of 5

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0036	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0037	4470000000-N	1160	REMOVE & RESET TEMPORARY CRASH CUSHION	4 EA		
0038	4485000000-E	1170	PORTABLE CONCRETE BARRIER	255 LF		
0039	4500000000-E	1170	REMOVE AND RESET PORTABLE CONCRETE BARRIER	296 LF		
0040	4516000000-N	1180	SKINNY DRUM	100 EA		
0041	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,060 LF		
0042	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,030 LF		
0043	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	20 LF		
0044	6000000000-E	1605	TEMPORARY SILT FENCE	1,505 LF		
0045	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	65 TON		
0046	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	260 TON		
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	125 TON		
0048	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0049	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0050	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6029000000-E	SP	SAFETY FENCE	320 LF		
0053	6030000000-E	1630	SILT EXCAVATION	370 CY		
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,000 SY		
0055	6037000000-E	1629	COIR FIBER MAT	100 SY		
0056	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	15 SY		
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	285 LF		
0058	6045000000-E	SP	*** TEMPORARY PIPE (15")	315 LF		
0059	6070000000-N	1639	SPECIAL STILLING BASINS	3 EA		
0060	6071002000-E	1642	FLOCCULANT	65 LB		
0061	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0062	6087000000-E	1660	MOWING	3 ACR		
0063	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0065	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0066	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0067	6111000000-E	SP	IMPERVIOUS DIKE	69 LF		
0068	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	13 EA		
0070	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0071	6123000000-E	1670	REFORESTATION	0.1 ACR		
0072	8140000000-E	416	CHANNEL EXCAVATION	60 CY		