



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

August 10, 2022

BID OPENING: SEPTEMBER 1, 2022, AT 2:00 P.M.  
CONTRACT ID: DG00571  
WBS ELEMENT NO.: 17BP.7.R.135  
COUNTY: GUILFORD  
LOCATION: SR 2752 (BETHEL CHURCH ROAD)  
DESCRIPTION: REPLACE BRIDGE #400205 OVER ROCK CREEK  
TYPE OF WORK: GRADING, PAVING, DRAINAGE AND STRUCTURE  
SUBJECT: INVITATION TO BID

**VOLUNTARY PRE-BID MEETING AUGUST 16, 2022, AT 3:00 P.M.**

This is to request quotations for replacing Bridge #400205 over Rock Creek on SR 2752 (Bethel Church Road) in Guilford County. The Contractor is to supply materials, equipment, and labor.

The bid opening will be September 1, 2022, at 2:00 p.m. The availability date is June 15.2023. The completion date is February 12.2024.

**Questions shall be emailed to Jennifer Sour at [jsour@ncdot.gov](mailto:jsour@ncdot.gov) prior to the bid opening. Contact with any other NCDOT personnel concerning this project is strictly prohibited and will result in bids being considered non-responsive**

**The public letting will be held via conference call.** You may join the conference call just prior to 2pm on 9/1/2022. Please dial (919) 250-7881, announce name and company name when prompted.

**Bid packages are now available on the NCDOT website at the following location: [https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let\\_type=7](https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7). Please download and print your bid package from the website.**

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:  
*Jennifer A. Sour*  
B213233052CA46B...  
Jennifer A. Sour  
DIVISION PROPOSAL ENGINEER

JAS/bcj

cc: file

ec: W. R. Archer, III, PE      P. P. Eason, PE      P. D. Wilson, PE      C. B. Smitherman, PE  
T.Powers, PE      B. Cvijetic, PE      Plan Rooms      Prospective Bidders

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS DIVISION 7  
PO BOX 14996  
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075  
Fax: (336) 334-3637  
Customer Service: 1-877-368-4968

Location:  
1584 YANCEYVILLE STREET  
GREENSBORO, NC 27405

Website: [www.ncdot.gov](http://www.ncdot.gov)

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (-L- 14+30.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	95 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	25 SY		
0008	0335200000-E	305	15" DRAINAGE PIPE	12 LF		
0009	0345000000-E	310	24" SIDE DRAIN PIPE	28 LF		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28 LF		
0011	0995000000-E	340	PIPE REMOVAL	20 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0013	1330000000-E	607	INCIDENTAL MILLING	245 SY		
0014	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	125 TON		
0015	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	215 TON		
0016	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	370 TON		
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	40 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0019	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	55 LF		
0021	3030000000-E	862	STEEL BEAM GUARDRAIL	150 LF		
0022	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	12.5 LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0024	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0025	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0026	3288000000-N	SP	GUARDRAIL END UNITS, TYPE TL-2	3 EA		
0027	3360000000-E	863	REMOVE EXISTING GUARDRAIL	387.5 LF		
0028	3635000000-E	876	RIP RAP, CLASS II	130 TON		
0029	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0030	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	412 SY		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	512 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0033	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0034	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,000 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	6000000000-E	1605	TEMPORARY SILT FENCE	540 LF		
0036	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	65 TON		
0037	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	335 TON		
0038	6012000000-E	1610	SEDIMENT CONTROL STONE	135 TON		
0039	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0040	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0041	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0042	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0043	6029000000-E	SP	SAFETY FENCE	200 LF		
0044	6030000000-E	1630	SILT EXCAVATION	270 CY		
0045	6036000000-E	1631	MATTING FOR EROSION CONTROL	810 SY		
0046	6037000000-E	SP	COIR FIBER MAT	100 SY		
0047	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	500 SY		
0048	6042000000-E	1632	1/4" HARDWARE CLOTH	260 LF		
0049	6071012000-E	SP	COIR FIBER WATTLE	80 LF		
0050	6071020000-E	SP	POLYACRYLAMIDE (PAM)	55 LB		
0051	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6087000000-E	1660	MOWING	0.5 ACR		
0053	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0054	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0055	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0056	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0057	6111000000-E	SP	IMPERVIOUS DIKE	138 LF		
0058	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0059	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0060	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0061	6123000000-E	1670	REFORESTATION	0.1 ACR		
<b>STRUCTURE ITEMS</b>						
0062	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+30.00 -L-)	Lump Sum	L.S.	
0063	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0064	8096000000-E	450	PILE EXCAVATION IN SOIL	100 LF		
0065	8097000000-E	450	PILE EXCAVATION NOT IN SOIL	40 LF		
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14+30.00 -L-)	Lump Sum	L.S.	
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	45 CY		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0068	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+30.00 -L-)	Lump Sum	L.S.	
0069	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,450 LB		
0070	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (12X53)	14 EA		
0071	8364000000-E	450	HP 12 X 53 STEEL PILES	140 LF		
0072	8391000000-N	450	STEEL PILE POINTS	14 EA		
0073	8475000000-E	460	TWO BAR METAL RAIL	124.37 LF		
0074	8522000000-E	460	GENERIC STRUCTURE ITEM 1'-2"X2'-9 3/4" CONCRETE PARAPET	140 LF		
0075	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	200 TON		
0076	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	222 SY		
0077	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0078	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		