




| PROJECT REFERENCE NO. | SHEET NO. | | | | | |
|-----------------------|-----------|--|--|--|--|--|
| 2023CPT.07.08.10171 | 1 | | | | | |
| | | | | | | |
| | | | | | | |


CASWELL COUNTY NORTH CAROLINA







| ACE 1000' PRIOR TO BEGINNING OF CONSTRUCTION LIMITS. LY USED ON -Y- LINES IF RESURFACING LIMITS EXTEND 1000' ALONG -Y- LINE. | NO REQUIRED STATI FOLLOWING -Y- |
|--|---|
| SIGN ONLY USED WHEN CONSTRUCTION LIMITS ARE 2 OR MORE MILES IN LENGTH. UND UP TO NEXT WHOLE NUMBER.(NO FRACTIONAL OR DECIMAL NUMBERS) | 1) LESS THAN 1000' OF F 2) SUBDIVISION ROADS 3) DEAD END ROADS |
| PLACE INITIALLY AT THE CONSTRUCTION LIMITS AND SPACE 1 MILE APART THEREAFTER. THEREAFTER. AT TEE INTERSECTIONS INSTALL INITIALLY $\frac{1}{2}$ MILE FROM INTERSECTION AND SPACE 1 MILE APART THEREAFTER. | WHEN PAVING/CONSTRUCTIO AN UNSIGNED -Y- LINE, F SHALL BE USED ALONG THE REMOVE UPON COMPLETION |
| THESE ARE FOR -Y- LINES THAT ARE "THROUGH" ROADWAYS. DEAD END AND SUBDIVISION ROADS ARE NOT "THROUGH" ROADWAYS. INSTALL 500' +/- FROM EACH -Y- LINE APPROACH AS SHOWN ABOVE. FOR MULTIPLE -Y- LINES THAT ARE SEPARATED BY 0.25 MILES OR LESS, TREAT AS A SINGLE UNIT AND INSTALL WITHIN 500' OF EACH APPROACH. A MAXIMUM OF 2 SIGN SETS PER MILE. DO NOT INSTALL WHEN -Y- LINES ARE WITHIN 0.5 MILES FROM "END ROAD WORK" SIGN. FOR TEE INTERSECTIONS, INSTALL WITHIN 500' +/- OF THE INTERSECTION ALONG -L- LINE. | ROAD WORK AHEAD W20-1 48'' X 48'' PLACED 500' IN ADVANCE OF FLAGGER. |
| ACE 500' FOLLOWING THE END OF CONSTRUCTION LIMITS OR AS SHOWN EN WORK ENDS AT A 3-WAY TEE INTERSECTION. | |
| ARE REQUIRED FOR A CONTRACTOR TO BEGIN A RESURFACING CONTRACT. ANY NCDOT DIVISIONS SHALL BE INSTALLED WITHIN 7 BUSINESS DAYS OF THE | |
| STRUCTION LIMITS LESS THAN 2 MILES IN LENGTH, NO STATIONARY SIGNS ARE UNDER CONSTRUCTION" OR "ROAD WORK AHEAD" SIGNS IN LIEU OF STATIONARY | |
| | |



SUMMARY OF QUANTITIES

| | | | | | | | | | | 1220000000-E | 1330000000-E | 151900000-E | 1575000000-E | 1704000000-E | 1775500000-E | 1838000000-E | 441300000-E | 4457000000-N | 468800000-F | | | 472000000-E | 489500000-N |
|---------------------|-----------|------------|--------|----------------------|--------|---|---------------------------------|--------|-------|------------------|--------------------|---|---------------------------------|-------------------------------|--|--|---|------------------------------|---------------------------|----------------------------|-------------------------|--------------------------|---|
| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | ΤΥΡ ΝΟ | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH | WIDTH | INCIDENTAL STONE | INCIDENTAL MILLING | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | ASPHALT BINDER FOR PLANT MIX | PATCHING EXISTING PAVEMENT | ASPHALT SURFACE TREATMENT, MAT COAT, #67 STONE | EMULSION FOR ASPHALT SURFACE TREATMENT | work zone Advance/general Warning signing | TEMPORARY TRAFFIC CONTROL | 6" X 90 M WHITE THERMO | 6" X 90 M YELLOW THERMO | THERMO MSG STOP 90 M | THERMO MSG AHEAD 90 M | NON-CAT IRON SNOWPLOWABLE PAVEMENT MARKERS YELLOW/YELLOW |
| | | | | | | | | МІ | FT | TONS | SY | TONS | TON | TONS | SY | GAL | SF | LS | LF | LF | EA | EA | EA |
| 2023CPT.07.08.10171 | Caswell | 1 | NC 119 | FROM US 158 TO NC 57 | 1 | NO | NO | 8.674 | 22 | 233 | 1,151 | 10,496 | 703 | 75 | 115,013 | 43,705 | 984 | 1.00 | 93,525 | 63,531 | 4 | 5 | 280 |
| TOTAL FO | OR MAP N | 0.1 | | | | | | 8.674 | | 233 | 1,151 | 10,496 | 703 | 75 | 115,013 | 43,705 | 984 | 1 | 93,525 | 63,531 | 4 | 5 | 280 |
| TOTAL FOR PROJ N | 0 202300 | DT 07 08 1 | 0171 | | | | | 8.674 | | 233 | 1,151 | 10,496 | 703 | 75 | 115,013 | 43,705 | 984 | 1 | 93,525 | 63,531 | 4 | 5 | 280 |
| | 0. 2023CF | 1.07.00.1 | .01/1 | | | | | | | | | | | | | | | | 157, | 056 | | 9 | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| GRA | ND TOTAL | | | | | | | 8.674 | | 233 | 1,151 | 10,496 | 703 | 75 | 115,013 | 43,705 | 984 | 1 | 93,525 | 63,531 | 4 | 5 | 280 |
| | | • | | | | | | | | | | | | | | | 157,056 | | | 056 | | 9 | |

| PROJECT NO. | SHEET NO. | TOTAL NO. | | | | |
|---------------------|-----------|-----------|--|--|--|--|
| 2023CPT.07.08.10171 | 6 | | | | | |
| | | | | | | |