



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

September 27, 2023

BID OPENING: OCTOBER 19, 2023, AT 2:00 P.M.
CONTRACT ID: DG00630
WBS ELEMENT NO.: 17BP.7. C.18
COUNTY: ALAMANCE
LOCATION: SR 2158 (DARRELL NEWTON ROAD)
DESCRIPTION: CULVERT IMPROVEMENTS ON SR 2158 (DARRELL NEWTON ROAD)
TYPE OF WORK: GRADING, DRAINAGE. AND CULVERT
SUBJECT: INVITATION TO BID

DATE AND TIME OF MANDATORY PRE-BID: OCTOBER 12, 2023, AT 1:00 PM

This is to request quotations for culvert improvements on SR 2158 (Darrell Newton Road) in Alamance County. The Contractor is to supply materials, equipment, and labor.

The bid opening will be October 19, 2023, at 2:00 p.m. The floating availability date is November 15, 2023, until February 15, 2024. The completion date is 360 consecutive calendar days from the start of construction.

Questions shall be emailed to Jennifer Sour at jsour@ncdot.gov 7 calendar days prior to the bid opening. Contact with any other NCDOT personnel concerning this project is strictly prohibited and will result in bids being considered non-responsive.

The public letting will be held via conference call. You may join the conference call just prior to 2pm on 10/19/2023. Please dial (919) 250-7881, announce name and company name when prompted.

Bid packages are now available on the NCDOT website at the following location: https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7. Please download and print your bid package from the website.

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:

Jennifer A. Sour

B213233052CA46B...

Jennifer A. Sour

DIVISION PROPOSAL ENGINEER

JAS/bcj

cc: file

ec: W. R. Archer, III, PE
J. Yates, PE

P. P. Eason, PE
B. J. Howell

P. D. Wilson, PE
Plan Rooms

C. B. Smitherman, PE
Prospective Bidders

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS DIVISION 7
PO BOX 14996
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075
Fax: (336) 334-3637
Customer Service: 1-877-368-4968

Location:
1584 YANCEYVILLE STREET
GREENSBORO, NC 27405

Website: www.ncdot.gov

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0223000000-E	275	ROCK PLATING	550 SY		
0005	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	5 TON		
0006	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	170 SY		
0007	0448700000-E	310	42" RC PIPE CULVERTS, CLASS IV	12 LF		
0008	1077000000-E	SP	#57 STONE	20 TON		
0009	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1.5)	360 SY		
0010	1330000000-E	607	INCIDENTAL MILLING	130 SY		
0011	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	50 TON		
0012	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	60 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	80 TON		
0014	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	10 TON		
0015	2253000000-E	840	PIPE COLLARS	0.89 CY		
0016	3030000000-E	862	STEEL BEAM GUARDRAIL	175 LF		
0017	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0019	3288000000-N	SP	GUARDRAIL END UNITS, TYPE TL-2	1 EA		
0020	3345000000-E	864	REMOVE & RESET EXISTING GUARDRAIL	100 LF		
0021	3628000000-E	876	RIP RAP, CLASS I	170 TON		
0022	3635000000-E	876	RIP RAP, CLASS II	40 TON		
0023	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	600 SY		
0024	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	489 SF		
0025	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0026	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	89 SF		
0027	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0028	4430000000-N	1130	DRUMS	20 EA		
0029	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0030	4455000000-N	1150	FLAGGER	30 DAY		
0031	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0032	4485000000-E	1170	PORTABLE CONCRETE BARRIER	60 LF		
0033	4510000000-N	1190	LAW ENFORCEMENT	120 HR		
0034	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	431 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	431 LF		
0036	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3 EA		
0037	5325800000-E	1510	8" WATER LINE	130 LF		
0038	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	750 LB		
0039	5546000000-E	1515	8" VALVE	1 EA		
0040	5801000000-E	1530	ABANDON 8" UTILITY PIPE	130 LF		
0041	6000000000-E	1605	TEMPORARY SILT FENCE	580 LF		
0042	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	95 TON		
0043	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	30 TON		
0044	6012000000-E	1610	SEDIMENT CONTROL STONE	55 TON		
0045	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0046	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0047	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0048	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0049	6029000000-E	SP	SAFETY FENCE	600 LF		
0050	6030000000-E	1630	SILT EXCAVATION	50 CY		
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	500 SY		

Sep 27, 2023 8:17 AM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00630

Page 4 of 5

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6037000000-E	SP	COIR FIBER MAT	100 SY		
0053	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0054	6045000000-E	SP	*** TEMPORARY PIPE (48")	175 LF		
0055	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0056	6071020000-E	SP	POLYACRYLAMIDE (PAM)	5 LB		
0057	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0058	6087000000-E	1660	MOWING	0.5 ACR		
0059	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0060	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0063	6111000000-E	SP	IMPERVIOUS DIKE	31 LF		
0064	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0065	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0066	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	3 EA		
0067	6123000000-E	1670	REFORESTATION	0.1 ACR		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
0068	8140000000-E	416	CHANNEL EXCAVATION	130 CY		
0069	8804000000-N	SP	GENERIC CULVERT ITEM 94'6"-9'-7" (SPAN) X 6'6"(RISE) CASPPA, 0.175" THICK WITH HEADWALL AND ENDWALL	Lump Sum	L.S.	
0070	8818000000-E	SP	GENERIC CULVERT ITEM CULVERT BACKFILL	1,000 TON		
0817/Sep27/Q9106.49/D310515020000/E70			Total Amount Of Bid For Entire Project :			