PROJECT REFERENCE NO.	SHEET NO.
W-5601BA	2
R/W SHEET NO.	

DocuSigned by: Greg S Davis 33D47B5FD78F4A8... 10/20/2017

NORTH CAROLINA PROFESSIONAL SEAL 26930 ENGINEER GREG S. DAVIS

DIVISION DESIGN ENGINEER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

TYPICAL SECTION NO. 1

NOTE: MILL 1.5" BELOW AND REPLACE FLUSH WITH GUTTER LINE

FROM SALISBURY ST. TO SUNSET AVE. HAS GRANITE CURB. CONTRACTOR SHALL MILL 1.5" MINIMUM AND RESURFACE AS DIRECTED BY THE ENGINEER.

PAVEMENT SCHEDULE

C1	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
U	EXISTING PAVEMENT.
V1	MILLING 1.5" TO 3" IN DEPTH

REVISIONS

8/17/99

20-OCT-2017 14:23
c:\pwworking\pdd\d0394810\W-5601BA_FayettevilleSt\psh\W-5601BA_typ.dgn
gsdavis