PROJECT NO.	SHEET NO.	TOTAL NO.
50138.3.4 (W-5601C)	3	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	GRADING LS	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES TON	FOUNDATION CONDITIONING GEOTEXTILE SY	18" SIDE DRAIN PIPE LF	18" RC PIPE CULVERT, CLASS IV LF	24" RC PIPE CULVERTS, CLASS IV LF	AGGREGATE BASE COURSE TONS	INCIDENTAL STONE BASE TONS	1.5" MILLING SY	BASE COURSE, B25.0B TONS	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TONS	MASONRY DRAINAGE STRUCTURE EA
50138.3.4 (W-5601C)	Randolph	1	US 64	DIRECTIONAL CROSSOVER AND BULBOUTS AT THE INTERSECTION WITH SR 2469 (BROWNS CROSSROADS)	1-15	MD	NO	NO	1.82	24-46	1.000	55	170	36	232	232	45	50	1,005	1,640	840	1,015	173	3
TOTAL FOR MAP NO. 1									**1.82**		**1.000**	**55**	**170**	**36**	**232**	**232**	**45**	**50**	**1,005**	**1,640**	**840**	**1,015**	**173**	**3**
TOTAL FOR PROJ NO. 50138.3.4 (W-5601C)									**1.82**		**1.000**	**55**	**170**	**36**	**232**	**232**	**45**	**50**	**1,005**	**1,640**	**840**	**1,015**	**173**	**3**
GRAND TOTAL									**1.82**		**1.000**	**55**	**170**	**36**	**232**	**232**	**45**	**50**	**1,005**	**1,640**	**840**	**1,015**	**173**	**3**

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	FRAME WITH TWO GRATES, STD 840.16 EA	FRAME WITH MH COVER, STD 840.54 EA	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED) SY	5" MONOLITHIC CONCRETE ISLANDS(KEYED-IN) SY	GENERIC PAVING ITEM - EMERGENCY VEHICLE ACCESS EA	CONVERT EXISTING DROP INLET TO JUNCTION BOX EA	REMOVE EXISTING GUARDRAIL LF	EROSION CONTROL STONE, CLASS A TON	EROSION CONTROL STONE, CLASS B TON	SEDIMENT CONTROL STONE TON	TEMPORARY MULCHING ACR	MATTING (EROSION CONTROL) SY	1/4" HARDWARE CLOTH LF	WATTLE LF
50138.3.4 (W-5601C)	Randolph	1	US 64	DIRECTIONAL CROSSOVER AND BULBOUTS AT THE INTERSECTION WITH SR 2469 (BROWNS CROSSROADS)	1-15	MD	NO	NO	1.82	24-46	3	2	95	510	1	2	378	20	20	50	1.95	4,500	130	275
TOTAL FOR MAP NO. 1									**1.82**		**3**	**2**	**95**	**510**	**1**	**2**	**378**	**20**	**20**	**50**	**1.95**	**4,500**	**130**	**275**
TOTAL FOR PROJ NO. 50138.3.4 (W-5601C)									**1.82**		**3**	**2**	**95**	**510**	**1**	**2**	**378**	**20**	**20**	**50**	**1.95**	**4,500**	**130**	**275**
GRAND TOTAL									**1.82**		**3**	**2**	**95**	**510**	**1**	**2**	**378**	**20**	**20**	**50**	**1.95**	**4,500**	**130**	**275**

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	POLYACRYLAMIDE (PAM) LB	COIR FIBER BAFFLES LF	SEED & MULCHING AC	SEED FOR REPAIR SEEDING LB	FERTILIZER FOR REPAIR SEEDING TON	4399000000-N TEMPORARY TRAFFIC CONTROL LS	4685000000-E 4" X 90 M WHITE THERMO LF	4685000000-E 4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4725000000-E THERMO U-TURN ARROW 90 M EA	4725000000-E THERMO LT ARROW 90 M EA	4905000000-N SNOW PLOWABLE MARKERS C & R MARKERS EA
50138.3.4 (W-5601C)	Randolph	1	US 64	DIRECTIONAL CROSSOVER AND BULBOUTS AT THE INTERSECTION WITH SR 2469 (BROWNS CROSSROADS)	1-15	MD	NO	NO	1.82	24-46	15	30	1.95	50	0.25	1	880	2,500	300	35	2,450	3	6	120
TOTAL FOR MAP NO. 1									**1.82**		**15**	**30**	**1.95**	**50**	**0.25**	**1**	**880**	**2,500**	**300**	**35**	**2,450**	**3**	**6**	**120**
TOTAL FOR PROJ NO. 50138.3.4 (W-5601C)									**1.82**		**15**	**30**	**1.95**	**50**	**0.25**	**1**	**880**	**2,500**	**300**	**35**	**2,450**	**3**	**6**	**120**
																	3,380		**335**			**9**		
											15													
									1.82			**30**	**1.95**	**50**	**0.25**	**1**	**880**	**2,500**	**300**	**35**	**2,450**	**3**	**6**	**120**
GRAND TOTAL																	**3,380**		**335**			**9**		