8/17/99

PROJECT REFERENCE NO.	SHEET NO.
W-5601C	1-A

DocuSigned by: Greg S. Davis 33D47B5FD78F4A8... 10/29/2015

DIVISION DESIGN / CONSTRUCT ENGINEER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET
1-A	INDEX OF SHEETS
1-B	CONVENTIONAL SYMBOLS
2 THRU 2-C	TYPICAL SECTIONS
2-D	DETAIL – EMERGENCY VEHICLE ACCESS FOR CONCRETE ISLANDS
2-E	DETAIL – CONVERT DI TO JUNCTION BOX
3	SUMMARY OF QUANTITIES
3-A	SUMMARY OF EARTHWORKS, ETC.
3-B	LIST OF PIPES, ETC.
4 THRU 12-A	PLAN SHEETS
13 THRU 17	VERTICAL PROFILE SHEETS
PM-1 THRU PM-5	PAVEMENT MARKING PLANS
EC-1 THRU EC-8	EROSION CONTROL PLANS
X-A	CROSS-SECTION SUMMARY
X-1 THRU X-43	CROSS-SECTIONS -L-MED-
X-44 THRU X-45	CROSS-SECTIONS -Y1-
X-46 THRU X-47	CROSS-SECTIONS -Y2-

GENERAL NOTES

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE THE PROPER TIE-IN.

CLEARING

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

UTILITIES

ANY RELOCATION OF EXISTING UTILITIES, WILL BE ACCOMPLISHED BY OTHERS PRIOR TO THE DATE OF AVAILABILITY.

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January 17, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
200.03	Method of Clearing – Method III
225.01	Guide for Grading Subgrade – Interstate amd Freeway
225.05	Method of Obtaining Superelevation – Divided Highway
560.01	Method of Shoulder Construction – High Side of Superelevated Curve – Method I
560.02	Method of Shoulder Construction – High Side of Superelevated Curve – Method II
654.01	Pavement Repairs
840.14	Concrete Drop Inlet
840.16	Drop Inlet Frame and Grates
840.25	Anchorage for Frames – Brick, Concrete, or Precast
840.54	Manhole Frame and Cover
852.01	Concrete Islands
876.02	Guide for Rip Rap at Pipe Outlets

29-OCT-2015 14:14
c:\pwworking\ca\US64 sr2469(browns_crossroads_rd)\psh\Indexofshts_psh.dgn
ashavis
AT FOR AD-220410