| PROJECT REFERENCE NO. | SHEET NO. |
|---|---|
| W-5145 | 1-A |

DocuSigned by: Greg S. Davis 33D47B5FD78F4A8...

NORTH CAROLINA PROFESSIONAL SEAL 26930 ENGINEER GREG S. DAVIS

11/18/2015

DIVISION DESIGN / CONSTRUCT ENGINEER

INDEX OF SHEETS


| SHEET NUMBER | SHEET |
|---|---|
| 1 | TITLE SHEET |
| 1-A | INDEX OF SHEETS |
| 1-B | CONVENTIONAL SYMBOLS |
| 2 | TYPICAL SECTIONS |
| 2H-1 | STOCKPILE CONTAINMENT DETAIL |
| 3 | SUMMARY OF QUANTITIES |
| 3-A | SUMMARY OF EARTHWORKS, ETC. |
| 4 THRU 6 | PLAN SHEETS |
| 7 THRU 9 | VERTICAL PROFILE SHEETS |
| PM-1 THRU PM-3 | PAVEMENT MARKING PLANS |
| EC-1 THRU EC-6 | EROSION CONTROL PLANS |
| X-A | CROSS-SECTION SUMMARY |
| X-1 THRU X-17 | CROSS-SECTIONS -L- |
| X-18 THRU X-20 | CROSS-SECTIONS -Y1- |


## GENERAL NOTES

### GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE THE PROPER TIE-IN.

### CLEARING

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

### SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

### UTILITIES

ANY RELOCATION OF EXISTING UTILITIES,
WILL BE ACCOMPLISHED BY OTHERS PRIOR TO THE DATE OF AVAILABILITY.

### 2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January 17, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

| STD.NO. | TITLE |
|---|---|
| 200.03 | Method of Clearing – Method III |
| 225.02 | Guide for Grading Subgrade – Secondary and Local |
| 225.04 | Method of Obtaining Superelevation – Two Lane Highway |
| 300.01 | Method of Pipe Installation |
| 560.01 | Method of Shoulder Construction – High Side of Superelevated Curve – Method I |
| 654.01 | Pavement Repairs |

17-NOV-2015 16:45
z:\projects\bridge\w5010_r 1614\barnes.bridge_rd\psh\Indexofshts.psh.dgn
psh\s
A1 08-A0 270410