COMPUTED BY: DDC DATE: 7/2/2015
CHECKED BY: GSD DATE: 7-8-2015

| PROJECT NO. | SHEET NO. |
|---|---|
| W-5145 | 3-A |

D8CAD221432

# STATE OF NORTH CAROLINA
# DIVISION OF HIGHWAYS

## SUMMARY OF EARTHWORK

| Station | Station | Uncl. Excav. | Embank. +% | Borrow | Waste |
|---|---|---|---|---|---|
| -L-11+00 | -L-17+80 | 160 | 209 | 49 | |
| -L-18+40 | -L-24+40 | 105 | 447 | 342 | |
| -Y1- 14+05 | -Y1- 14+50 | 5 | 17 | 12 | |
| -Y1- 15+20 | -Y1- 15+40 | 2 | 4 | 2 | |
| SUBTOTALS: | | 272 | 677 | 405 | 0 |
| EST. 5% from Borrow Pit | | | | 20 | |
| PROJECT TOTALS: | | 272 | | 425 | |
| GRAND TOTALS: | | 272 | | 425 | |
| SAY: | | 275 | | 425 | |

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, (Shoulder Reconstruction) fine grading, clearing and grubbing,
and removal of existing pavement
will be paid for at the lump sum price for "Grading".

## SUMMARY OF EXISTING CONCRETE PAVEMENT REMOVAL

| LINE | Station | Station | LOC LT/RT/CL | SF |
|---|---|---|---|---|
| -L- | 27+29 | 27+40 | CL | 221.70 |
| | | | TOTAL: | 221.70 |
| | | | SAY: | 222 |