PROJECT NO.	SHEET NO.	TOTAL NO.
8SP.20535.1	5	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	LENGTH MI	WIDTH FT	ASPHALT SURFACE TREATMENT, SLURRY SEAL SY	ASPHALT SURFACE TREATMENT, SINGLE SEAL SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	BLOTTING SAND TON	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4810000000-E 4" YELLOW PAINT LF
8SP.20535.1	Lee	1	SR 1738 (VILLANOW DR)	FROM SR 1300 TO DEAD END	1.93	20	22,650	22,650	7,928				38,800
TOTAL FOR MAP NO. 1					**1.93**		**22,650**	**22,650**	**7,928**				**38,800**
8SP.20535.1	Lee	2	SR 1740 (HARRINGTON PL)	FROM SR 1738 T DEAD END	0.08	20	940	940	329				
TOTAL FOR MAP NO. 2					**0.08**		**940**	**940**	**329**				
8SP.20535.1	Lee	3	SR 1757 (TWIN BRIDGE CIR)	FROM SR 1738 TO DEAD END	0.07	20	822	822	288				
TOTAL FOR MAP NO. 3					**0.07**		**822**	**822**	**288**				
8SP.20535.1	Lee	4	SR 1748 (HOLLY POND RD)	FROM SR 1738 TO DEAD END	0.11	20	1,295	1,295	454				
TOTAL FOR MAP NO. 4					**0.11**		**1,295**	**1,295**	**454**				
8SP.20535.1	Lee	5	SR 1756 (PERSIMMON PATH)	FROM SR 1738 TO DEAD END	0.11	18	1,165	1,165	408				
TOTAL FOR MAP NO. 5					**0.11**		**1,165**	**1,165**	**408**				
8SP.20535.1	Lee	6	SR 1749 (SUGAR CREEK RD)	FROM SR 1738 TO DEAD END	0.12	20	1,410	1,410	494				
TOTAL FOR MAP NO. 6					**0.12**		**1,410**	**1,410**	**494**				
8SP.20535.1	Lee	7	SR 1737 (CRICKET HEARTH RD)	FROM NC 42 TO END OF MAINTENANCE	0.69	22	8,910	8,910	3,119				12,600
TOTAL FOR MAP NO. 7					**0.69**		**8,910**	**8,910**	**3,119**				**12,600**
8SP.20535.1	Lee	8	SR 1750 (SUGAR MILL RD)	FROM SR 1737 TO DEAD END	0.2	20	2,350	2,350	823				
TOTAL FOR MAP NO. 8					**0.2**		**2,350**	**2,350**	**823**				
8SP.20535.1	Lee	9	SR 1741 (FOGGY BOTTOM RD)	FROM SR 1737 TO DEAD END	0.1	22	1,295	1,295	454				
TOTAL FOR MAP NO. 9					**0.1**		**1,295**	**1,295**	**454**				
8SP.20535.1	Lee	10	SR 1727 (MILL POND RD)	FROM NC 42 T SR 1737	0.34	22	4,390	4,390	1,537				
TOTAL FOR MAP NO. 10					**0.34**		**4,390**	**4,390**	**1,537**				
8SP.20535.1	Lee	11	SR 1196 (CHESHIRE DR)	FROM SR 1197 TO SR 1298	0.55	20	6,455	6,455	2,260				11,800
TOTAL FOR MAP NO. 11					**0.55**		**6,455**	**6,455**	**2,260**				**11,800**
8SP.20535.1	Lee	12	SR 1298 (CORNSILK DR)	FROM SR 1196 TO DEAD END	0.28	20	3,290	3,290	1,152				3,900
TOTAL FOR MAP NO. 12					**0.28**		**3,290**	**3,290**	**1,152**				**3,900**
8SP.20535.1	Lee	13	SR 1751 (CATTLE DR)	FROM SR 1298 TO DEAD END	0.15	20	1,760	1,760	616				
TOTAL FOR MAP NO. 13					**0.15**		**1,760**	**1,760**	**616**				
8SP.20535.1	Lee	14	SR 1299 (HIBISCUS CT)	FROM SR 1196 TO DEAD END	0.07	20	825	825	290				
TOTAL FOR MAP NO. 14					**0.07**		**825**	**825**	**290**	*	*	*	
TOTAL FOR PROJ NO. 8SP.20535.1					**4.80**		**57,557**	**57,557**	**20,152**	**15**	**538**	**1**	**67,100**
GRAND TOTAL					**4.80**		**57,557**	**57,557**	**20,152**	**15**	**538**	**1**	**67,100**