PROJECT REFERENCE NO.	SHEET NO.
W-5601AZ	1-A

DocuSigned by: Greg S. Davis 33D47B5FD78F4A8...

NORTH CAROLINA PROFESSIONAL SEAL 26930 ENGINEER GREG S. DAVIS

2/25/2016

DIVISION DESIGN / CONSTRUCT ENGINEER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET
1-A	INDEX OF SHEETS
1-B	CONVENTIONAL SYMBOLS
2	TYPICAL SECTIONS
2-A	DETAIL – RESURFACING ADVANCE WARNING SIGNS FOR URBAN /SUBURBAN FACILITIES
3	SUMMARY OF QUANTITIES
4 THRU 11	PLAN SHEETS
PM-1 THRU PM-8	PAVEMENT MARKING PLANS
SGN-1 THRU SGN-9	SIGNING PLANS
SIG-1.0 THRU SIG-P3	SIGNAL PLANS

GENERAL NOTES

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE THE PROPER TIE-IN.

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January 17, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
225.04	Method of Obtaining Superelevation – Two Lane Pavement

25-FEB-2016 12:20
c:\pwworking\ocd\d0810\W5601AZ_Church_St\psh\Indexofshts_psh.dgn
$$USER$$ $$DATE$$ $$TIME$$