



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY  
GOVERNOR

ANTHONY J. TATA  
SECRETARY

March 6, 2015

**MEMORANDUM TO: PROSPECTIVE BIDDERS**

**PROJECT: Contract No. DH00165  
WBS Element No. 42394  
Constructing turn lanes on SR 1916 (Corinth Road) at the entrance of  
Arauco Panels, LLC Industrial Plant approximately 1 mile south of Old US  
1 in Chatham County  
Bid Opening Date: 3/24/15**

**SUBJECT: Addendum #1**

The following revisions have been made to the project plans associated with the above referenced project:

- A quantity 5,405 LF of 4" x 90 mil Thermoplastic Pavement Markings was added:
  - **Line Number 47, 468500000-E, 4" x 90 mil Thermoplastic Pavement Markings, 5,405 LF.**
  - **Summary of Quantities sheets were revised to reflect this change.**
- Pavement marking labels were inadvertently omitted from the Pavement Marking Plans:
  - **Pavement Marking sheets were revised to reflect this change.**

Please replace the Bid Form with the attached sheets. A revised set of the project plans will be available for download on the Division 8 Letting Page at: [https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let\\_type=8](https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=8)

**Bidders shall sign below acknowledging receipt of this addendum and attach to the front of the Contract Proposal.**

We apologize for any inconvenience this may have caused. If this office can provide additional information, please call me at (910) 944-2344.

Sincerely,

DocuSigned by:

A3C912A7820D436...

Jeffrey A. Stroder, PE  
Division Proposal Engineer

**Acknowledgement of receipt:** \_\_\_\_\_

**Bidder Signature/Company Name**

cc: J. R. G. Olinger, PE  
M. C. Tillman

T. L. Morgan, PE  
J. A. Stroder, PE

902 N. SANDHILLS BLVD., ABERDEEN, NORTH CAROLINA 28315  
PHONE (910)944-2344 FAX (910)944-5623

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	50 TON		
0005	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	150 SY		
0006	0343000000-E	310	15" SIDE DRAIN PIPE	88 LF		
0007	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	348 LF		
0008	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	12 LF		
0009	0995000000-E	340	PIPE REMOVAL	231 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,360 TON		
0012	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	930 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,305 TON		
0014	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	183 TON		
0015	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	40 TON		
0016	2253000000-E	840	PIPE COLLARS	1 CY		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0018	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3 EA		
0019	2619000000-E	850	4" CONCRETE PAVED DITCH	60 SY		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	80 SY		
0021	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC CHAIN LINK FENCE, 72" FABRIC	1,345 LF		
0022	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE METAL LINE POSTS FOR 72" CHAIN LINK FENCE	135 EA		
0023	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE METAL TERMINAL POSTS FOR 72" CHAIN LINK FENCE	7 EA		
0024	3554000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, DOUBLE GATE METAL GATE POSTS FOR 72" CHAIN LINK FENCE , DOUBLE GATE	4 EA		
0025	3578000000-N	SP	GENERIC FENCING ITEM GENERIC FENCING ITEM - INSTALL OWNER-SUP PLIED GATE	2 EA		
0026	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0027	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	10 SY		
0028	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0029	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	8,080 LF		
0030	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	495 LF		
0031	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	50 LF		
0032	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	70 LF		
0033	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	2 EA		
0034	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	13 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	113	EA	
0036	5325800000-E	1510	8" WATER LINE	50	LF	
0037	6000000000-E	1605	TEMPORARY SILT FENCE	975	LF	
0038	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	25	TON	
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	35	TON	
0040	6015000000-E	1615	TEMPORARY MULCHING	1.6	ACR	
0041	6042000000-E	1632	1/4" HARDWARE CLOTH	65	LF	
0042	6071010000-E	SP	WATTLE	320	LF	
0043	6071020000-E	SP	POLYACRYLAMIDE (PAM)	15	LB	
0044	6084000000-E	1660	SEEDING & MULCHING	1.6	ACR	
0045	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0046	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	
0047	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5,405	LF	

1532/Mar06/Q22222.7/D157169030000/E47

Total Amount Of Bid For Entire Project :

SIGNATURE OF AUTHORIZED AGENT \_\_\_\_\_

COMPANY \_\_\_\_\_