COMPUTED BY: DDC DATE: 1/12/2015
CHECKED BY: GSD DATE: 1/16/2015

PROJECT NO.	SHEET NO.
SS-4908AL	3-B

D8CAD221432

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF EARTHWORK

Station	Station	Uncl. Excav.	Embank. +%	Borrow	Waste
-L- 13+40	-L- 14+55	16	50	34	
-L- 15+80	-L- 16+80	88	33		55
-Y1- 11+60	-Y1- 12+75	46	71	25	
-RAB_1- 10+00	-RAB_1- 14+00	455	479	24	
SUBTOTALS:		605	633	83	55
Waste to Replace Borrow				-55	-55
	SUBTOTAL			28	
EST. 5% TO REPLACE TOPSOIL ON BORROW PITS				1	
PROJECT TOTALS:		605		29	0
SAY:		610		30	

NOTE:
Shoulder Material included in Embankment quantities listed

Approximate quantities only. Unclassified excavation, borrow
excavation, fine grading, clearing and grubbing,
and removal of existing pavement will be paid for at the lump sum price for "Grading".

SUMMARY OF EXISTING ASPHALT PAVEMENT REMOVAL

LINE	Station	Station	LOC LT/RT/CL	SF
-Y1	12+76.72	13+89.78	LT	3509.69
			TOTAL:	3509.69
			SAY:	**3510**

SUMMARY OF BREAKING EXISTING ASPHALT PAVEMENT

SUMMARY OF EXISTING CONCRETE PAVEMENT REMOVAL

LINE	Station	Station	LOC LT/RT/CL	SF
-Y1	12+05	12+74	RT	376.45
			TOTAL:	376.45
			SAY:	**380**