PROJECT REFERENCE NO.	SHEET NO.
SS–4908AL	1–A

DocuSigned by: Greg S. Davis
33D4785FD7EF4A8...
3/3/2015
DIVISION DESIGN / CONSTRUCT ENGINEER

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET
1–A	INDEX OF SHEETS
1–B	CONVENTIONAL SYMBOLS
2 THRU 2–D	TYPICAL SECTION
2–E	DETAIL – CONCRETE FLUME
2–F	DETAIL – ADVANCE WARNING SIGNS
3 THRU 3–A	SUMMARY OF QUANTITIES
3–B	SUMMARY OF EARTHWORKS, ETC.
3–C	DRAINAGE SUMMARY
4 THRU 5	PLAN SHEETS
TMP–1 THRU TMP–7	TRAFFIC MANAGEMENT PLANS
PMP–1	PAVEMENT MARKING PLAN
EC–1 THRU EC–3	EROSION CONTROL PLANS
X–A	CROSS–SECTION SUMMARY
X–1 THRU X–13	CROSS–SECTIONS

GENERAL NOTES

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE THE PROPER TIE–IN.

CLEARING

CLEARING ON THESE PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

UTILITIES

ANY RELOCATION OF EXISTING UTILITIES EXCEPT AS NOTED IN PLANS, WILL BE ACCOMPLISHED BY OTHERS PRIOR TO THE DATE OF AVAILABILITY.

PERMANENT SIGNAGE

DIVISION 8 TRAFFIC SERVICES WILL INSTALL PERMANENT SIGNAGE FOR THE ROUNDABOUT CONTRACTOR SHALL COORDINATE WITH TRAFFIC SERVICES 5 CALENDAR DAYS PRIOR TO FINAL INSTALLATION.

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January 17, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
200.03	Method of Clearing – Method III
225.02	Guide for Grading Subgrade – Secondary and Local
225.04	Method of Obtaining Superelevation – Two Lane Pavement
300.01	Method of Pipe Installation
310.10	Driveway Pipe Construction
560.01	Method of Shoulder Construction – High Side of Superelevated Curve – Method I
560.02	Method of Shoulder Construction – High Side of Superelevated Curve – Method II
654.01	Pavement Repair
700.01	Concrete Pavement Joints – Construction and Contraction Joints
840.24	Frames and Narrow Slot Sag Grates
846.01	Concrete Curb, Gutter and Curb & Gutter
848.01	Driveway Turnout – Drop Curb Type
876.02	Guide for Rip Rap at Pipe Outlets

8/17/99
03-MAR-2015 09:15
z:\rdy\randolph\us220_bus@sr_2114(Providence_Ch)_rab\psh\Indexofshts_psh.dgn
psdgvis A1 DRAFT 270410