PROJECT REFERENCE NO.	SHEET NO.
SS-4908AL	2
R/W SHEET NO.	

ROADWAY DESIGN AND HYDRAULICS ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 26930 ENGINEER GREG S. DAVIS

DocuSigned by: Greg S. Davis 3/3/2015

DIVISION DESIGN / CONSTRUCT ENGINEER

PAVEMENT SCHEDULE

C1	PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.	R2	1'-6" CONCRETE CURB AND GUTTER.
C2	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS OF 1½".	R3	5" MONOLITHIC CONCRETE ISLAND. (KEYED-IN)
D1	PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.	R4	5" MONOLITHIC CONCRETE ISLAND. (SURFACE MOUNTED)
D2	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 2½" IN DEPTH OR GREATER THAN 4" IN DEPTH.	R5	7.00" TH. CLASS 'A' CONCRETE TRUCK APRON. REINFORCED WITH 6X6 W14-W14 WELDED WIRE MESH, CONTROL JOINTS 10' o.c. EXPANSION JOINTS 90' o.c. BROOM FINISH.
E1	PROP. APPROX. 5.5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 570 LBS. PER SQ. YD.	T	EARTH MATERIAL.
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5½" IN DEPTH.	TS	TOPSOIL
R1	2"-6" CONCRETE CURB AND GUTTER.	U	EXISTING PAVEMENT.
		W	WEDGING OF EXISTING PAVEMENT (SEE WEDGING DETAIL)

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.

REVISIONS

8/17/99

03-MAR-2015 13:21
z:\rdy\randolph\us220_bus@sr_2114(Providence_Ch)_rab\psh\typ\us220_bus@sr_2114_typ.dgn
csavis AT RBCAD-270410