PROJ. REFERENCE NO.	SHEET NO.
SS-4908AL	X-A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+40.00	0	0
13+60.00	1	7
13+80.00	2	6
14+00.00	3	6
14+20.00	3	7
14+27.11	1	3
14+40.00	3	5
14+50.00	2	4
14+55.00	1	2

Station RAB_1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+00.00	9	21
13+20.00	9	19
13+40.00	8	14
13+60.00	5	13
13+80.00	1	18
14+00.00	0	24

Station -L-	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+80.00	0	0
15+90.00	32	1
16+00.00	21	1
16+20.00	23	3
16+40.00	9	7
16+60.00	3	9
16+80.00	0	7

Station -Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+60.01	0	0
11+80.01	5	13
11+96.59	7	15
12+00.01	1	3
12+20.04	5	8
12+40.17	7	7
12+49.91	5	6
12+60.30	5	4
12+69.16	5	2
12+75.00	6	2

Station RAB_1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.50	0	0
10+20.00	1	24
10+40.00	1	23
10+60.00	1	30
10+80.00	1	32
11+00.00	12	21
11+20.00	48	10
11+40.00	101	6
11+60.00	106	6
11+80.00	67	7
12+00.00	38	11
12+20.00	26	17
12+40.00	16	36
12+60.00	1	39
12+80.00	4	26

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE:

Shoulder Material included in Embankment quantities listed