



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

April 4, 2018

**NOTICE TO PROSPECTIVE BIDDERS**

Contract Number: 11789595  
TIP Number: N/A  
WBS Number: 15008.1063014  
County: Moore  
Description: Emergency pipe replacement on NC 5

**Subject: Addendum #1**

The following revisions have been made to the project proposal and plans associated with the above referenced project:

- Pre-bid meeting attendance sheet is attached. Only those contractors listed on this sheet will be allowed to bid on the project.
- Pre-bid meeting minutes are attached and shall become an addendum to the contract.

Please attach this Addendum to the front of your proposal when submitting your bid.

If this office can provide additional information, please call me at (910) 944-2344.

Sincerely,

DocuSigned by:

*Jeffrey A. Stroder*

A3C912A7820D436...

Jeffrey A. Stroder, PE  
Division Proposal Engineer

cc: C. E. Dumas, PE  
S. G. Foster, PE  
J. S. Brooks  
File

*Mailing Address:*  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS, DIVISION 8  
902 NORTH SANDHILLS BOULEVARD  
ABERDEEN, NC 28315

*Telephone:* (910) 944-2344  
*Fax:* (910) 944-5623  
*Customer Service:* 1-877-368-4968

*Website:* [www.ncdot.gov](http://www.ncdot.gov)

*Location:*  
902 NORTH SANDHILLS BOULEVARD  
ABERDEEN, NC 28315

CONTRACT 11789595

EMERGENCY PIPE REPLACEMENT ON IUCS

<u>NAME</u>	<u>COMPANY</u>	<u>Ph #</u>
HOWARD REEDY	NCDOT DIV 8	
Stephen JAMES	Chatham Civil	919-930-7307
Steve Sharpe	P+S Grading LLC	334 362 1818
Sarah G Foster	<del>910-944-2344</del> NCDOT	910-944-2344
David Jordan	NCDOT DIV 8	910-944-7554
Jim Dietrich	NCDOT	910-944-7554
JOSH BROOBS	NCDOT	(910)944-2233
Sonny Upde - 910-639-1637	NORTH STATE ENVIRONMENTAL	
Chuck Dumas	NCDOT	
EBEN MILLER	FRED SMITH Co.	919-795-6886
↳ eben.miller@Fredsmithcompany.net		

Prebid Minutes –

Contract 11789595

Emergency Pipe Replacement – Replacement of 48’ of 18” Class III Reinforced Concrete Pipe

- Pipe shall be furnished and installed in accordance with section 300 of the Roadway Standard Drawings.
- Per the prebid meeting, the pipe may be backfilled with suitable earth material or stone meeting NCDOT Standard Specifications.
- Bidders shall plan on placing silt fence at the toe of the fill on both sides of the pipe.
- Bidders shall plan on seeding and matting all exposed areas once pipe is installed. Please coordinate with Bob Ferron with Pinehurst Resorts on type of seed. If Mr. Ferron is unavailable please use seed mix in contract. No bahia is to be used.
- The contractor will be responsible for locating and working around any utilities. There is an NCDOT fiber optic line on NC 5 – Evan Mckinnon 910-947-3930 is the NCDOT contact. There is also irrigation for the golf course in the area. Coordinate location with Mr. Bob Ferron with Pinehurst Resorts – his office is located at the intersection of NC 5 and Morganton Road.
- Waste material from the project and equipment may be staged at the NCDOT property located on NC 5 near the Resident Engineer’s office at 2654 NC Hwy 5. Waste must be disposed of in accordance with State, Federal, and Local guidelines. The successful bidder must furnish a copy of the permit for the waste site.
- The successful bidder shall plan to place Class B rip rap at each end of the pipe. It is estimated that approximately 2 tons will be needed on each end.
- The contractor shall place an asphalt patch prior to opening NC 5 to traffic. Failure to patch the asphalt will result in assessment of damages in accordance with the contract.
- Per the pre-bid conference, the contractor shall patch with a minimum depth of 10” of B25.0 asphalt flush with the existing surface.
- The contractor shall place an overlay with S9.5 B on NC 5 over the patch. The short overlay shall be a minimum of 100’ in length (approx. 50’ each side of the center of the patch). The contractor shall be responsible for striping centerline within 5 days and edgelines within 30 days of obliteration of the markings. Paint or Thermoplastic markings will be acceptable and shall meet the minimum requirements of NCDOT Standard Specifications.
- The contractor will be responsible for signing the detour route for pipe replacement. The contractor will be responsible for producing a detour plan using the routes in the contract. The detour plan must be submitted to the Engineer for approval prior to implementation.
- The contractor shall not close or narrow a lane of traffic on NC 5 from 6:00 am on July 24<sup>th</sup> through 6:00 am on July 30<sup>th</sup> due to the Kids US Open.