NORTH CAROLINA PROFESSIONAL SEAL 26930 ENGINEER GREG S. DAVIS

DocuSigned by: Greg S. Davis 33D47B5FD78F4A8...

1/13/2015

DIVISION DESIGN / CONSTRUCT ENGINEER

INDEX OF SHEETS

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET
1-A	INDEX OF SHEETS
1-B	CONVENTIONAL SYMBOLS
2	TYPICAL SECTIONS
3	SUMMARY OF QUANTITIES
4 THRU 5	PLAN SHEETS
TMP-1 THRU TMP-3	TRAFFIC MANAGEMENT PLANS
SIG 1.0 THRU SIG. 1.2	SIGNAL PLANS
SIG. P1 THRU SIG. P3	PEDESTRIAN PUSHBUTTON LOCATIONS

ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in the "Roadway standard Drawings" highway Design Branch – N.C. Department of Transportation – Raleigh, N.C., dated January 17, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD. NO.	TITLE
200.02	Method of Clearing – Method II
225.02	Guide for Grading Subgrade – Secondary and Local
225.04	Method of Obtaining Superelevation – Two Lane Pavement
846.01	Concrete Curb, Gutter, and Curb & Gutter
848.01	Concrete Sidewalk
848.05	Curb Ramp – Proposed Curb and Gutter
848.06	Curb Ramp – Existing Curb and Gutter

GENERAL NOTES

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE THE PROPER TIE-IN.

CLEARING

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SIDE ROADS

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

SUBSURFACE PLANS

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

CURB RAMPS

CURB RAMPS ARE SHOWN ON THE PLANS AT APPROXIMATE LOCATIONS.
CONSTRUCT ALL CURB RAMPS IN ACCORDANCE WITH ROADWAY STD. 848.05 AND 848.06

UTILITIES

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS PRIOR TO THE DATE OF AVAILABILITY.

8/17/99
13-JAN-2015 17:00
r:\hydraulics\Ashlandrd_US311_Pedestrian Crossing\psh\Index_of_Sheets.dgn
$$$$USER$$$$ $$$$DATE$$$$