



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

April 27, 2017

NOTICE TO PROSPECTIVE BIDDERS

Contract Number: DH00241
TIP Number: N/A
WBS Number: 17BP.8.R.89, 17BP.8.R.116
County: Moore
Description: Replacement of Bridge No. 19 over Deep Creek on SR 1112 (Roseland Road) and Bridge No. 25 over Jackson Creek on SR 1122 (Jackson Springs Rd)

Subject: Addendum #1

The following revisions have been made to the project proposal associated with the above referenced project:

- Line # 0077, 3'-0" x 2'-0" Prestressed Conc Cored Slabs –
 - The quantity has changed from 1,515 LF to 910 LF.
- Line # 0080, 3'-0" x 1'-9" Prestressed Conc Cored Slabs has been added–
 - A quantity of 605 LF has been added.

Please replace the itemized proposal bid form with the attached sheets.

This addendum letter shall be attached to the front of the contract proposal. These sheets and EBS Addendum File will also be available for download on the Division 8 Letting Page at: https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=8

We apologize for any inconvenience this may have caused. If this office can provide additional information, please call me at (910) 944-2344.

Sincerely,

DocuSigned by:

Jeffrey A. Stroder

A3C912A7820D436...

Jeffrey A. Stroder, PE
Division Proposal Engineer

cc: J. R. G. Olinger, PE
M. G. Phillips
File

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS, DIVISION 8
902 NORTH SANDHILLS BOULEVARD
ABERDEEN, NC 28315

Telephone: (910) 944-2344
Fax: (910) 944-5623
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS, DIVISION 8
902 NORTH SANDHILLS BOULEVARD
ABERDEEN, NC 28315

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (BRIDGE 019, STATION 16+47.00)	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (BRIDGE 25, STATION 18+71.00)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	150 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	2 ACR		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	150 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	150 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	50 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	124 LF		
0013	0335850000-E	305	*** DRAINAGE PIPE ELBOWS 15"	1 EA		
0014	1121000000-E	520	AGGREGATE BASE COURSE	31 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	260 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,260 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	720 TON		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	580 TON		
0020	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	135 TON		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0023	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	46 LF		
0025	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0026	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TYPE 350 TL-3	8 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0028	3635000000-E	876	RIP RAP, CLASS II	1,080 TON		
0029	3649000000-E	876	RIP RAP, CLASS B	41 TON		
0030	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	294 SY		
0031	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0032	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,000 LF		
0033	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,000 LF		
0034	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,673 LF		
0035	6000000000-E	1605	TEMPORARY SILT FENCE	2,785 LF		
0036	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	140 TON		
0038	6012000000-E	1610	SEDIMENT CONTROL STONE	115 TON		
0039	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0040	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0041	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1 TON		
0042	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400 LF		
0043	6029000000-E	SP	SAFETY FENCE	400 LF		
0044	6030000000-E	1630	SILT EXCAVATION	130 CY		
0045	6036000000-E	1631	MATTING FOR EROSION CONTROL	16,410 SY		
0046	6037000000-E	SP	COIR FIBER MAT	200 SY		
0047	6042000000-E	1632	1/4" HARDWARE CLOTH	375 LF		
0048	6071010000-E	SP	WATTLE	90 LF		
0049	6071013000-E	SP	WATTLE BARRIER	520 LF		
0050	6071020000-E	SP	POLYACRYLAMIDE (PAM)	15 LB		
0051	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0052	6087000000-E	1660	MOWING	1 ACR		
0053	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0054	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0055	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0056	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6111000000-E	SP	IMPERVIOUS DIKE	140 LF		
0058	6114500000-N	1667	SPECIALIZED HAND MOWING	20 MHR		
0059	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	50 EA		
0060	6123000000-E	1670	REFORESTATION	0.2 ACR		
0061	6132000000-N	SP	GENERIC EROSION CONTROL ITEM CONCRETE WASHOUT STRUCTURE	4 EA		
0062	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (BRIDGE 019, STATION 16+47.00)	Lump Sum	L.S.	
0063	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (BRIDGE 25, STATION 18+71.00)	Lump Sum	L.S.	
0064	8112730000-N	450	PDA TESTING	2 EA		
0065	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (BRIDGE 019, STATION 16+47.00)	Lump Sum	L.S.	
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (BRIDGE 25, STATION 18+71.00)	Lump Sum	L.S.	
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	96 CY		
0068	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE 019, STATION 16+47.00)	Lump Sum	L.S.	
0069	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (BRIDGE 25, STATION 18+71.00)	Lump Sum	L.S.	
0070	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,548 LB		
0071	8364000000-E	450	HP12X53 STEEL PILES	955 LF		
0072	8391000000-N	450	STEEL PILE POINTS	14 EA		
0073	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	250 LF		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	885 TON		
0075	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	975 SY		
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	910 LF		
0078	8860000000-N	SP	GENERIC STRUCTURE ITEM ASBESTOS ASSESSMENT, BRIDGE 19 STATION 16+47.00	Lump Sum	L.S.	
0079	8860000000-N	SP	GENERIC STRUCTURE ITEM ASBESTOS ASSESSMENT, BRIDGE 25 STATION 18+71.00	Lump Sum	L.S.	
0080	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	605 LF		

1337/Apr27/Q47600.45/D383683423000/E80

Total Amount Of Bid For Entire Project :

SIGNATURE OF AUTHORIZED AGENT _____ COMPANY NAME _____