TOTAL BILL OF MATERIAL

	INCIDENTAL MILLING	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	ASPHALT BINDER FOR PLANT MIX	2'-6" CONCRETE CURB & GUTTER	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	INDUCTIVE LOOP SAWCUT	GROOVING BRIDGE FLOORS	CLASS AA CONCRETE	EPOXY COATED REINFORCING STEEL	CLASS II SURFACE PREPARATION	LATEX MODIFIED CONCRETE OVERLAY	PLACING & FINISHING OF LATEX MODIFIED CONCRETE OVERLAY	SILICONE JOINT SEALANT	ELASTOMERIC CONCRETE	BRIDGE JOINT DEMOLITION	HYDRO-DEMOLITION OF BRIDGE DECK	REMOVAL OF EXISTING ISLAND	SCARIFYING BRIDGE DECK
	SQ. YDS	TONS	TONS	LN. FT.	SQ. YDS.	LN. FT.	SQ. FT.	CU. YDS.	LBS.	SQ. YDS.	CU. YDS.	SQ. YDS.	LN. FT.	CU. FT.	SQ. FT.	SQ. YDS.	SQ. YDS.	SQ. YDS.
750017	1187	99.7	6.0	46	253	200	7221	10.2	781	12.6	55.5	943	180.0	39.1	155.6	943	345.1	943
750177	300	25.2	1.5	-	-	-	9217	-	-	88.0	70.5	1070	194.0	39.4	157.2	1070	-	1070
750196	1504	126.3	7.6	-	228	200	7549	6.3	410	42.7	55.6	944	160.7	34.3	136.3	944	287.1	944
750197	1753	185.1	11.1	77	98	280	9138	8.4	455	35.6	59.2	1138	177.0	38.3	150.5	1138	280.3	1138
TOTAL	4744	436.3	26.2	123	579	680	33125	24.9	1646	178.9	240.8	4095	711.7	151.1	599.6	4095	912.5	4095

✳ESTIMATED QUANTITY FOR BIDDING PURPOSES

PROJECT NO. 8BPR.10761
RANDOLPH COUNTY
BRIDGE NO. 750017

NORTH CAROLINA PROFESSIONAL SEAL 020208 ENGINEER ERIC B. NELSON JR.

DocuSigned by: Eric B. Nelson Jr. 5/15/2018
ACB8082119D74CD...

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

TOTAL BILL OF MATERIAL

PLANS PREPARED BY:
Gannett Fleming
Excellence Delivered As Promised
2610 Wycliff Road
Suite 102
Raleigh NC 27607-3073
(919) 420-7660
NC Lic. No. F-0270

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-1
1			3			TOTAL SHEETS
2			4			34

DRAWN BY : M. SPENCER DATE : 5/2018
CHECKED BY : R. NELSON DATE : 5/2018