| SUMMARY OF QUANTITIES FOR SPAN "B" | | |
|---|---|---|
| | ESTIMATE | ACTUAL |
| SCARIFYING BRIDGE DECK | 278 SY | |
| HYDRO-DEMOLITION OF BRIDGE DECK | 278 SY | |
| CLASS II SURFACE PREPARATION | 14.5 SY | |
| BRIDGE JOINT DEMOLITION | 52.4 SF | |
| GROOVING BRIDGE FLOORS | 2381 SF | |




PLAN OF SPAN "B"

(SEE SHEET NO. S-17 FOR SECTION A-A)

## NOTES:

PAYMENT FOR CLASS II SURFACE PREPARATION IS BASED UPON SQUARE FEET OF ADDITIONAL DEMOLITION REQUIRED FOLLOWING SCARIFICATION OF BRIDGE DECK. SEE "OVERLAY SURFACE PREPARATION" SPECIAL PROVISION.

- SCARIFYING AND HYDRO-DEMOLITION OF BRIDGE DECK
- APPROX. AREA CLASS II SURFACE PREPARATION
- BRIDGE JOINT DEMOLITION

PROJECT NO. 8BPR.10761

RANDOLPH COUNTY

BRIDGE NO. 750177

NORTH CAROLINA PROFESSIONAL SEAL 020208 ENGINEER ERIC B. NELSON JR.

DocuSigned by: 5/9/2018

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SURFACE PREPARATION
SPAN "B"

PLANS PREPARED BY:

Gannett Fleming
Excellence Delivered As Promised

2610 Wycliff Road
Suite 102
Raleigh NC 27607-3073
(919) 420-7660
NC Lic. No. F-0270

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

| REVISIONS | | | | | | |
|---|---|---|---|---|---|---|
| NO. | BY: | DATE: | NO. | BY: | DATE: | |
| 1 | | | 3 | | | |
| 2 | | | 4 | | | |

SHEET NO. S-14

TOTAL SHEETS 34

DRAWN BY : M. SPENCER DATE : 5/2018

CHECKED BY : R. NELSON DATE : 5/2018