SUMMARY OF QUANTITIES FOR SPAN ``A''		
	ESTIMATE	ACTUAL
SCARIFYING BRIDGE DECK	274 SY	
HYDRO-DEMOLITION OF BRIDGE DECK	274 SY	
CLASS II SURFACE PREPARATION	21.2 SY	
BRIDGE JOINT DEMOLITION	34.1 SF	
GROOVING BRIDGE FLOORS	2193 SF	



PLAN OF SPAN ``A''

(SEE SHEET NO. S-25 FOR SECTION A-A)

BILL OF MATERIAL FOR CONCRETE MEDIAN					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	6	#4	STR.	18'-4"	74
G1	24	#4	STR.	2'-7"	42
REINFORCING STEEL (EPOXY COATED)					116 LBS
CLASS AA CONCRETE					1.8 CY

NOTES:

PAYMENT FOR CLASS II SURFACE PREPARATION IS BASED UPON SQUARE FEET OF ADDITIONAL DEMOLITION REQUIRED FOLLOWING SCARIFICATION OF BRIDGE DECK. SEE ``OVERLAY SURFACE PREPARATION'' SPECIAL PROVISION.

GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE MEDIAN STRIP IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. THE CONTRACTION JOINTS SHALL BE LOCATED AT A SPACING OF 8 FT. TO 10 FT. BETWEEN EXPANSION JOINTS. NO CONTRACTION JOINTS WILL BE REQUIRED FOR SEGMENTS LESS THAN 10 FEET IN LENGTH.

- SCARIFYING AND HYDRO-DEMOLITION OF BRIDGE DECK
- APPROX. AREA CLASS II SURFACE PREPARATION
- BRIDGE JOINT DEMOLITION

PROJECT NO. 8BPR.10761

RANDOLPH COUNTY

BRIDGE NO. 750196

NORTH CAROLINA PROFESSIONAL SEAL 020208 ENGINEER ERIC B. NELSON, JR.

DocuSigned by: Eric B Nelson Jr. ACB80821196074CD... 5/9/2018

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SURFACE PREPARATION
SPAN ``A''

REVISIONS							SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:		S-22
1			3				TOTAL SHEETS
2			4				34

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PLANS PREPARED BY:
Gannett Fleming
Excellence Delivered As Promised
2610 Wycliff Road
Suite 102
Raleigh NC 27607-3073
(919) 420-7660
NC Lic. No. F-0270

DRAWN BY : M. SPENCER DATE : 5/2018
CHECKED BY : R. NELSON DATE : 5/2018