SUMMARY OF QUANTITIES FOR SPAN "C"		
	ESTIMATE	ACTUAL
SCARIFYING BRIDGE DECK	341 SY	
HYDRO-DEMOLITION OF BRIDGE DECK	341 SY	
CLASS II SURFACE PREPARATION	51.2 SY	
BRIDGE JOINT DEMOLITION	52.4 SF	
GROOVING BRIDGE FLOORS	2942 SF	



PLAN OF SPAN "C"

(SEE SHEET NO. S-17 FOR SECTION A-A)

NOTES:

PAYMENT FOR CLASS II SURFACE PREPARATION IS BASED UPON SQUARE FEET OF ADDITIONAL DEMOLITION REQUIRED FOLLOWING SCARIFICATION OF BRIDGE DECK. SEE "OVERLAY SURFACE PREPARATION" SPECIAL PROVISION.

- SCARIFYING AND HYDRO-DEMOLITION OF BRIDGE DECK
- APPROX. AREA CLASS II SURFACE PREPARATION
- BRIDGE JOINT DEMOLITION

PROJECT NO. 8BPR.10761

RANDOLPH COUNTY

BRIDGE NO. 750177

NORTH CAROLINA PROFESSIONAL SEAL 020208 ENGINEER ERIC B. NELSON JR.

DocuSigned by: Eric B. Nelson Jr. 5/9/2018

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SURFACE PREPARATION
SPAN "C"

PLANS PREPARED BY:

Gannett Fleming
Excellence Delivered As Promised

2610 Wycliff Road
Suite 102
Raleigh NC 27607-3073
(919) 420-7660
NC Lic. No. F-0270

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS							
NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.	S-15
1			3			TOTAL SHEETS	34
2			4				

DRAWN BY : M. SPENCER DATE : 5/2018

CHECKED BY : R. NELSON DATE : 5/2018