DocuSign Envelope ID: 92649902-AF9F-48F2-A4E5-585777C59F84

PROJECT: 17BP.8.R.113

CONTRACT:

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

LEE COUNTY

LOCATION: BRIDGE NO. 520087 ON SR 1133 (LEE AVENUE) OVER GASTERS CREEK

TYPE OF WORK: GRADING, DRAINAGE, PAVING AND STRUCTURE.

TIP NO.	SHEET NO.
17BP.8.R.113	PMP–1

APPROVED: DocuSigned by: Brandon W. Johnson 6A29A2BE0C9B45E...

DATE: 2/21/2017

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 034371 ENGINEER BRANDON W. JOHNSON

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS
1205.02	PAVEMENT MARKINGS - BRIDGES
1250.01	RAISED PAVEMENT MARKERS
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL & BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	QUANTITY
THERMO(4", 1 COAT)		
TI	YELLOW DOUBLE CENTER	950 LF
TA	WHITE EDGE LINE	950 LF
RAISED MARKERS		9 EA

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
LEE AVE	THERMO	RAISED

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

D) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.

PAVEMENT MARKING DETAIL



Prepared in the Office of:
SUMMIT DESIGN AND ENGINEERING SERVICES
NC FIRM LICENSE No: P-0339
504 Meadowlands Drive
Hillsborough, NC 27278
(919) 732-3883
(919) 732-6676 (FAX)

BRANDON W. JOHNSON, PE — *PROJECT ENGINEER*

FAITH E. JAHNKE, EI — *PROJECT DESIGNER*

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

INDEX

PMP-1 PAVEMENT MARKING PLAN TITLE, SCHEDULE, QUANTITIES AND PAVEMENT MARKING DETAIL.

02-FEB-2017 12:05
520087_TC_PMP_1.dgn
faith.jahnke