PROJECT REFERENCE NO.	SHEET NO.
U-5758	2
R/W SHEET NO.	
DIVISION DESIGN ENGINEER	HYDRAULICS ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 26930 ENGINEER GREG S. DAVIS

DocuSigned by: Greg S Davis 6/17/2017

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

WIDENING BEGINS –L– STA. 15+88

TYPICAL SECTION NO. 1

USE TYPICAL NO. 1
FROM –L– STA. 15+43.00 TO STA. 19+98.21
AND –L– STA. 20+47.17 TO STA. 26+18.00

TYPICAL SECTION NO. 2

USE TYPICAL NO. 2
FROM –Y2– STA. 15+75.00 TO STA. 17+10

PAVEMENT SCHEDULE

C1	PROP. APPROX. 1.5″ ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
C2	PROP. APPROX. 3.0″ ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, PLACED IN 2 LIFTS AT AN AVERAGE RATE OF 168 LBS PER SQ. YD.
D1	PROP. APPROX. 4″ ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
E1	PROP. APPROX. 4″ ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
R1	2′ – 6″ CURB AND GUTTER
T	EARTH MATERIAL
U	EXISTING PAVEMENT.
V1	MILLING 1.5″ IN DEPTH

REVISIONS

8/17/99

17-JUN-2017 14:17
Z:\dgn\proj\bus 2200\sr 2344(presnell.st)\pdh\typ\U-5758_typ.dgn
pgdavis
AT PRCAD-292010