PROJECT REFERENCE NO.	SHEET NO.
U-5758	SCP 2

CONSTRUCTION NOTES:

1) PRIOR TO DISCONNECTING/REMOVING THE EXISTING FIBER CABLES FROM THE INTERCONNECT CENTER, RECORD THE EXISTING SPLICE CONFIGURATION AND COMPARE TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.

2) BACK PULL AND RE-ROUTE THE TWO (2) EXISTING 12 FIBER CABLES FROM THE EXISTING CABINET TO THE EXISTING SNOW SHOE ARRANGEMENT AND INSTALL A NEW AERIAL SPLICE ENCLOSURE.

GENERAL NOTE:

1) NOTIFY THE DIVISION'S TRAFFIC SIGNAL SUPERVISOR, GARY PHILLIPS, AT (910) 947-3930 FIVE (5) DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEM COMMUNICATIONS CABLE. NOTIFY THE TRAFFIC SIGNAL SUPERVISOR AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared in the Offices of:

750 N. Greenfield Pkwy., Garner, NC 27529

COMMUNICATIONS CABLE AND CONDUIT ROUTING PLANS

DIVISION 8 RANDOLPH CO. ASHEBORO

PLAN DATE: JUNE 2017 REVIEWED BY:

PREPARED BY: I. N. AVERY REVIEWED BY:

SCALE 0 60 1" = 60'

REVISIONS	INIT.	DATE

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 032108 ENGINEER MOHD A. ASLAMI

DocuSigned by: Mohd Aslami 5D9B0BA6DBB6495... 8/14/2017

DATE

CADD Filename: