PROJECT REFERENCE NO.	SHEET NO.
U-5758	1-A

NORTH CAROLINA PROFESSIONAL SEAL 26930 ENGINEER GREG S. DAVIS

DocuSigned by: Greg S Davis 33D47B5FD78F4A8...

DIVISION DESIGN ENGINEER

6/17/2017

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET
1-A	INDEX OF SHEETS
1-B	CONVENTIONAL SYMBOLS
1-C	SURVEY CONTROL SHEET
2	TYPICAL SECTIONS
3	SUMMARY OF QUANTITIES
3-A	SUMMARY OF EARTHWORKS, ETC.
3-B	LIST OF PIPES, ETC.
4 THRU 6	PLAN SHEETS
ROW-1 THRU ROW-3	RIGHT OF WAY PLANS
TM-1 THRU TM-2	TRAFFIC MANAGEMENT PLANS
PM-1 THRU PM-2	PAVEMENT MARKING PLANS
EC-1 THRU EC-6	EROSION CONTROL PLANS
SIG-1 THRU SIG-P3	SIGNAL PLANS
SCP 1 THRU SCP 3	SIGNAL COMMUNICATION PLANS
UBO-1 THRU UBO-3	UTILITIES BY OTHERS PLANS
X-A	CROSS-SECTION SUMMARY
X-1 THRU X-13	CROSS-SECTIONS -L-

GENERAL NOTES

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE THE PROPER TIE-IN.

CLEARING

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD III.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

UTILITIES

ANY RELOCATION OF EXISTING UTILITIES, WILL BE ACCOMPLISHED BY OTHERS PRIOR TO THE DATE OF AVAILABILITY.

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January 17, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
200.03	Method of Clearing – Method III
225.02	Guide for Grading Subgrade – Seconary and Local
225.04	Method of Obtaining Superelevation – Two Lane Pavement
225.04	Method of Obtaining Superelevation – Two Lane Pavement
300.01	Method of Pipe Installation
560.01	Method of Shoulder Construction – High Side of Superelevated Curve – Method I
560.02	Method of Shoulder Construction – High Side of Superelevated Curve – Method II
654.01	Pavement Repairs
840.02	Concrete Catch Basin – 12" thru 54" Pipe
840.03	Frame, Grates and Hood
840.25	Anchorage for Frames – Brick, Concrete, or Precast
840.72	Pipe Collar
846.01	Concrete Curb, Gutter and Curb & Gutter
848.01	Concrete Sidewalk
848.03	Driveway Turnout – Drop Curb Type
848.05	Curb Ramp – Proposed Curb and Gutter
848.06	Curb Ramp – Existing Curb and Gutter

8/17/99
17-JUN-2017 14:16
z:\pwworkpl\bhbus2200\pr2344(presnell.st)\psh\indexofshts.psh.dgn
psdavis
AT PRCAD-272010