DocuSign Envelope ID: 6C28DFD1-AEB9-4F32-97AA-3411A8BFC24A

TIP PROJECT: 17BP.8.R.77

CONTRACT:

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

TIP NO.	SHEET NO.
17BP.8.R.77	PMP–1

APPROVED: DocuSigned by: Brandon W. Johnson 6A29A2BE0C9B45E...

DATE: 9/18/2015

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 034371 ENGINEER BRANDON W. JOHNSON

RANDOLPH COUNTY

LOCATION: BRIDGE NO. 750232 ON SR 1107 (LASSITER MILL ROAD) OVER HANNAH'S CREEK.

TYPE OF WORK: GRADING, DRAINAGE, PAVING AND STRUCTURE.

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.08	PAVEMENT MARKINGS - SYMBOLS AND WORD MESSAGES

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	QUANTITY
PAINT (4", 2 COATS) PI	YELLOW DOUBLE CENTER	1600 LF
PAINT (4", 2 COATS) PA	WHITE EDGE LINE	1600 LF

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
LASSITER MILL ROAD	PAINT	NONE

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

D) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.

PAVEMENT MARKING DETAIL



Prepared in the Office of:
SUMMIT DESIGN AND ENGINEERING SERVICES
NC FIRM LICENSE No: P–0339
504 Meadowlands Drive
Hillsborough, NC 27278
(919) 732–3883
(919) 732–6676 (FAX)
TRACY N. PARROTT, PE — PROJECT ENGINEER
BRANDON W. JOHNSON, PE — PROJECT DESIGN ENGINEER

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

INDEX

PMP-1 PAVEMENT MARKING PLAN TITLE, SCHEDULE, QUANTITIES AND PAVEMENT MARKING DETAIL.

17-SEP-2015 14:05
N:\Infrastructure Jobs\2014 Projects\13-0219.103 Div 8 On CallBridges\750232\Traffic\TrafficControl\TCP\750232_TC_PMP_01.dgn
$$$$USERNAME$$$$