

ADDENDUM No. 003
Issued July, 20, 2017NCDOT Wagram Equipment Shop
23161 Airbase Road,
Scotland County, North Carolina

SCO ID# 14-11279-01A

To all Bidding Contractors:

The following items supersede the Bid Documents "Issue for Bidding" dated 06.30.17 and shall become a part of those Bid Documents with full force and effect, as set forth here-in. Bidders shall acknowledge receipt of Addendum Nos 001, 002, and this Addendum No. 003 on the Form of Proposal.

1. Overhead Doors: Section 083613: The following are clarifications regarding the overhead door specifications:

- a. 083613 2.02A 424 series: **Insulated Doors are required. Provide 426 Series as basis of design.**
- b. 083613 2.03A2: **Factory Finish is acceptable (disregard "paint to match siding" note on sheet A6.0.**
- b. 083613 2.04G Locks: **Omit locks for motor operated overhead doors on the main building.**
- c. 083613 2.06G4 Wash bay door: **Provide NEMA4X, corrosion resistant, operator in lieu of NEMA 4.**
- d. 083613 2.05C insulation: **Provide 400 series doors with "polystyrene" insulation.**
- e. A8.0 calls out "manual pull chains": **Omit manual pull chains for O.H. Doors of the Tire Storage Building Alt. #1.**
- f. A6.0 drawing: calls for "electric operation with manual over ride". **Provide chain hoists for manual over ride of overhead doors of main shop building.**

2. Substitution as acceptable manufacturer: Raynor Worldwide commercial sectional doors, Series "Steel form S-24 insulated doors and operators as a "comparable product" for the North Carolina Dept. of Transportation Hwys Division 8 Wagram Equipment shop project as listed in Section 083613. The specific product, when submitted, will be checked for compliance with the project plans, specifications, and warranties.

3. Substitution as approved acceptable supplier of the pre-engineered metal building: Mesco Building Solutions. The specific product, when submitted, will be checked for compliance with the project plans, specifications, and warranties.

4. Owner Furnished Vehicle Lifts: Delete in ground scissors vehicle lift Stirtil Koni "Eco-Lift Eco 60" including floor/foundation recess and sump per detail 8/S4, and all installation related plumbing, mechanical, and electrical work. Retain the in-ground platform lift Stirtil Koni "Sky-Lift 200", foundation, sump, and related PME installation scope, but relocate the lift to Work Bay #2.

5. Substitution as approved acceptable supplier of the Vehicle Exhaust System, Specification section 23 5050.2.08: Carmon

Series CO -X Exhaust Package. It is the Mechanical Contractor's responsibility to provide all required submittal data to show the product meets, plans, specifications, and warranties for equal equipment.

6. Substitution as approved acceptable supplier of the Wall Louvers, Specification section 23 5050.2.04 Wall Louvers: Reliable Products Louvers, Model 635ODS. It is the Mechanical Contractor's responsibility to provide all required submittal data to show the product meets, plans, specifications, and warranties for equal equipment.

End of Addendum No. 003