

Town of Pittsboro

Addenda No. 1

Notice to Prospective Bidders

to construct concrete sidewalk along US 64 (East Street)

August 21, 2014

****Revised Bid Form to submit****

The following items represent material changes to the Bid Form, pp 72, to be submitted as a part of the bid package on or before August 28, 2014, 2pm:

1. Line items #5 and #6: Changed from 15" and 18" RC Pipe Culverts, Class III to HDPE, double-walled, smooth interior, black plastic pipe.
2. Line item #13, Temporary Traffic Control, lump sum item now includes the following scope of work: "Assume one lane closure for the 223' section between Chatham Business Park Dr. and the US Post Office exit road. In doing so, use the following NCDOT Specifications:

2012 NCDOT Roadway Standard Drawings

Std. 1101.01, Work Zone Advance Warning Signs

Std. 1101.02, Temporary Lane Closures

Std. 1101.04, Temporary Shoulder Closures

3. Bid form is not required to be filled out digitally. Hard copy, filled out by hand is acceptable.

****Bidders shall replace the original Bid Form with the attached REVISED bid form****

TOWN OF PITTSBORO

ENGINEERING DEPARTMENT

BID FORM – REVISED 8/21/14

TIP Number: C-5551

WBS No: 51021.3.1

Description: US 64 Bus. Sidewalk Extension

Location: Town of Pittsboro, Chatham County

LINE ITEM	ITEM NUMBER	SECT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT BID
1	0000100000-N	800	MOBILIZATION	1	LS		
2	0000400000-N	801	CONSTRUCTION SURVEYING	1	LS		
3	0000930000-E	SP	GENERAL MISCELLANEOUS ITEM, HANDRAIL	12	LF		
4	0043000000-N	226	GRADING	1	LS		
5	03352000000-E	305	15" DRAINAGE PIPE, HDPE DOUBLE-WALLED, SMOOTH INTERIOR, BLACK PLASTIC	27	LF		
6	03353000000-E	305	18" DRAINAGE PIPE, HDPE DOUBLE-WALLED, SMOOTH INTERIOR, BLACK PLASTIC	223	LF		
7	2286000000-N	840	MASONRY DRAINAGE STRUCTURE	3	EA		
8	2352000000-N	840	FRAME WITH GRATE, STD 840.xx	3	EA		
9	2570000000-N	SP	MODIFIED CONCRETE FLUME	1	EA		
10	2591000000-E	848	4" CONCRETE SIDEWALK	1,171	SY		
11	26000000000-N	SP	RETROFIT EXISTING CURB RAMP	1	EA		
12	2605000000-N	848	CONCRETE CURB RAMP	3	EA		
13	4457000000-N	1105	TEMPORARY TRAFFIC CONTROL	1	LS		
14	48200000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	368	LF		
15	60000000000-E	1605	TEMPORARY SILT FENCE	2,010	LF		
16	60060000000-E	1610	EROSION CONTROL STONE, CLASS A	50	TON		
17	6009000000-E	1610	EROSION CONTROL STONE, CLASS B	24	TON		
18	6012000000-E	1610	SEDIMENT CONTROL STONE	50	TON		
19	6029000000-E	SP	SAFETY FENCE	2,020	LF		

LINE ITEM	ITEM NUMBER	SECT	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT BID
20	6042000000-E	1632	1/4" HARDWARE CLOTH	120	LF		
21	6071010000-E	SP	WATTLE	70	LF		
22	6071020000-E	SP	POLYACRYLAMIDE (PAM)	7	LB		
23	6084000000-E	1660	SEED & MULCHING	0.80	AC		

TOTAL BID FOR PROJECT: _____

CONTRACTOR _____

ADDRESS _____

Federal Identification Number _____ Contractors License Number _____

Authorized Agent _____ Title _____

Signature _____ Date _____

****The REVISED bid form must be filled out and signed and submitted with the bid package.**