D8CAD221432

COMPUTED BY: DDC DATE: 8-31-2015
CHECKED BY: GSD DATE: 9-2-2015

PROJECT NO.	SHEET NO.
36049.93	3-A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF EARTHWORK

Station	Station	Uncl. Excav.	Embank. +%	Borrow	Waste
-L- 13+80	-L-15+20	78	124	46	
-T1- 11+20	-T1- 14+20	3245	0		3245
-T1- 16+20	-T1- 19+80	2197			
SUBTOTALS:		5520	124	46	3245
WASTE TO REPLACE BORROW				-46	-46
PROJECT TOTALS:		5520			3199
GRAND TOTALS:		5520			3199
SAY:		**5525**			**3200**

SUMMARY OF EXISTING ASPHALT PAVEMENT REMOVAL

LINE	Station	Station	LOC LT/RT/CL	SF
-L	14+00	15+00	CL	2000
			TOTAL:	2000.00
			SAY:	**2000**

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".