

PROJECT NO.	SHEET NO.	TOTAL NO.
8.101911, 8.104711		
8.105311, 8.106311		

**SUMMARY OF QUANTITIES**

PROJECT NO	COUNTY	PICTURE NO	ROUTE	DESCRIPTION	LAT.	LONG.	036000000-E 12" RC PIPE CULVERTS, CLASS III	036600000-E 15" RC PIPE CULVERTS, CLASS III	037200000-E 18" RC PIPE CULVERTS, CLASS III	227500000-E FLOWABLE FILL	236500000-N FRAME WITH TWO GRATES, STD 840.22	228600000-N MASONRY DRAINAGE STRUCTURE	247200000-N GENERIC DRAINAGE ITEM - REPLACE CONCRETE APRON	247300000-N GENERIC DRAINAGE ITEM - DROP INLET REPAIR	248400000-N GENERIC DRAINAGE ITEM - JOINT SEAL	248900000-N GENERIC DRAINAGE ITEM - CONCRETE DITCH REPAIR	253000000-N GENERIC GRADING ITEM - BACKFILL AROUND DRAINAGE INLET	285000000-N GENERIC DRAINAGE ITEM - CONCRETE TOP SLAB (LID)	285000000-N GENERIC DRAINAGE ITEM - ADJUST EXISTING CONCRETE LID	445700000-E TEMPORARY TRAFFIC CONTROL	603600000-E MATTING (EROSION CONTROL)	607101000-E WATTLE	608400000-E SEED & MULCHING	SPECIAL NOTES		
							LF	LF	LF	CY	EA	EA	EA	EA	LF	SY	CY	EA	EA	EA	SYD	LF	ACR			
8.101911	Chatham	79	US-1	380' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1972 (Pea Ridge Rd.) in NB shoulder	35°38'02.31585"N	79°03'11.82280"W											1						0.005	Needs backfill		
	<b>TOTAL FOR PICTURE NO. 79</b>																	1						0.005		
	Chatham	80	US-1	2,720' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1972 (Pea Ridge Rd.) in NB shoulder	35°38'12.65902"N	79°02'36.26330"W								1	12.5			1							Concrete apron is cracked with chunk breaking off. Needs new apron. Needs grading	
	<b>TOTAL FOR PICTURE NO. 80</b>													1	12.5			1								
	Chatham	81	US-1	650' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1931 (Moncure School Rd.) in median	35°37'41.78899"N	79°04'32.76781"W				1								3					4	0.005	Needs flowable fill and some grading	
	<b>TOTAL FOR PICTURE NO. 81</b>									1								3					4	0.005		
	Chatham	83	US-1	390' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1972 (Pea Ridge Rd.) in median	35°38'03.10904"N	79°03'12.08619"W				1								3					3	0.005	Needs flowable fill and some grading	
	<b>TOTAL FOR PICTURE NO. 83</b>									1								3					3	0.005		
	Chatham	84	US-1	440' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1972 (Pea Ridge Rd.) in median	35°38'05.62769"N	79°03'02.52231"W								1	12.5			7					12	15	0.005	Needs backfill, and new concrete apron, some grading
	<b>TOTAL FOR PICTURE NO. 84</b>													1	12.5			7					12	15	0.005	
	Chatham	85	US-1	980' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1972 (Pea Ridge Rd.) in median	35°38'07.44500"N	79°02'56.32483"W								1	12.5			2							0.005	Needs new concrete apron and needs backfill
	<b>TOTAL FOR PICTURE NO. 85</b>													1	12.5			2								0.005
	Chatham	88	US-1	1.24 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1972 (Pea Ridge Rd.) in median	35°38'26.19389"N	79°01'53.18441"W								1	12.5			2					4	0.005	Needs new concrete apron and needs backfill	
	<b>TOTAL FOR PICTURE NO. 88</b>													1	12.5			2					4	0.005		
	Chatham	89	US-1	1.50 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1972 (Pea Ridge Rd.) in median	35°38'30.88779"N	79°01'37.01934"W												1							0.005	Needs flowable fill
	<b>TOTAL FOR PICTURE NO. 89</b>																	1								0.005
	Chatham	90	US-1	940' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1910 (New Elam Church Rd.) in median	35°38'39.50695"N	79°01'01.09866"W								1	1	12.5		7					15	10	0.005	Needs new concrete apron and backfill, root growing from under apron into box, might need patch inside wall. Needs grading
	<b>TOTAL FOR PICTURE NO. 90</b>													1	1	12.5		7					15	10	0.005	
	Chatham	92	US-1	4,440' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1972 (Pea Ridge Rd.) in NB shoulder	35°38'18.52610"N	79°02'16.59103"W								1	12.5			1								Needs new concrete apron and needs some backfill
	<b>TOTAL FOR PICTURE NO. 92</b>													1	12.5			1								
Chatham	93	US-1	1.16 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1972 (Pea Ridge Rd.) in NB shoulder	35°38'24.21354"N	79°01'57.63169"W								1	12.5			3					2	0.005	Needs new concrete apron and needs backfill		
<b>TOTAL FOR PICTURE NO. 93</b>													1	12.5			3					2	0.005			
Chatham	94	US-1	1.24 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1972 (Pea Ridge Rd.) in NB shoulder	35°38'25.64074"N	79°01'52.79756"W								1	12.5			3					7	10	0.005	Place new concrete apron and backfill ruts, and grade to drain	
<b>TOTAL FOR PICTURE NO. 94</b>													1	12.5			3					7	10	0.005		
Chatham	95	US-1	1,120' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1011 (Old US 1) in median	35°38'40.46777"N	79°00'24.20920"W												3					3	0.005	Needs flowable fill and some grading		
<b>TOTAL FOR PICTURE NO. 95</b>																	3					3	0.005			
Chatham	97	US-1	1,700' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1011 (Old US 1) in median	35°38'37.64193"N	78°59'50.18101"W		8			1							2					2	0.005	need flowable fill and some grading, also pipe beside structure may be damaged.		
<b>TOTAL FOR PICTURE NO. 97</b>							8			1							2					2	0.005			
<b>TOTAL FOR PROJ NO. 8.101911</b>							8			3			8	1	100			39			1	52	35	0.060		
8.104711	Hoke	1	US-401	US 401 (Fayetteville Rd.) intersection with SR 1408 (Club Pond Rd.) EB shoulder SE quadrant	35°00'26.36558"N	79°10'21.64820"W											1								Concrete apron needs to be replaced	
	<b>TOTAL FOR PICTURE NO. 1</b>																	1								
	Hoke	5	US-401	200' East of US 401 (Fayetteville Rd.) intersection with SR 1634 (Belle Chase Dr.) in median	35°00'30.86582"N	79°09'59.35198"W												1					6	0.005	Concrete apron is cracked, but still functional. Ditch needs to be stabilized	
	<b>TOTAL FOR PICTURE NO. 5</b>																	1					6	0.005		
	Hoke	8	US-401	770' East of US 401 (Fayetteville Rd.) intersection with SR 1634 (Belle Chase Dr.) in median	35°00'32.95782"N	79°09'53.05282"W												1					4	0.005	Concrete apron is cracked, but still functional. Needs grading	
	<b>TOTAL FOR PICTURE NO. 8</b>																	1					4	0.005		
	Hoke	9	US-401	330' west of US 401 (Fayetteville Rd.) intersection with SR 1409 (Johnson Mill Rd.) in median	35°00'48.77424"N	79°09'33.92898"W												1								Needs new frame grate
	<b>TOTAL FOR PICTURE NO. 9</b>																	1								
	Hoke	10	US-401	1,130' east of US 401 (Fayetteville Rd.) intersection with SR 1409 (Johnson Mill Rd.) in median	35°01'00.78279"N	79°09'23.90005"W												12.5								Needs seal around structure
	<b>TOTAL FOR PICTURE NO. 10</b>																	12.5								
	Hoke	13	US-401	1,460' east of US 401 (Fayetteville Rd.) intersection with SR 1588 (Bugle Call Dr.) in median	35°01'27.98978"N	79°08'51.97433"W								1	12.5			1					4	0.005	Concrete apron undermined on both sides of box, needs new concrete apron	
	<b>TOTAL FOR PICTURE NO. 13</b>													1	12.5			1					4	0.005		
	Hoke	16	US-401	70' West of US 401 (Fayetteville Rd.) intersection with SR 1411 (N. Parker Church Rd.) in WB shoulder	35°01'43.19073"N	79°08'24.55908"W								1	12.5											Concrete apron has some undermining/settling, look like it will need backfill and a new concrete apron
	<b>TOTAL FOR PICTURE NO. 16</b>													1	12.5											
	Hoke	21	US-401	1,520' East of US 401 (Fayetteville Rd.) intersection with SR 1411 (N. Parker Church Rd.) in median	35°01'51.09781"N	79°08'08.12633"W								1	1	12.5		1								Concrete apron needs to be replaced, missing steps, pipe coming into side wall needs grout and trimming, needs flowable fill, has washout, side of str. Likely under mined
	<b>TOTAL FOR PICTURE NO. 21</b>													1	1	12.5		1								
	Hoke	24	US-401	1,650' East of US 401 (Fayetteville Rd.) intersection with SR 1411 (N. Parker Church Rd.) in median	35°01'51.39471"N	79°08'06.54182"W								1	1	12.5										Concrete apron needs to be replaced, has washout at bottom of str., hard to tell, but bottom section of wall may be gone.
	<b>TOTAL FOR PICTURE NO. 24</b>													1	1	12.5										
	Hoke	25	US-401	2,410' East of US 401 (Fayetteville Rd.) intersection with SR 1411 (N. Parker Church Rd.) in median	35°01'52.43352"N	79°07'57.42486"W								1	12.5											Concrete apron needs to be replaced, looks like a section of it is missing.
	<b>TOTAL FOR PICTURE NO. 25</b>													1	12.5											
Hoke	26	US-401	780' West of US 401 (Fayetteville Rd.) intersection with Heybud Dr. in median	35°01'53.51213"N	79°07'47.37916"W																				Concrete apron is cracked, but functional. Box needs to be sealed up	
<b>TOTAL FOR PICTURE NO. 26</b>																										
Hoke	29	US-401	410' West of US 401 (Fayetteville Rd.) intersection with SR 1339 (Carolina Dr.) in EB shoulder	35°01'53.44065"N	79°06'49.05647"W								1	12.5											Concrete apron is cracked and settling, needs new apron	
<b>TOTAL FOR PICTURE NO. 29</b>													1	12.5												
Hoke	31	US-401	980' East of US 401 (Fayetteville Rd.) intersection with SR 1317 (Brock Rd.) in median	35°01'54.41013"N	79°06'19.90551"W								1	12.5											Concrete apron is broken, needs to be replaced, needs backfill	
<b>TOTAL FOR PICTURE NO. 31</b>													1	12.5												
Hoke	32	US-401	360' West of US 401 (Fayetteville Rd.) intersection with SR 1305 (Wayside Rd.) in median	35°01'54.70212"N	79°05'47.43805"W								1	12.5											Concrete apron missing chunk, needs new apron.	
<b>TOTAL FOR PICTURE NO. 32</b>													1	12.5												
<b>TOTAL FOR PROJ NO. 8.104711</b>											1		9	2	137.5			3			1	14		0.015		

PROJECT NO.	SHEET NO.	TOTAL NO.
8.101911, 8.104711		
8.105311, 8.106311		

### SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	PICTURE NO	ROUTE	DESCRIPTION	LAT.	LONG.	036000000-E	036600000-E	037200000-E	227500000-E	236500000-N	228600000-N	247200000-N	247300000-N	248400000-N	248900000-N	253000000-N	285000000-N	285000000-N	445700000-E	603600000-E	607101000-E	608400000-E	SPECIAL NOTES	
							12" RC PIPE CULVERTS, CLASS III	15" RC PIPE CULVERTS, CLASS III	18" RC PIPE CULVERTS, CLASS III	FLOWABLE FILL	FRAME WITH TWO GRATES, STD 840.22	MASONRY DRAINAGE STRUCTURE	GENERIC DRAINAGE ITEM - REPLACE CONCRETE APRON	GENERIC DRAINAGE ITEM - DROP INLET REPAIR	GENERIC DRAINAGE ITEM - JOINT SEAL	GENERIC DRAINAGE ITEM - CONCRETE DITCH REPAIR	GENERIC GRADING ITEM - BACKFILL AROUND DRAINAGE INLET	GENERIC DRAINAGE ITEM - CONCRETE TOP SLAB (LID)	GENERIC DRAINAGE ITEM - ADJUST EXISTING CONCRETE LID	TEMPORARY TRAFFIC CONTROL	MATTING (EROSION CONTROL)	WATTLE	SEED & MULCHING		
							LF	LF	LF	CY	EA	EA	EA	EA	LF	SY	CY	EA	EA	EA	SYD	LF	ACR		
		23	US-1	1.14 miles South of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1173 (Pine Forrest Rd.) in NB shoulder	35°20'28.55106"N	79°14'11.56525"W				1							3					2		0.005	Needs flowable fill and some grading
		<b>TOTAL FOR PICTURE NO. 23</b>							1								3					2		0.005	
		30	US-1	350' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1731 (Quail Ridge Dr.) in median	35°23'39.56987"N	79°13'52.37423"W						1		1			1							0.005	Needs an entire new drainage structure and grading
		<b>TOTAL FOR PICTURE NO. 30</b>									1		1				1							0.005	
		31	US-1	530' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1733 (Divot Dr.) in median	35°23'52.52153"N	79°13'52.98901"W								1		1	1	1						0.005	Needs brick wall repaired, new concrete lid, and some grading, may need new concrete swale
		<b>TOTAL FOR PICTURE NO. 31</b>											1		1	1	1							0.005	
		32	US-1	230' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with Ridgefield Ct. in median	35°23'57.38599"N	79°13'53.09574"W										4	1							0.005	Leftover concrete lid needs to be removed, needs grading and apron repaired. Pipe near structure may be damaged and need replacement
		<b>TOTAL FOR PICTURE NO. 32</b>													4	1								0.005	
		33	US-1	720' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with Ridgefield Ct. in median	35°24'02.22981"N	79°13'53.26311"W	8		8					1		3	1	1						0.005	Concrete swale needs to be repaired, wall needs repair, needs new concrete lid. Pipe near structure may be damaged and need replacement
		<b>TOTAL FOR PICTURE NO. 33</b>					8	8					1		3	1	1							0.005	
		34	US-1	760' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1179 (Rocky Fork Church Rd.) in median	35°24'21.50414"N	79°13'53.67073"W																		0.005	Needs new concrete lid
		<b>TOTAL FOR PICTURE NO. 34</b>																						0.005	
		35	US-1	1,330' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1179 (Rocky Fork Church Rd.) in median	35°24'27.05527"N	79°13'54.00423"W								1		3	1	1						0.005	Needs new lid, part of the wall for the structure is also damaged and needs repair, may need concrete swale, will need some grading
		<b>TOTAL FOR PICTURE NO. 35</b>											1		3	1	1							0.005	
		36	US-1	630' South of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1302 (Arthur Maddox Rd.) in median	35°24'54.60875"N	79°13'46.39381"W																		0.005	Needs new lid and possible grading
		<b>TOTAL FOR PICTURE NO. 36</b>																						0.005	
		37	US-1	430' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1302 (Arthur Maddox Rd.) in median	35°25'04.41048"N	79°13'42.12491"W								1										0.005	Needs new lid, needs grout around pipe
		<b>TOTAL FOR PICTURE NO. 37</b>											1											0.005	
		38	US-1	420' South of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1197 (McDaniel Dr.) in median	35°25'47.11378"N	79°13'18.24804"W																		0.005	Lid needs to be placed back on structure
		<b>TOTAL FOR PICTURE NO. 38</b>																						0.005	
		41	US-1	490' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1334 (Pendergrass Rd.) in median	35°26'33.62690"N	79°12'55.51793"W																		0.005	Lid needs to be placed back on structure
		<b>TOTAL FOR PICTURE NO. 41</b>																						0.005	
		42	US-1	140' South of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1237 (Carthage St.) in median	35°26'38.20784"N	79°12'53.97886"W								1										0.005	Needs new lid and concrete apron, some backfill
		<b>TOTAL FOR PICTURE NO. 42</b>											1											0.005	
		43	US-1	530' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1237 (Carthage St.) in median	35°26'44.87313"N	79°12'53.76857"W																		0.005	Needs new lid
		<b>TOTAL FOR PICTURE NO. 43</b>																						0.005	
		44	US-1	430' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1333 (Phillips Dr.) in median	35°27'07.48697"N	79°12'49.39003"W																		0.005	May need new concrete swale section and concrete apron
		<b>TOTAL FOR PICTURE NO. 44</b>																						0.005	
		98	US-1	1,130' North of US Hwy 1 (Jefferson Davis Hwy.) intersection with SR 1333 (Phillips Dr.) in median	35°27'13.37333"N	79°12'45.01687"W																		0.005	Needs seal around structure
		<b>TOTAL FOR PICTURE NO. 98</b>																						0.005	
		99	US-1	1,420' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection with SR 1333 (Phillips Dr.) in median	35°27'15.70559"N	79°12'43.03521"W																		0.005	Needs seal around structure
		<b>TOTAL FOR PICTURE NO. 99</b>																						0.005	
		100	US-1	1,830' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection with SR 1333 (Phillips Dr.) in median	35°27'19.05681"N	79°12'40.20543"W																		0.005	Needs seal around structure
		<b>TOTAL FOR PICTURE NO. 100</b>																						0.005	
		101	US-1	2,220' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection with SR 1333 (Phillips Dr.) in median	35°27'22.30234"N	79°12'37.45258"W																		0.005	Needs seal around structure
		<b>TOTAL FOR PICTURE NO. 101</b>																						0.005	
		102	US-1	4,600' South of US Hwy 1 (Claude E. Pope Memorial Hwy.)	35°27'26.38479"N	79°12'33.99880"W																		0.005	Needs seal around structure
		<b>TOTAL FOR PICTURE NO. 102</b>																						0.005	
		45	US-1	4,040' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with NC 42 (Wicker St.) in median	35°27'30.85837"N	79°12'30.20809"W				1														0.005	Needs new concrete apron and needs backfill, may need flowable fill
		<b>TOTAL FOR PICTURE NO. 45</b>							1															0.005	
		46	US-1	1,630' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with NC 42 (Wicker St.) in median	35°27'51.72804"N	79°12'16.24838"W																		0.005	Needs backfill/grading and new concrete apron
		<b>TOTAL FOR PICTURE NO. 46</b>																						0.005	
		47	US-1	3,040' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with NC 42 (Wicker St.) in NB shoulder	35°27'38.86484"N	79°12'22.73229"W																		0.005	Needs new lid
		<b>TOTAL FOR PICTURE NO. 47</b>																						0.005	
		48	US-1	790' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with NC 42 (Wicker St.) in NB shoulder	35°27'59.54275"N	79°12'12.62873"W																		0.005	Lid needs to be placed back on structure
		<b>TOTAL FOR PICTURE NO. 48</b>																						0.005	
		49	US-1	1,570' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with NC 42 (Wicker St.) in median	35°28'22.07578"N	79°12'05.73566"W																		0.005	Needs concrete apron and backfill. See pics
		<b>TOTAL FOR PICTURE NO. 49</b>																						0.005	
		50	US-1	2,620' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with NC 42 (Wicker St.) in median	35°28'32.03098"N	79°12'02.35011"W																		0.005	Needs new concrete apron and needs backfill
		<b>TOTAL FOR PICTURE NO. 50</b>																						0.005	
		51	US-1	1,290' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1009 (Carbonton Rd.) in median	35°28'36.46103"N	79°12'00.79990"W																		0.005	Needs new concrete apron
		<b>TOTAL FOR PICTURE NO. 51</b>																						0.005	
		52	US-1	880' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1009 (Carbonton Rd.) in median	35°28'40.35048"N	79°11'59.47239"W																		0.005	Needs new concrete apron and needs backfill
		<b>TOTAL FOR PICTURE NO. 52</b>																						0.005	
		53	US-1	1,050' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1009 (Carbonton Rd.) in median	35°28'58.72327"N	79°11'53.23760"W																		0.005	Needs new concrete apron/swale and needs backfill
		<b>TOTAL FOR PICTURE NO. 53</b>																						0.005	
		54	US-1	510' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with SR 1100 (Spring Ln.) in median	35°29'19.70677"N	79°11'49.07151"W																		0.005	Needs new concrete apron and needs backfill
		<b>TOTAL FOR PICTURE NO. 54</b>																						0.005	
		55	US-1	1,110' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) intersection/bridge with US 421 BUS. (N. Horner Blvd.) in median	35°29'32.53397"N	79°11'47.11316"W																			

PROJECT NO.	SHEET NO.	TOTAL NO.
8.101911, 8.104711		
8.105311, 8.106311		

**SUMMARY OF QUANTITIES**

PROJECT NO	COUNTY	PICTURE NO	ROUTE	DESCRIPTION	LAT.	LONG.	036000000-E 12" RC PIPE CULVERTS, CLASS III	036600000-E 15" RC PIPE CULVERTS, CLASS III	037200000-E 18" RC PIPE CULVERTS, CLASS III	227500000-E FLOWABLE FILL	236500000-N FRAME WITH TWO GRATES, STD 840.22	228600000-N MASONRY DRAINAGE STRUCTURE	247200000-N GENERIC DRAINAGE ITEM - REPLACE CONCRETE APRON	247300000-N GENERIC DRAINAGE ITEM - DROP INLET REPAIR	248400000-N GENERIC DRAINAGE ITEM - JOINT SEAL	248900000-N GENERIC DRAINAGE ITEM - CONCRETE DITCH REPAIR	253000000-N GENERIC GRADING ITEM - BACKFILL AROUND DRAINAGE INLET	285000000-N GENERIC DRAINAGE ITEM - CONCRETE TOP SLAB (LID)	285000000-N GENERIC DRAINAGE ITEM - ADJUST EXISTING CONCRETE LID	445700000-E TEMPORARY TRAFFIC CONTROL	603600000-E MATTING (EROSION CONTROL)	607101000-E WATTLE	608400000-E SEED & MULCHING	SPECIAL NOTES		
							LF	LF	LF	CY	EA	EA	EA	EA	LF	SY	CY	EA	EA	EA	SYD	LF	ACR			
	Lee	56	US-1	2,100' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in NB shoulder	35°31'43.90596"N	79°10'54.06834"W																				
<b>TOTAL FOR PICTURE NO. 56</b>																									0.005 Needs new concrete apron and needs backfill	
	Lee	57	US-1	3,820' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in median	35°31'59.38760"N	79°10'46.24407"W																				
<b>TOTAL FOR PICTURE NO. 57</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	58	US-1	4,230' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in median	35°32'02.76604"N	79°10'43.51205"W																				
<b>TOTAL FOR PICTURE NO. 58</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	59	US-1	1.05 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in median	35°32'13.12676"N	79°10'33.44056"W																				
<b>TOTAL FOR PICTURE NO. 59</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	60	US-1	1.25 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in median	35°32'20.93108"N	79°10'24.97035"W																				
<b>TOTAL FOR PICTURE NO. 60</b>																										0.005 Needs new seal around structure
	Lee	61	US-1	1.57 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in median	35°32'33.07184"N	79°10'11.60602"W																				
<b>TOTAL FOR PICTURE NO. 61</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	62	US-1	1.70 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in median	35°32'38.20906"N	79°10'06.04750"W																				
<b>TOTAL FOR PICTURE NO. 62</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	63	US-1	1.90 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in median	35°32'46.02782"N	79°09'57.60987"W																				
<b>TOTAL FOR PICTURE NO. 63</b>																										0.005 Needs new seal around structure
	Lee	64	US-1	2.01 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in median	35°32'50.60094"N	79°09'52.95556"W																				
<b>TOTAL FOR PICTURE NO. 64</b>																										0.005 Needs new seal around structure
	Lee	65	US-1	2.43 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in median	35°33'08.16070"N	79°09'37.25531"W																				
<b>TOTAL FOR PICTURE NO. 65</b>																										0.005 Concrete apron in fine, but has undermining underneath. Will need to remove apron use backfill and replace apron.
	Lee	66	US-1	1,680 South of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with SR 1415 (Colon Rd.) in median	35°33'26.30895"N	79°09'22.59535"W																				
<b>TOTAL FOR PICTURE NO. 66</b>																										0.005 Needs new seal around structure
	Lee	67	US-1	1,070 South of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with SR 1415 (Colon Rd.) in median	35°33'31.27431"N	79°09'18.57392"W																				
<b>TOTAL FOR PICTURE NO. 67</b>																										0.005 Needs patchwork on concrete apron, and has undermining underneath concrete apron.
	Lee	68	US-1	1.41 miles North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in SB shoulder	35°32'27.53861"N	79°10'18.74858"W																				
<b>TOTAL FOR PICTURE NO. 68</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	69	US-1	4,630' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in SB shoulder	35°32'06.48682"N	79°10'41.36017"W																				
<b>TOTAL FOR PICTURE NO. 69</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	70	US-1	2,510' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with US 15 (Hawkins Ave.) in SB shoulder	35°31'48.06571"N	79°10'53.83497"W																				
<b>TOTAL FOR PICTURE NO. 70</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	71	US-1	3,270' North of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with SR 1415 (Colon Rd.) in median	35°34'06.51773"N	79°08'48.55966"W																				
<b>TOTAL FOR PICTURE NO. 71</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	72	US-1	2,740' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with SR 1426 (Zion Church Rd.) in median	35°34'20.13994"N	79°08'31.81393"W																				
<b>TOTAL FOR PICTURE NO. 72</b>																										0.005 One of the grates is missing
	Lee	73	US-1	900' South of US Hwy 1 (Claude E. Pope Memorial Hwy.) Intersection/bridge with SR 1423 (Farrell Rd.) in median	35°35'09.95349"N	79°07'27.21231"W																				
<b>TOTAL FOR PICTURE NO. 73</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	74	US-1	4,140' North of US Hwy 1 (Jefferson Davis Hwy.) Intersection with SR 1173 (Pine Forrest Rd.) in NB shoulder	35°22'07.26713"N	79°13'54.34910"W																				
<b>TOTAL FOR PICTURE NO. 74</b>																										0.005 Needs backfill
	Lee	75	US-1	350' North of US Hwy 1 (Jefferson Davis Hwy.) Intersection with SR 1731 (Quail Ridge Dr.) in median	35°23'39.56987"N	79°13'52.37423"W																				
<b>TOTAL FOR PICTURE NO. 75</b>																										0.005 Needs new concrete apron and needs backfill
	Lee	104	US-421 BUS	3,750' South of US 421 BUS. (Boone Trail Rd.) Intersection/bridge with SR 1384 (Forestwood Park Rd.) in NB shoulder	35°31'18.5232"N	79°13'22.1376"W																				
<b>TOTAL FOR PICTURE NO. 104</b>																										0.005 Needs new concrete apron and needs backfill
<b>TOTAL FOR PROJ NO. 8.105311</b>							8		8	2	1	1	24	7	419	24	88	9	3	1	15		0.045			

