



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

October 5, 2023

NOTICE TO PROSPECTIVE BIDDERS


Contract Number: DH00538
TIP Number: N/A
WBS Number: 17BP.8.R.124
County: Chatham
Description: Replacement of Bridge No. 94 over Dry Creek on SR 1520 (Old NC 87)
Subject: **Addendum # 1**

The following revisions have been made to the project proposal associated with the above referenced project:

- The line item No. 72 has been changed from 3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS to 3'-0" X 3'-3" PRESTRESSED CON BOX BEAMS .
- Please replace the North Carolina Department of Transportation Contract Item Sheets for DH00538 in the Proposal.
- The addendum file DH00538.001x file has been updated to the Bid Express site.

If this office can provide additional information, please contact me at (910) 773-8034 or cgbrown1@ncdot.gov.

Sincerely,

DocuSigned by:

15C686F6ED674C5...

Chad G. Brown
Division Proposal Engineer

cc: Mr. M. G. Phillips
Mr. M. L. McKenzie
File

County: CHATHAM

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (14+02 -L-)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	200 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0008	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	10 SY		
0009	0335200000-E	305	15" DRAINAGE PIPE	28 LF		
0010	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0011	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0012	1330000000-E	607	INCIDENTAL MILLING	220 SY		
0013	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	250 TON		
0014	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	230 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	330 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	45 TON		
0017	2000000000-N	806	RIGHT-OF-WAY MARKERS	8 EA		

County: CHATHAM

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0019	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	18 LF		
0021	3030000000-E	862	STEEL BEAM GUARDRAIL	25 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0023	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0024	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4 EA		
0025	3649000000-E	876	RIP RAP, CLASS B	30 TON		
0026	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	240 SY		
0027	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0028	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,920 LF		
0029	5801000000-E	1530	ABANDON 8" UTILITY PIPE	300 LF		
0030	5804000000-E	1530	ABANDON 12" UTILITY PIPE	325 LF		
0031	6000000000-E	1605	TEMPORARY SILT FENCE	1,245 LF		
0032	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	65 TON		
0033	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50 TON		
0034	6012000000-E	1610	SEDIMENT CONTROL STONE	40 TON		

County: CHATHAM

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0036	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0037	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0038	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0039	6029000000-E	SP	SAFETY FENCE	200 LF		
0040	6030000000-E	1630	SILT EXCAVATION	30 CY		
0041	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,280 SY		
0042	6037000000-E	SP	COIR FIBER MAT	500 SY		
0043	6042000000-E	1632	1/4" HARDWARE CLOTH	120 LF		
0044	6071020000-E	SP	POLYACRYLAMIDE (PAM)	15 LB		
0045	6071030000-E	1640	COIR FIBER BAFFLE	10 LF		
0046	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0047	6087000000-E	1660	MOWING	0.5 ACR		
0048	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0049	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0050	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0051	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		

County: CHATHAM

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	611450000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0053	611700000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0054	611750000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0055	612300000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0056	802100000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** 14+02.00-L-	Lump Sum	L.S.	
0057	806500000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0058	809600000-E	450	PILE EXCAVATION IN SOIL	42 LF		
0059	809700000-E	450	PILE EXCAVATION NOT IN SOIL	28 LF		
0060	8112730000-N	450	PDA TESTING	1 EA		
0061	812100000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** 14+02.00-L-	Lump Sum	L.S.	
0062	818200000-E	420	CLASS A CONCRETE (BRIDGE)	58 CY		
0063	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** 14+02.00-L-	Lump Sum	L.S.	
0064	821700000-E	425	REINFORCING STEEL (BRIDGE)	9,220 LB		
0065	832820000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES HP12X53 STEEL PILES	14 EA		
0066	836400000-E	450	HP 12 X 53 STEEL PILES	245 LF		
0067	839100000-N	450	STEEL PILE POINTS	14 EA		

County: CHATHAM

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0068	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	200 LF		
0069	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	348 TON		
0070	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	385 SY		
0071	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0072	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,100 LF		

0949/Oct05/Q26077.1/D353045330000/E72

Total Amount Of Bid For Entire Project :