PROJ. REFERENCE NO.	SHEET NO.
17BP.8.R.127	TMP-2

SIGN NUMBER: SP-1
TYPE: STATIONARY
QUANTITY: SEE PLANS

SIGN WIDTH: 4′-6″
HEIGHT: 2′-0″
TOTAL AREA: 9.0 Sq.Ft.

BORDER TYPE: INSET
RECESS: 0.47″
WIDTH: 0.63″
RADII: 1.5″

NO. Z BARS:
LENGTH:

BACKG COLOR: Fluorescent Orange
COPY COLOR: Black

SYMBOL	X	Y	WID	HT

MAT′L: 0.080″ (2.0 mm) ALUMINUM

1. Legend and border shall be direct applied black non-reflective sheeting.
2. Background shall be NC GRADE B fluorescent orange retroreflective sheeting.

DESIGN BY: J BAUMAN
PROJECT ID: MOORE 212
CHECKED BY: S MILLER
LOCATION: MOORE COUNTY
DATE: MAY 19, 2017
DIVISION: 8



BORDER
R=1.5″
TH=0.63″
IN=0.47″

Panel Style: construction_guide.ssi
M.U.T.C.D.: 2009 Edition

Spacing Factor is 1 unless specified otherwise

LETTER POSITIONS

Letter locations are panel edge to lower left corner

	G	U	R	N	E	Y		W	E	S	T															Series/Size Text Length
	3.1	7.6	12.3	16.7	21.4	25	28.8	34.8	40.2	44	47.9															C 2000 47.9
	R	O	A	D																						C 2000
	18.7	23	27.2	31.9																						16.6

FILENAME: Bridge 212 TMP-2

NORTH CAROLINA D.O.T. SIGN DETAIL

SEPI ENGINEERING & CONSTRUCTION
1025 Wade Avenue
Raleigh, NC 27605
Tel:919-789-9977
Fax:919-789-9591
License: C-2197

APPROVED: _____

DATE: _____

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 037026 ENGINEER STEVEN D. MILLER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION WORK ZONE TRAFFIC CONTROL

SIGN DESIGN

4/16/2018
X:\2017\SEI7.034.00 Bridge 212\TP\Traffic\TMP\Bridge 212 TMP-2.dgn
JBauman