



PROJECT NO.	SHEET NO.	l
2023CPT.08.12.20632	2	




MAP SHEETS 1, 4



PROJECT NO. SHEET NO. 2023CPT.08.12.20632 3




MAP SHEETS 2, 3, 6






PROJECT NO. SHEET NO.
2023CPT.08.12.20632 4



MAP NUMBERS 5, 7, 8



PROJECT NO.	SHEET NO.			
2023CPT.08.12.20632	5			



	PAVEMENT SCHEDULE
F1	PROP. ASPHALT SURFACE TREATMENT, DOUBLE SEAL
U	EXISTING PAVEMENT

PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.08.12.20632	6	
2023CP1.08.12.20032	0	

SUMMARY OF QUANTITIES

												1575000000-E	1704000000-E	1803500000-E	1838000000-E	1838500000-N	2143000000-E
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, DOUBLE SEAL	EMULSION FOR ASPHALT SURFACE TREATMENT	VACUUM TRUCK	BLOTTING SAND
										MI	FT	TONS	TONS	SY	GAL	WK	TON
2023CPT.08.12.20632	Moore	1	SR-1493 / CRABTREE RD	FROM NC 22 TO NC 24	1	2	2WU	NO	NO	2.16	20	3	70	25,344.00	13,939		
	TOTAL	FOR MAP N	IO. 1							2.16		3	70	25,344.00	13,939		
				FROM NC 705 TO SR 1405 (DOVER													
2023CPT.08.12.20632	Moore	2	SR-1428 / DAN RD	CHURCH RD)	1	2	2WU	NO	NO	4.09	20	6	125	47,990.00	26,394		
	TOTAL	FOR MAP N	IO. 2							4.09		6	125	47,990.00	26,394		
				FROM NC 705 TO SR 1411 (MT ZIONS													
2023CPT.08.12.20632	Moore	3	SR-1410 / ADAMS RD	CHURCH RD)	1	2	2WU	NO	NO	2.02	19.5	3	70	23,109.00	12,710		
	TOTAL	FOR MAP N	IO. 3							2.02		3	70	23,109.00	12,710		
				FROM SR1487 (BORDEN RD) TO SR													
2023CPT.08.12.20632	Moore	4	SR-1489 / COCKMAN RD	1477 (PLANK RD)	1	2	2WU	NO	NO	0.66	20	2	50	7,774.00	4,260		
	TOTAL FOR MAP NO. 4									0.66		2	50	7,774.00	4,260		
		_		FROM SR 1661 (STANTON HILL RD)		_						_				*	*
2023CPT.08.12.20632	Moore		SR-1663 / LAMMS GROVE RD	TO 15-501	1	2	2WU	NO	NO	2.16	18	5	100	22,810.00	12,546		
	TOTAL	FOR MAP N	10. 5							2.16		5	100	22,810.00	12,546		
				FROM SR 1138 (EAGLE SPRINGS RD) TO PVMT JOINT AT SR1140 (MARTIN													
2023CPT.08.12.20632	Moore	6	SR-1139 / EAGLE BRANCH RD	RD)	1	2	2WU	NO	NO	1.24	17	2	50	15,277.00	8,403		
	TOTAL	FOR MAP N	IO. 6							1.24		2	50	15,277.00	8,403		
				FROM SR 1814 (RED HILL RD) TO NC	•												
2023CPT.08.12.20632	Moore	7	SR-1823 / NICKENS RD	24/27	1	2	2WU	NO	NO	0.48	21	1	20	5,914.00	3,253		
	TOTAL	FOR MAP N	IO. 7							0.48		1	20	5,914.00	3,253		
				FROM NC 24/27 TO SR 1824													
2023CPT.08.12.20632	Moore	8	SR-1823 / DALRYMPLE RD	(EDMONDS RD/ DOBY RD)	1	2	2WU	NO	NO	1.32	20	4	75	21,120.00	11,616		
TOTAL FOR MAP NO. 8										1.32		4	75	21,120.00	11,616		
TOTAL FOR PROJ NO. 2023CPT.08.12.20632										14.13		26	560	169,338.00	93,121	8.00	10
GRAND TOTAL										14.13		26	560	169,338.00	93,121	8.00	10


PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.08.12.20632	7	
2023CF1.08.12.20032	,	

THERMOPLASTIC AND PAINT QUANTITIES

										4413000000-E	4457000000-N
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	WORK ZONE ADVANCE/GE NERAL WARNING	TEMPORARY TRAFFIC CONTROL
										SIGNING	
								MI	FT	SF	LS
2023CPT.08.12.20632	Moore	1	SR-1493 / CRABTREE RD	FROM NC 22 TO NC 24	1	2	2WU	2.16	20	245	
	TOTAL	FOR MAP	NO. 1					2.16		245	
				FROM NC 705 TO SR 1405 (DOVER							
2023CPT.08.12.20632	Moore	2	SR-1428 / DAN RD	CHURCH RD)	1	2	2WU	4.09	20	459	
	TOTAL	FOR MAP	NO. 2					4.09		459	
				FROM NC 705 TO SR 1411 (MT ZIONS							
2023CPT.08.12.20632	Moore	3	SR-1410 / ADAMS RD	CHURCH RD)	1	2	2WU	2.02	19.5	227	
	TOTAL	FOR MAP	NO. 3					2.02		227	
				FROM SR1487 (BORDEN RD) TO SR							
2023CPT.08.12.20632	Moore	4	SR-1489 / COCKMAN RD	1477 (PLANK RD)	1	2	2WU	0.66	20	74	
	TOTAL	FOR MAP	NO. 4					0.66		74	
				FROM SR 1661 (STANTON HILL RD)							*
2023CPT.08.12.20632	Moore	5	SR-1663 / LAMMS GROVE RD	TO 15-501	1	2	2WU	2.16	18	242	
	TOTAL	FOR MAP	NO. 5					2.16		242	
		FROM SR 1138 (EAGLE SPRINGS RD)									
				TO PVMT JOINT AT SR1140 (MARTIN							
2023CPT.08.12.20632	Moore	6	SR-1139 / EAGLE BRANCH RD	RD)	1	2	2WU	1.24	17	139	
	TOTAL	FOR MAP	NO. 6					1.24		139	
				FROM SR 1814 (RED HILL RD) TO NC							
2023CPT.08.12.20632	Moore	7	SR-1823 / NICKENS RD	24/27	1	2	2WU	0.48	21	54	
	TOTAL	FOR MAP	NO. 7					0.48		54	
				FROM NC 24/27 TO SR 1824							
2023CPT.08.12.20632	<u> </u>	8	SR-1823 / DALRYMPLE RD	(EDMONDS RD/ DOBY RD)	1	2	2WU	1.32	20	202	
TOTAL FOR MAP NO. 8								1.32		202	
TOTAL FOR PROJ NO. 2023CPT.08.12.20632								14.13		1,642	1.000
	L							4442		1.512	4 000
	GR	AND TOTA	L					14.13		1,642	1.000

PROJ. REFERENCE NO. SHEET NO. 2023CPT.08.12.20632

SIGNING FOR ASPHALT SURFACE TREATMENT



MAINLINE (-L-) SIGNING

-Y- LINE SIGNING

STATIONARY SIGNING NOT REQUIRED FOR ROAD - PLACE 1000' PRIOR TO BEGINNING OF CONSTRUCTION LIMITS. ONLY USED ON -Y-WORK THE FOLLOWING -Y- LINE CONDITIONS: LINES IF RESURFACING LIMITS EXTEND 1000' ALONG -Y- LINE. AHEAD / W20-1 48" X 48" 1) LESS THAN 1000' OF RESURFACING ALONG -Y- LINE - SIGN #2 ONLY USED WHEN RESURFACING LIMITS ARE 2 OR MORE MILES IN LENGTH 2 2) SUBDIVISION ROADS ROUND UP TO THE NEAREST WHOLE NUMBER. DO NOT USE FRACTIONAL OR DECIMAL 3) DEAD END ROADS TES AND DIRECTION WHEN PAVING/CONSTRUCTION ACTIVITIES PROCEED ACROSS LOOSE - ALTERNATE THE FOLLOWING TWO SIGNS: (3) AN UNSIGNED -Y- LINE, PORTABLE ADVANCE WARNING SIGNS GRAVEL SHALLE BE USED ALONG THE -Y- LINE AS SHOWN BELOW. - STARTING WITH "LOOSE GRAVEL" (W8-7) FOLLOWED BY "UNMARKED PAVEMENT". W8-7 48" X 48" REMOVE UPON COMPLETION OF WORK. - PLACE INITIALLY AT THE CONSTRUCTION LIMITS AND SPACED 1 MILE APART THEREAFTER. NOT ER UNMARKED - AT TEE INTERSECTIONS INSTALL INITIALLY 0.5 MILE FROM INTERSECTION ROAD PAVEMENT AND SPACE 1 MILE APART THEREAFTER. WORK ŚP 48'' X 48'' Д AHFAD SIGNING PLACEMENT F - THESE ARE FOR -Y- LINES THAT ARE "THROUGH" ROADWAYS. DEAD END AND PLACED 500' IN ADVANCE PLACED 250' IN ADVANCE SUBDIVISION ROADS ARE NOT "THROUGH" ROADWAYS. OF FLAGGER. OF FLAGGER. ROAD - INSTALL 500' +/- FROM EACH -Y- LINE APPROACH AS SHOWN ABOVE. UNDER - FOR MULTIPLE -Y- LINES THAT ARE SEPARATED BY 0.25 MILES OR LESS. TREAT CONST SP 13106 AS A SINGLE UNIT AND INSTALL WITHIN 500' OF EACH APPROACH. - A MAXIMUM OF 2 SIGN SETS PER MILE. DO NOT INSTALL WHEN -Y- LINES ARE WITHIN 0.5 MILES FROM "END ROAD WORK" SIGN. FND



ADVANCE WARNING SIGNS FOR 2-LANE ROADWAY ASPHALT SURFACE TREATMENT

TEE INTERSECTION

MAPS LESS THAN 2 MILES ROAD WORK

G20–2 A 48" X 24"

START OF CONTRACT WORK.

FOR AST RESURFACING MAPS WITH CONSTRUCTION LIMITS LESS THAN 2 MILES IN LENGTH, USE A STATIONARY "LOOSE GRAVEL" SIGN AT THE BEGINNING CONSTRUCTION LIMIT FOLLOWED BY AN "UNMARKED PAVEMENT" SIGN MIDWAY THROUGH AND AN "END ROAD WORK" SIGN AT THE END CONSTRUCTION LIMIT.

WHEN WORK ENDS AT A 3-WAY TEE INTERSECTION.

THE ABOVE SIGNS ARE ALL THAT ARE REQUIRED FOR A CONTRACTOR TO BEGIN A RESURFACING CONTRACT. ANY ADDITIONAL SIGNS REQUESTED BY NCDOT DIVISIONS SHALL BE INSTALLED WITHIN 7 BUSINESS DAYS OF THE

PLACE 500' FOLLOWING THE END OF CONSTRUCTION LIMITS OR AS SHOWN